

Summary of Quantities

ACF	ACNHPP
FAI 64	
RURAL	
90% FED., 10% STATE	
WHITE COUNTY	
CONST. CODE	0005 <i>004</i> 0014

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
X5030530	FLOOR DRAIN EXTENSION	EACH	218		218
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	98		98
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	8986		8986
Z0005880	BRIDGE HANDRAIL REMOVAL	FOOT	72	72	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	98		98
Z0015802	PLUG EXISTING DECK DRAINS	EACH	210		210
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	271		271
Z0034105	MATERIAL TRANSFER DEVICE	TON	37396	37396	
44213204	TIE BARS 3/4"	EACH	203	203	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	43232	43232	
40600300	AGGREGATE (PRIME COAT)	TON	720	720	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1608	1608	
40600990	TEMPORARY RAMP	SQ YD	248	248	
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, PG, N90	TON	22044	22044	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	15994	15352	642
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	116	116	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	181878	181878	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	1048	1048	
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	316	316	
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	507	507	
44213000	PATCHING REINFORCEMENT	SQ YD	1870	1870	
44213200	SAW CUTS	FOOT	8429	8429	

12

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cs:\p\work\p\dot\mccordr\100207031\7822\1\1\plan.dgn		DRAWN	REVISED			64	*	WHITE	54	5	
PLOT SCALE = 100,0000 1/2 in.		CHECKED	REVISED			CONTRACT NO. 78282					
PLOT DATE = 10/17/2013		DATE	REVISED			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	

(97-2-11RS-1); BSMART 2012-1.2.3