

**SHOULDER RESURFACING SCHEDULE - MAINLINE**

**WESTBOUND LANES**  
(SEE NOTE 1)

LOCATION STATION TO STATION	LENGTH (INFO ONLY)	HMA SURFACE REMOVAL - 2 1/4"	SHOULDERS				PRIME COAT		SHOULDER RUMBLE STRIP		NOTES		
			HOT-MIX ASPHALT		AGGREGATE		POLY. BIT. MAT' LS.	AGG.					
			10' OUTSIDE (RT.)	6' INSIDE (LT.)	2' WEDGE OUTSIDE	2' WEDGE INSIDE			GAL	TON		FOOT	FOOT
<b>FAI 64 ( I-64) WESTBOUND</b>			<b>FEET</b>	<b>SQ YD</b>	<b>TON</b>	<b>TON</b>	<b>TON</b>	<b>TON</b>	<b>GAL</b>	<b>TON</b>	<b>FOOT</b>	<b>FOOT</b>	
5455+88.00	TO	5456+18.00	30.0		3	2	1	1	5	0.1	30	30	
5456+18.00	TO	5493+65.00	3747.0		350	210	71	71	600	10.0	3747	3747	
5493+65.00	TO	5496+25.00	260.0	462	49	29	5	5	42	0.7	260	260	At Overpass
5496+25.00	TO	5512+48.00	1623.0		152	91	31	31	260	4.3	1623	1623	
SN 097-0039 - Sta. 5512+48 to Sta. 5519+36			NA										
Rt.	5519+36.00	TO	5624+67.00	10531.0		590		200	632	10.5		10531	
Lt.	5519+36.00	TO	5573+65.00	5429.0		507		103	543	9.0	5429		See Note 2
Lt.	5587+48.00	TO	5617+58.00	3010.0		281		57	301	5.0	3010		See Note 2
Lt.	5622+88.00	TO	5624+67.00	179.0		17		4	18	0.3	179		See Note 2
	5624+67.00	TO	5627+27.00	260.0	462	49	29	5	42	0.7	260	260	At Overpass
	5627+27.00	TO	5716+33.00	8906.0		831	499	169	1425	23.7	8906	8906	
	5716+33.00	TO	5718+93.00	260.0	462	49	29	5	42	0.7	260	260	At Overpass
	5718+93.00	TO	5763+58.00	4465.0		417	250	85	714	11.9	4465	4465	
SN 097-0051 - Sta. 5763+58 to Sta. 5764+72			NA										
	5764+72.00	TO	5800+02.00	3530.0		330	198	67	565	9.4	3530	3530	
	5800+02.00	TO	5800+32.00	30.0		3	2	1	5	0.1	30	30	
SN 097-0002 - Sta. 5827+88 to Sta. 5830+83			NA										
<b>WESTBOUND TOTALS</b>				<b>1,387</b>	<b>3038</b>	<b>1929</b>	<b>604</b>	<b>640</b>	<b>5,191</b>	<b>86</b>	<b>31,729</b>	<b>33,642</b>	

Note 1: For pay items related to structures, see sheets 27 to 51.  
 Note 2: Existing Weigh Station entrance and exit ramps at these locations.

**SUMMARY OF SHOULDER CALCULATIONS FOR FAI 64 MAINLINE AND RAMPS**

	HMA SURFACE REMOVAL - 2 1/4"	SHOULDERS				PRIME COAT		SHOULDER RUMBLE STRIP	
		HOT-MIX ASPHALT		AGGREGATE		POLY. BIT. MAT' LS.	AGG.		
		10' OUTSIDE (RT.)	6' INSIDE (LT.)	2' WEDGE OUTSIDE	2' WEDGE INSIDE			GAL	TON
	SQ YD	TON	TON	TON	TON	GAL	TON	FOOT	FOOT
FAI 64 EASTBOUND LANES	1387	3216	1929	639	639	5383	90	33642	33642
FAI 64 WESTBOUND LANES	1387	3038	1929	604	640	5191	86	31729	33642
<b>PROJECT TOTALS</b>	<b>2,774</b>	<b>10,112</b>		<b>2524</b>		<b>10,574</b>	<b>176</b>	<b>132,655</b>	

\*(97-2-1)RS-1; BSMART 2012-1,2,3