

SUMMARY OF QUANTITIES - CONT

FUNDING:	HSIP
	90% FED 10% STATE
LOCATION:	RURAL
ROUTE:	FAP 726 (IL 37)
TOTAL QUANTITY	ROADWAY 0004

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2	2
60221800	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 9 FRAME AND GRATE	EACH	2	2
60500060	REMOVING INLETS	EACH	2	2
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,702	1,702
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	75	75
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	2
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	2,673	2,673
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	32	32
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2500	2500
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
67100100	MOBILIZATION	L SUM	1	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8

⚠
⚠
⚠

* SPECIALTY ITEM

⚠ 12-27-13