

SEEDING SCHEDULE

LOCATION STA TO STA				SEEDING, CLASS 2	SEEDING, CLASS 7	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE
				ACRE	ACRE	TON	POUND	POUND	POUND	ACRE
LT	STA 513+00.	TO STA 514+09.35		0.06	0.06	0.12	7.8	5.4	5.4	0.12
LT	STA 514+09.35	TO STA 516+75.		0.05	0.05	0.10	6.5	4.5	4.5	0.10
LT	STA 516+75.	TO STA 520+95.3		0.35	0.35	0.70	45.5	31.5	31.5	0.70
LT	STA 520+95.3	TO STA 523+39.58		0.24	0.24	0.48	31.2	21.6	21.6	0.48
LT	STA 523+39.58	TO STA 526+68.17		0.17	0.17	0.34	22.1	15.3	15.3	0.34
LT	STA 526+68.17	TO STA 530+25.		0.22	0.22	0.44	28.6	19.8	19.8	0.44
RT	STA 513+00.	TO STA 513+81.25		0.06	0.06	0.12	7.8	5.4	5.4	0.12
RT	STA 513+81.25	TO STA 520+53.9		0.43	0.43	0.86	55.9	38.7	38.7	0.86
RT	STA 520+53.9	TO STA 530+25.		1.12	1.12	2.24	145.6	100.8	100.8	2.24
PROJECT TOTAL				2.7	2.7	5.4	351.0	243.0	243.0	5.4