

PAVEMENT MARKING SCHEDULE

LOCATION STA TO STA	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, - LINE 4"				SHORT TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT REMOVAL SQ FT	TEMPORARY PAVEMENT MARKING, - LINE 4"				RAISED REFLECTIVE PAVEMENT MARKER REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL SQ FT
	YELLOW		WHITE	- LINE 24" FOOT			YELLOW		WHITE	- LINE 24" FOOT		
	SOLID	SKIP DASH	SOLID				SOLID	SKIP DASH	SOLID			
	FOOT	FOOT	FOOT				FOOT	FOOT	FOOT			
	FOOT	FOOT	FOOT				FOOT	FOOT	FOOT			
STA 513+00.00 TO STA 518+00.00	500.0	130.0	1,000.0		104	17	500.0	130.0	1,000.0		6	13
STA 518+00.00 TO STA 521+00.00	600.0		600.0		64	11	600.0		600.0		4	8
STA 521+00.00 TO STA 530+25.00	925.0	230.0	1,850.0		184	31	925.0	230.0	1,850.0		12	23
STA 9+78.00 PULLEYS MILL RD											20.0	
STA 10+22.00 PULLEYS MILL RD											18.0	
SUB TOTALS	2,025.0	360.0	3,450.0	38.0			2,025.0	360.0	3,450.0	38.0		
PROJECT TOTALS	5,835.0			38.0	352	59	5,835.0			38.0	22	44

SIGN SCHEDULE

SIGN ID NO.	DESCRIPTION	SIGN SIZE	AREA PER SIGN SQ FT	TOTAL SIGNS REQUIRED	SIGN PANEL	
					TYPE 1 SQ FT	TYPE 2 SQ FT
M6-1	HORIZONTAL ARROW	21" X 15"	2.1875	8	17.5	
M6-2R	ANGLED ARROW	21" X 15"	2.1875	2	4.5	
M1-4	IL ROUTE 37	24" X 24"	4	12	48.0	
M4-8	DETOUR	24" X 12"	2	12	24.0	
R11-3A	ROAD CLOSED 1 MILES AHEAD LOCAL TRAFFIC ONLY	60" X 30"	12.5	1		12.5
R11-3A	ROAD CLOSED 3 MILES AHEAD LOCAL TRAFFIC ONLY	60" X 30"	12.5	1		12.5
W20-2	DETOUR AHEAD	36" X 36"	9.75	2		19.5
M1-1	INTERSTATE 57	24" X 24"	4	2	8.0	
	VIA	24" X 12"	2	2	4.0	
PROJECT TOTAL					106.0	44.5