FINAL SURVEY	NOTE BOOK	NO.
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		

BY	DATE

ORIGINAL SURVEY	NOTE BOOK	NO.
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		

BY	DATE

70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80

615 610 605 600 595

PROP. ROW

EXIST. ROW

4:1

5%

598.46

4.0%

1.5%

1.5%

4.0%

598.46

5%

4:1

EXIST. ROW

PROP. ROW

℄ IL 37

599.21

604.39

CUT = 408.7

FILL = 0

ROCK FILL = 0

517 + 25.00

615 610 605 600 595

PROP. ROW

EXIST. ROW

7.4%

CEL

598.85

4.0%

1.5%

1.5%

4.0%

598.85

5%

4:1

EXIST. ROW

PROP. ROW

℄ IL 37

599.60

604.40

CUT = 432.1

FILL = 0

ROCK FILL = 0

517 + 00.00

70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80

FILE NAME = c:\pw_work\pwidot\kranzjc\d0308025\78320-sht-sections.dgn	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 10.0000 ' / in.	CHECKED -	REVISED -
$MODELNAME$	PLOT DATE = 10/18/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS – IL 37

SCALE: | SHEET OF SHEETS | STA. 517+00.00 | TO STA. 517+25.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	D9 SAFETY 2013-1	WILLIAMSON	112	64
		CONTRACT NO. 78320		
		ILLINOIS FED. AID PROJECT		