

TREE REMOVAL (6 TO 15 UNITS DIAMETER)			
LOCATION	LT / RT	OFFSET	20100110
		FT	UNIT
IL 91 Main Line			
STA. 106 + 21.37	RT	46.12	13.00
STA. 108 + 54.39	RT	88.80	11.00
STA. 108 + 54.76	RT	84.44	12.00
STA. 110 + 22.48	LT	41.48	12.00
STA. 117 + 28.47	LT	47.81	12.00
STA. 117 + 43.49	LT	47.44	12.00
STA. 117 + 72.46	RT	50.86	12.00
STA. 138 + 90.03	LT	36.59	7.00
STA. 139 + 07.70	LT	43.80	6.00
Legion Hall Road (East)			
STA. 010 + 98.05	RT	42.41	14.00
STA. 011 + 04.66	LT	47.17	10.00
STA. 011 + 10.22	LT	43.11	8.00
STA. 011 + 13.98	RT	43.28	14.00
STA. 012 + 12.10	LT	39.13	12.00
STA. 014 + 91.36	RT	35.71	7.00
STA. 016 + 00.00	RT	38.52	8.00
TOTAL			170.0

TREE REMOVAL (OVER 15 UNITS DIAMETER)			
LOCATION	LT / RT	OFFSET	20100210
		FT	UNIT
IL 91 Main Line			
STA. 104 + 91.75	RT	45.47	30.00
STA. 105 + 21.85	RT	44.46	16.00
STA. 106 + 30.49	RT	63.63	18.00
STA. 107 + 35.52	RT	73.21	17.00
STA. 107 + 55.01	RT	50.77	20.00
STA. 107 + 62.26	RT	61.16	22.00
STA. 107 + 84.22	RT	55.05	15.00
STA. 108 + 06.20	RT	48.48	24.00
STA. 108 + 55.76	RT	69.99	17.00
STA. 113 + 35.11	RT	48.99	42.00
STA. 116 + 06.94	RT	48.00	17.00
STA. 116 + 51.31	RT	49.33	19.00
STA. 117 + 09.86	RT	50.26	24.00
STA. 117 + 29.43	RT	50.15	15.00
STA. 117 + 47.46	RT	50.54	19.00
STA. 117 + 60.46	RT	50.71	19.00

TREE REMOVAL (OVER 15 UNITS DIAMETER)(Cont.)			
LOCATION	LT / RT	OFFSET	20100210
		FT	UNIT
IL 91 Main Line			
STA. 117 + 81.46	RT	50.98	15.00
STA. 120 + 60.50	RT	46.34	24.00
STA. 121 + 70.40	RT	40.06	18.00
STA. 124 + 77.12	RT	39.92	36.00
STA. 126 + 49.35	LT	23.31	19.00
STA. 126 + 70.46	LT	23.75	40.00
STA. 126 + 93.70	LT	22.95	18.00
STA. 135 + 68.71	RT	39.50	34.00
STA. 136 + 18.97	RT	36.79	36.00
STA. 136 + 45.34	LT	31.34	18.00
STA. 137 + 26.83	LT	38.98	28.00
STA. 137 + 38.48	LT	35.18	15.00
STA. 138 + 57.15	LT	36.38	29.00
STA. 140 + 15.13	RT	38.05	46.00
Legion Hall Road (East)			
STA. 010 + 85.05	LT	50.10	21.00
STA. 010 + 91.94	LT	47.79	19.00
STA. 011 + 42.21	LT	38.73	17.00
STA. 011 + 80.82	LT	40.22	17.00
STA. 012 + 20.44	LT	38.74	16.00
STA. 012 + 30.83	LT	37.16	30.00
STA. 012 + 45.31	RT	45.24	20.00
STA. 012 + 59.71	LT	41.63	30.00
STA. 012 + 88.50	RT	51.79	15.00
STA. 013 + 15.72	RT	52.22	15.00
STA. 013 + 15.82	RT	39.93	16.00
STA. 013 + 29.62	RT	40.42	16.00
STA. 013 + 46.87	LT	45.69	30.00
STA. 013 + 56.37	RT	45.46	16.00
STA. 013 + 69.30	RT	44.41	18.00
STA. 013 + 98.57	LT	46.41	31.00
STA. 014 + 31.80	LT	50.10	32.00
STA. 014 + 31.80	LT	50.10	33.00
TOTAL			1,102

TREE REMOVAL, ACRES					
LOCATION			LT / RT	AREA	20100500
				SQ FT	ACRE
STA. 147 + 44.66	TO	STA. 147 + 99.13	LT	1,030.15	0.024
STA. 148 + 23.00	TO	STA. 148 + 79.60	LT	1,812.90	0.042
TOTAL					0.1

EARTHWORK SCHEDULE (PRE-STAGE)						
LOCATION	20200100		EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
	EARTH EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE				
	CU YD	CU YD				
W. ASH ST (Detention Pond)						
STA. 000 + 00.00	TO	STA. 007 + 00.00	3511.5	2,633.6	0.00	2,633.6
TOTALS			3,511	2,634	0	2,634

EARTHWORK SCHEDULE (STAGE 1A)						
LOCATION	20200100		EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
	EARTH EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE				
	CU YD	CU YD				
IL 91 Main Line (PRE-STAGE 1A)						
STA. 103 + 75.00	TO	STA. 110 + 25.00	61.1	45.8	66.60	-20.8
STA. 142 + 50.00	TO	STA. 150 + 50.00	657.0	492.8	1,335.00	-842.3
TOTALS			718	539	1,402	-863