

SEEDING SCHEDULE														
LOCATION	LT/RT	PLAN AREA	21101615	25000210	25000400		25000500		25000600		25100115	25200110	28000250	
			TOPSOIL FURNISH & PLACE 4"	SEEDING CLASS 2A	NITROGEN (90 LB/ACRE)	NITROGEN (60 LB/ACRE)	PHOSPHORUS (90 LB/ACRE)	PHOSPHORUS (60 LB/ACRE)	POTASSIUM (90 LB/ACRE)	POTASSIUM (60 LB/ACRE)	MULCH, METHOD 2	SODDING SALT TOLERANT	* TEMPORARY EROSION CONTROL SEEDING (100 LB/ACRE)	
			SQ FT	SQ YD	ACRE	POUND	POUND	POUND	POUND	POUND	POUND	ACRE	SQ YD	POUND
Main Line (IL-91)														
STA. 099 + 00.00	TO	STA. 104 + 27.00	LT	13,889.77	1,543.31	0.3189	28.70		28.70		28.70		0.3189	63.77
STA. 099 + 00.00	TO	STA. 104 + 34.52	RT	15,107.87	1,678.65	0.3468	31.21		31.21		31.21		0.3468	69.37
STA. 104 + 62.00	TO	STA. 106 + 25.67	LT	1,667.72	185.30		2.30		2.30		2.30		0.0383	185.30
STA. 104 + 35.32	TO	STA. 106 + 21.79	RT	5,832.56	648.06		8.03		8.03		8.03		0.1339	648.06
STA. 107 + 16.32	TO	STA. 112 + 85.97	LT	9,967.55	1,107.51		13.73		13.73		13.73		0.2288	1107.51
STA. 106 + 99.50	TO	STA. 109 + 85.57	RT	10,942.11	1,215.79		15.07		15.07		15.07		0.2512	1215.79
STA. 110 + 72.16	TO	STA. 113 + 15.15	RT	5,972.11	663.57		8.23		8.23		8.23		0.1371	663.57
STA. 114 + 00.00	TO	STA. 116 + 42.00	RT	5,525.48	613.94		7.61		7.61		7.61		0.1268	613.94
STA. 114 + 73.00	TO	STA. 120 + 09.33	LT	5,359.58	595.51		7.38		7.38		7.38		0.1230	595.51
STA. 117 + 35.00	TO	STA. 120 + 05.00	RT	5,192.31	576.92		7.15		7.15		7.15		0.1192	576.92
STA. 120 + 62.00	TO	STA. 124 + 22.80	LT	2,771.80	307.98		3.82		3.82		3.82		0.0636	307.98
STA. 120 + 62.00	TO	STA. 124 + 17.17	RT	2,043.05	227.01		2.81		2.81		2.81		0.0469	227.01
STA. 124 + 78.00	TO	STA. 128 + 49.00	LT	3,707.84	411.98		5.11		5.11		5.11		0.0851	411.98
STA. 124 + 78.00	TO	STA. 128 + 26.43	RT	2,435.57	270.62		3.35		3.35		3.35		0.0559	270.62
STA. 129 + 00.00	TO	STA. 147 + 63.32	LT	9,725.63	1,080.63		13.40		13.40		13.40		0.2233	1080.63
STA. 129 + 00.00	TO	STA. 132 + 57.00	RT	1,863.07	207.01		2.57		2.57		2.57		0.0428	207.01
STA. 133 + 15.00	TO	STA. 136 + 76.72	RT	5,376.33	597.37		7.41		7.41		7.41		0.1234	597.37
STA. 137 + 35.61	TO	STA. 140 + 86.00	RT	2,298.44	255.38		3.17		3.17		3.17		0.0528	255.38
STA. 132 + 48.56	TO	STA. 136 + 94.15	LT	10,679.50	1,186.61	0.2452	22.07		22.07		22.07		0.2452	49.03
STA. 139 + 00.00	TO	STA. 150 + 59.78	LT	36,483.16	4,053.68	0.8375	75.38		75.38		75.38		0.8375	167.51
STA. 146 + 00.00	TO	STA. 149 + 58.00	RT	6,770.03	752.23	0.1554	13.99		13.99		13.99		0.1554	31.08
STA. 141 + 50.00	TO	STA. 146 + 00.00	RT	8,794.18	977.13		12.11		12.11		12.11		0.2019	977.13
W. Legion Hall Rd														
STA. 002 + 53.72	TO	STA. 009 + 48.00	LT	10,154.69	1,128.30		13.99		13.99		13.99		0.2331	1128.30
STA. 002 + 85.22	TO	STA. 009 + 51.23	RT	2,733.22	303.69		3.76		3.76		3.76		0.0627	303.69
E. Legion Hall Rd														
STA. 010 + 64.00	TO	STA. 020 + 06.34	LT	16,932.61	1,881.40		23.32		23.32		23.32		0.3887	1881.40
STA. 010 + 64.00	TO	STA. 017 + 10.00	RT	8,173.02	908.11		11.26		11.26		11.26		0.1876	908.11
STA. 014 + 84.70	TO	STA. 018 + 30.00	RT	6,256.10	695.12	0.1436	12.93	0.00	12.93	0.00	12.93	0.00	0.1436	28.72
S. Castle Dr														
STA. 010 + 31.50	TO	STA. 010 + 75.00	LT	412.92	45.88		0.57		0.57		0.57		0.0095	45.88
STA. 010 + 31.50	TO	STA. 011 + 00.00	RT	656.38	72.93		0.90		0.90		0.90		0.0151	72.93
N. Castle Dr														
STA. 010 + 30.00	TO	STA. 010 + 55.72	LT	281.12	31.24		0.39		0.39		0.39		0.0065	31.24
STA. 010 + 33.00	TO	STA. 010 + 98.00	RT	790.41	87.82		1.09		1.09		1.09		0.0181	87.82