

EPOXY PAVEMENT MARKING - LINE 8"						
LOCATION			LENGTH	78005140		
				WHITE SOLID LINE	WHITE SKIP DASH LINE	
			FT	FT	FT	
Main Line (IL-91)						
STA. 102+78.50	TO	STA. 104+33.57	155			39
STA. 104+33.57	TO	STA. 106+04.23	171	171		
Legion Hall Intersection						
STA. 106+04.80	TO	STA. 106+76.00	89	LT TURN FROM IL 91 TO LEGIN HALL W.		22
STA. 106+04.80	TO	STA. 106+61.00	94	LT TURN FROM E. LEGIN HALL TO IL 91 S.		24
STA. 106+77.00	TO	STA. 107+31.21	82	LT TURN FROM W. LEGIN HALL TO IL 91 N.		21
STA. 106+62.14	TO	STA. 107+31.21	93	LT TURN FROM IL 91 TO LEGIN HALL E.		23
Crossing Legin Hall						
		STA. 009+60.22	89		89	
		STA. 009+67.65	100		100	
		STA. 010+42.71	96		96	
		STA. 010+50.71	83		83	
		STA. 016+53.28	30		30	
		STA. 016+59.28	29		29	
Crossing IL-91						
		STA. 106+09.80	73		73	
		STA. 106+17.80	75		75	
		STA. 107+18.13	72		72	
		STA. 107+26.13	67		67	
		STA. 147+44.40	46		46	
		STA. 147+58.87	46		46	
SUB - TOTAL				977		128
<b>TOTAL</b>				<b>1,105</b>		

EPOXY PAVEMENT MARKING - LINE 4"							
LOCATION			LENGTH	78005110			
				WHITE SOLID LINE	YELLOW SKIP DASH LINE	YELLOW SOLID LINE	DOUBLE YELLOW LINE
			FT	FT	FT	FT	FT
Main Line (IL-91)							
STA. 099+21.00	TO	STA. 099+66.00	45	45			
STA. 099+21.00	TO	STA. 099+51.00	30	30			
STA. 099+21.00	TO	STA. 099+90.00	69				138
STA. 099+90.00	TO	STA. 102+84.00	294				1,176
STA. 102+84.00	TO	STA. 104+01.00	117				468
STA. 104+01.00	TO	STA. 106+05.00	204				408
STA. 104+01.00	TO	STA. 106+05.00	204	415			
STA. 107+31.00	TO	STA. 108+58.50	128	262			
STA. 107+31.00	TO	STA. 109+46.50	216				431
STA. 107+33.00	TO	STA. 108+87.00	154	154			
STA. 107+32.00	TO	STA. 112+86.00	554	554			
STA. 109+46.50	TO	STA. 110+15.00	69		40	137	
STA. 110+68.00	TO	STA. 112+86.00	218		120	436	
STA. 110+68.00	TO	STA. 113+11.00	243	243			
STA. 113+72.00	TO	STA. 120+00.00	628	628			
STA. 114+00.00	TO	STA. 116+57.00	257		140	514	
STA. 114+03.00	TO	STA. 116+42.00	239	239			
STA. 117+20.00	TO	STA. 120+00.00	280		140	560	
STA. 117+28.00	TO	STA. 120+00.00	272	272			
STA. 120+71.00	TO	STA. 124+29.00	358	716	180	716	
STA. 124+78.00	TO	STA. 128+48.00	370	370	200	740	
STA. 124+78.00	TO	STA. 128+35.00	357	357			
STA. 128+99.00	TO	STA. 145+10.00	1,611	1,611			
STA. 128+99.00	TO	STA. 132+61.00	362		190	724	
STA. 128+99.00	TO	STA. 132+46.00	347	347			
STA. 133+11.00	TO	STA. 136+80.00	369		200	738	
STA. 133+19.00	TO	STA. 136+74.00	355	355			
STA. 137+32.00	TO	STA. 140+89.00	357		180	714	
STA. 137+39.00	TO	STA. 140+86.00	347	347			
STA. 141+50.00	TO	STA. 145+10.00	360	360	180	720	
STA. 145+10.00	TO	STA. 146+90.00	180	360			720
STA. 146+90.00	TO	STA. 147+57.00	67	67			
STA. 146+90.00	TO	STA. 147+45.00	55				110
STA. 146+90.00	TO	STA. 147+32.00	42	42			
STA. 147+71.00	TO	STA. 149+88.00	217	217			
STA. 147+59.00	TO	STA. 149+88.00	229				458
STA. 147+46.00	TO	STA. 149+88.00	242	242			
Legion Hall Rd (West)							
STA. 002+47.00	TO	STA. 004+63.00	216				432
STA. 005+65.00	TO	STA. 008+10.00	245				985
STA. 008+10.00	TO	STA. 009+52.00	142	291			284
Legion Hall Rd (East)							
STA. 010+55.00	TO	STA. 011+88.00	133	273			266
STA. 011+90.00	TO	STA. 016+91.58	502				2,394
STA. 017+66.68	TO	STA. 020+32.00	265				531
SUB - TOTAL				8,795	1,570	5,999	8,801
<b>TOTAL</b>				<b>25,165</b>			

EPOXY PAVEMENT MARKING - LETTERS & SYMBOLS						
LOCATION			78005100			
			LEFT TURN ARROW	TWO WAY LEFT TURN ARROWS	RIGHT TURN ARROW	THROUGH ARROW
			SQFT	SQFT	SQFT	SQFT
Main Line (IL-91)						
STA. 105+06.25	TO	STA. 106+04.80	26.4		26.4	
STA. 107+40.00	TO	STA. 110+14.88	26.4			26
STA. 110+68.00	TO	STA. 113+11.00		52.8		26
STA. 113+71.75	TO	STA. 116+56.89		52.8		26
STA. 117+20.65	TO	STA. 120+00.00		52.8		26
STA. 120+71.00	TO	STA. 124+28.62		52.8		26
STA. 124+78.00	TO	STA. 128+48.36		52.8		26
STA. 128+99.00	TO	STA. 132+60.78		52.8		26
STA. 133+11.44	TO	STA. 136+80.27		52.8		26
STA. 137+32.00	TO	STA. 140+88.73		52.8		26
STA. 141+50.35	TO	STA. 149+57.82		52.8		52
Legion Hall Rd						
STA. 008+10.00	TO	STA. 009+51.65	26.4			
STA. 010+57.34	TO	STA. 011+90.00	26.4			
SUB - TOTAL			106	476	27	286
<b>TOTAL</b>			<b>1,243</b>			