

EPOXY PAVEMENT MARKING - LINE 12"						
LOCATION			LENGTH	78005150		
				WHITE SOLID LINE	DIAGONAL LINES	CHEVRONS
			FT	FT	FT	FT
Main Line (IL-91)						
STA. 099 + 90.00	TO	STA. 104 + 01.21	411		196	
STA. 104 + 01.21	TO	STA. 106 + 04.35	203			114
STA. 107 + 31.80	TO	STA. 108 + 58.50	127			74
Crossing IL-91						
STA. 147 + 52.34				145		
Legion Hall Rd						
STA. 008 + 10.00	TO	STA. 009 + 51.65	142			80
STA. 010 + 55.71	TO	STA. 011 + 90.00	134			80
Legin Hall Crossing (East)						
STA. 016 + 56.00				54		
SUB - TOTAL				199	196	348
TOTAL				743		

EPOXY PAVEMENT MARKING - LINE 24"			
LOCATION		LENGTH	STOP BAR WHITE SOLID LINE
			78005180
		FT	FT
Crossing IL-91			
STA. 106 + 04.32		43	43
STA. 107 + 31.87		34	34
Crossing Legion Hall Rd			
STA. 009 + 51.20		36	36
STA. 010 + 55.71		36	36
TOTAL			149

PAVEMENT MARKING REMOVAL							
LOCATION			LENGTH	78300100			
				DOUBLE YELLOW LINE REMOVAL 4"	YELLOW SOLD REMOVAL 4"	YELLOW SKIP DASH REMOVAL 4"	WHITE SOLID LINE REMOVAL 4"(LEFT)
STA.	TO	STA.	FT	SQ FT	SQ FT	SQ FT	SQ FT
STAGE 2-IL 91 (EXISTING PAV. MAK. ON CL & LEFT SIDE ONLY)							
STA. 099 + 21.00	TO	STA. 140 + 30.00	4109.00			1027.25	4109.00
STA. 140 + 30.00	TO	STA. 147 + 25.00	695.00		695.00	173.75	695.00
STA. 147 + 25.00	TO	STA. 148 + 30.00	105.00	210.00			105.00
STA. 148 + 30.00	TO	STA. 149 + 88.00	158.00		158.00	39.50	158.00
SUB-TOTAL				210.00	853.00	1240.50	5067.00
TOTAL				7,371			

RAISED REFLECTIVE PAVEMENT MARKERS						
LOCATION			78100100			
			ONE WAY AMBER MARKER	ONE WAY CRYSTAL MARKER	TWO WAY AMBER MARKER	
STA.	TO	STA.	EACH	EACH	EACH	
IL 91						
STA. 099 + 21.00	TO	STA. 011 + 06.00			4	
STA. 011 + 06.00	TO	STA. 104 + 01.00	20			
STA. 104 + 01.00	TO	STA. 106 + 04.81		11	12	
STA. 107 + 31.00	TO	STA. 110 + 15.00		4	16	
STA. 110 + 68.00	TO	STA. 112 + 86.00			10	
STA. 114 + 00.00	TO	STA. 116 + 57.00			12	
STA. 117 + 20.54	TO	STA. 120 + 00.00			14	
STA. 120 + 71.00	TO	STA. 124 + 28.62			18	
STA. 124 + 78.00	TO	STA. 128 + 48.00			18	
STA. 129 + 00.00	TO	STA. 132 + 61.00			18	
STA. 133 + 11.44	TO	STA. 136 + 80.00			18	
STA. 137 + 32.00	TO	STA. 140 + 88.73			18	
STA. 141 + 50.35	TO	STA. 145 + 10.00			18	
STA. 145 + 10.00	TO	STA. 149 + 88.00	8		10	
Legin Hall (east)						
STA. 002 + 47.00	TO	STA. 004 + 63.00	6		6	
STA. 005 + 65.00	TO	STA. 009 + 51.65	14	4	8	
Legin Hall (west)						
STA. 010 + 55.71	TO	STA. 016 + 91.58	26	4	8	
STA. 017 + 66.67	TO	STA. 020 + 32.00			8	
SUBTOTAL			74	23	216	
TOTAL			313			

PCC SIDEWALK 4 INCH, SPECIAL						
LOCATION			LT/RT	WIDTH	X4240420	
					STATE 100%	STATE/CITY 80% / 20%
				FT	SQ FT	SQ FT
Main Line (IL 91)						
STA. 113 + 44.33	TO	STA. 114 + 24.96	LT	8		752.51
STA. 115 + 62.40	TO	STA. 116 + 64.69	LT	5		447.42
STA. 120 + 55.26	TO	STA. 121 + 68.97	LT	5	651.06	
STA. 122 + 02.25	TO	STA. 122 + 17.05	LT	5	83.11	
STA. 122 + 46.80	TO	STA. 123 + 17.14	LT	5	392.47	
STA. 123 + 45.56	TO	STA. 124 + 07.49	LT	5	345.67	
STA. 123 + 72.62	TO	STA. 124 + 30.75	RT	5	267.47	
STA. 129 + 17.42	TO	STA. 129 + 44.60	LT	5		151.71
STA. 129 + 85.09	TO	STA. 129 + 96.20	LT	5	62.02	
STA. 130 + 24.70	TO	STA. 130 + 44.23	LT	5	144.04	
STA. 130 + 72.72	TO	STA. 132 + 26.87	LT	5	885.44	
STA. 132 + 55.37	TO	STA. 132 + 75.01	LT	5		110.43
STA. 137 + 49.59	TO	STA. 138 + 32.01	RT	5		467.49
TOTAL					2831	1930
GRAND TOTAL					4761	

PCC SIDEWALK 6 INCH, SPECIAL			
LOCATION		LT/RT	X4240440
			SQ FT
Main Line (IL 91)			
STA. 121 + 72.22		LT	1.25
STA. 122 + 00.00		LT	1.25
STA. 122 + 44.57		LT	1.25
STA. 123 + 43.31		LT	1.25
STA. 129 + 46.86		LT	1.25
STA. 129 + 98.46		LT	1.25
STA. 130 + 46.49		LT	1.25
STA. 132 + 29.32		LT	1.25
TOTAL			10.00