#### **BID PROPOSAL INSTRUCTIONS**

**ABOUT IDOT PROPOSALS:** All proposals are potential bidding proposals. Each proposal contains all certifications and affidavits, a proposal signature sheet and a proposal bid bond.

#### **PREQUALIFICATION**

Any contractor who desires to become pre-qualified to bid on work advertised by IDOT must submit the properly completed pre-qualification forms to the Bureau of Construction no later than 4:30 p.m. prevailing time twenty-one days prior to the letting of interest. This pre-qualification requirement applies to first time contractors, contractors renewing expired ratings, contractors maintaining continuous pre-qualification or contractors requesting revised ratings. To be eligible to bid, existing pre-qualification ratings must be effective through the date of letting.

#### WHO CAN BID?

Bids will be accepted from only those companies that request and receive written Authorization to Bid from IDOT's Central Bureau of Construction.

#### **REQUESTS FOR AUTHORIZATION TO BID**

Contractors wanting to bid on items included in a particular letting must submit the properly completed "Request for Authorization to Bid/or Not For Bid Status" (BDE 124) and the ORIGINAL "Affidavit of Availability" (BC 57) to the proper office no later than 4:30 p.m. prevailing time, three (3) days prior to the letting date.

#### WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?

When a prospective prime bidder submits a "Request for Authorization to Bid/or Not For Bid Status" (BDE 124) he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued an **Authorization to Bid or Not for Bid Report**, approved by the Central Bureau of Construction and the Chief Procurement Officer that indicates which items have been approved For Bidding. If **Authorization to Bid** cannot be approved, the **Authorization to Bid or Not for Bid Report** will indicate the reason for denial.

#### **ABOUT AUTHORIZATION TO BID**

Firms that have not received an Authorization to Bid or Not For Bid Report within a reasonable time of complete and correct original document submittal should contact the Department as to the status. Firms unsure as to authorization status should call the Prequalification Section of the Bureau of Construction at the number listed at the end of these instructions.

#### ADDENDA AND REVISIONS

It is the bidder's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum or revision will be included with the Electronic Plans and Proposals. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription service emails are an added courtesy the Department provides. It is suggested that bidders check IDOT's website at <a href="http://www.dot.il.gov/desenv/delett.html">http://www.dot.il.gov/desenv/delett.html</a> before submitting final bid information.

#### IDOT IS NOT RESPONSIBLE FOR ANY E-MAIL FAILURES.

Addenda questions may be directed to the Contracts Office at (217)782-7806 or <a href="mailto:DOT.D&Econtracts@illlinois.gov">DOT.D&Econtracts@illlinois.gov</a>

Technical questions about downloading these files may be directed to Tim Garman at (217)524-1642 or <a href="mailto:Timothy.Garman@illinois.gov">Timothy.Garman@illinois.gov</a>.

#### STANDARD GUIDELINES FOR SUBMITTING BIDS

- All pages should be single sided.
- Use the Cover Page that is provided in the Bid Proposal (posted on the IDOT Web Site) as the first page of your submitted bid. It has the item number in large bold type in the upper left-hand corner and lines provided for your company name and address in the upper right-hand corner.
- Do not use report covers, presentation folders or special bindings and do not staple multiple times on left side like a book. Use only 1 staple in the upper left hand corner. Make suer all elements of your bid are stapled together including the bid bond or guaranty check (if required).
- Do not include any certificates of eligibility, your authorization to bid, Addendum Letters or affidavit of availability.
- Do not include the Subcontractor Documentation with your bid (pages i iii and pages a g). This documentation is required only if you are awarded the project.
- Use the envelope cover sheet (provided with the proposal) as the cover for the proposal envelope.
- Do not rely on overnight services to deliver your proposal prior to 10 AM on letting day. It will not be read if it is delivered after 10 AM.
- Do not submit your Substance Abuse Prevention Program (SAPP) with your bid. If you are awarded the contract this form is to be submitted to the district engineer at the pre-construction conference.

#### **BID SUBMITTAL CHECKLIST**

Cover page (the sheet that has the item number on it) – This should be the first page of your bid proposal, followed by your bid (the Schedule of Prices/Pay Items). If you are using special software or CBID to generate your schedule of prices, do not include the blank pages of the schedule of prices that came with the proposal package.
☐ Page 4 (Item 9) — Check "YES" if you will use a subcontractor(s) with an annual value over \$50,000. Include the subcontractor(s) name, address, general type of work to be performed and the dollar amount. If you will use subcontractor(s) but are uncertain who or the dollar amount; check "YES" but leave the lines blank.
After page 4 – Insert the following documents: The Illinois Office Affidavit (Not applicable to federally funded projects) followed by Cost Adjustments for Steel, Bituminous and Fuel (if applicable) and the Contractor Letter of Assent (if applicable). The general rule should be, if you don't know where it goes, put it after page 4.
☐ Page 10 (Paragraph J) – Check "YES" or "NO" whether your company has any business in Iran.
☐ Page 10 (Paragraph K) — (Not applicable to federally funded projects) List the name of the apprenticeship and training program sponsor holding the certificate of registration from the US Department of Labor. If no applicable program exists, please indicate the work/job category Your bid will not be read if this is not completed. Do not include certificates with your bid. Keep the certificates in your office in case they are requested by IDOT.
☐ Page 11 (Paragraph L) – A copy of your State Board of Elections certificate of registration is no longer required with your bid.
☐ Page 11 (Paragraph M) – Indicate if your company has hired a lobbyist in connection with the job for which you are submitting the bid proposal.
☐ Page 12 (Paragraph C) – This is a work sheet to determine if a completed Form A is required. It is not part of the form and you do not need to make copies for each completed Form A.
Pages 14-17 (Form A) – One Form A (4 pages) is required for each applicable person in your company. Copies of the forms can be used and only need to be changed when the information changes. The certification signature and date must be original for each letting. Do not staple the forms together. If you answered "NO" to all of the questions in Paragraph C (page 12), complete the first section (page 14) with your company information and then sign and date the Not Applicable statement on page 17.
Page 18 (Form B) - If you check "YES" to having other current or pending contracts it is acceptable to use the phrase, "See Affidavit of Availability on file". Ownership Certification (at the bottom of the page) - Check N/A if the Form A(s) you submitted accounts for 100 percent of the company ownership. Check YES if any percentage of ownership falls outside of the parameters that require reporting on the Form A. Checking NO indicates that the Form A(s) you submitted is not correct and you will be required to submit a revised Form A.
☐ <b>Page 20 (Workforce Projection)</b> – Be sure to include the Duration of the Project. It is acceptable to use the phrase "Per Contract Specifications".

☐ <b>Proposal Bid Bond</b> – (Insert after the proposal signature page) Submit you using the current Proposal Bid Bond form provided in the proposal package. the Proposal Bid Bond. If you are using an electronic bond, include your bid the Proof of Insurance printed from the Surety's Web Site.	The Power of Attorney page should be stapled to
☐ <b>Disadvantaged Business Utilization Plan and/or Good Faith Effort</b> – T Utilization Plan (SBE 2026), followed by the DBE Participation Statement (SB documentation of a Good Faith Effort, it is to follow the SBE Forms.	
The Bid Letting is now available in streaming Audio/Video from the IDOT the main page of the current letting on the day of the Letting. The stream will bids does not begin until approximately 10:30 AM.	<b>T Web Site.</b> A link to the stream will be placed on not begin until 10 AM. The actual reading of the
Following the Letting, the As-Read Tabulation of Bids will be posted by the en Web page for the current letting.	nd of the day. You will find the link on the main
QUESTIONS: pre-letting up to execution of the contract	
Contractor pre-qualification	217-782-3413
Small Business, Disadvantaged Business Enterprise (DBE)	
Contracts, Bids, Letting process or Internet downloads	
Estimates Unit	
Aeronautics	
IDNR (Land Reclamation, Water Resources, Natural Resources)	217-782-6302
QUESTIONS: following contract execution	
Subcontractor documentation, payments	217-782-3413
Railroad Insurance	217-785-0275

123

Proposal Submitted By
Name
Address
City

### Letting January 17, 2014

#### NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction.

BIDDERS NEED NOT RETURN THE ENTIRE PROPOSAL

## Notice to Bidders, Specifications, Proposal, Contract and Contract Bond



Springfield, Illinois 62764

Contract No. 89496
TAZEWELL County
Section 07-00176-00-BR (Pekin)
Route FAU 6759 (Sheridan Road)
Project M-5093(132)
District 4 Construction Funds

PLEASE MARK THE APPROPRIATE BOX BELOW:	
☐ A <u>Bid</u> <u>Bond</u> is included.	
☐ A <u>Cashier's Check</u> or a <u>Certified</u> <u>Check</u> is included	

Prepared by

F

Checked by

(Printed by authority of the State of Illinois)

#### Page intentionally left blank



**PROPOSAL** 

#### TO THE DEPARTMENT OF TRANSPORTATION

**District 4 Construction Funds** 

1. Proposal of	
Taxpayer Identification Number (Mandatory)	
For the improvement identified and advertised for bids in the Invitation for Bids a	s:
Contract No. 89496 TAZEWELL County Section 07-00176-00-BR (Pekin) Project M-5093(132) Route FAU 6759 (Sheridan Road)	

Project consists of replacing the structure carrying Sheridan Road over Lick Creek, located in the City of Pekin.

2. The undersigned bidder will furnish all labor, material and equipment to complete the above described project in a good and workmanlike manner as provided in the contract documents provided by the Department of Transportation. This proposal will become part of the contract and the terms and conditions contained in the contract documents will govern performance and payments.

- 3. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned bidder further declares that he/she has carefully examined the proposal, plans, specifications, addenda form of contract and contract bond, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this bid proposal he/she waives all right to plead any misunderstanding regarding the same.
- 4. **EXECUTION OF CONTRACT AND CONTRACT BOND.** The undersigned bidder further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, or as specified in the special provisions, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- 5. **PROPOSAL GUARANTY.** Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

<u>A</u>	mount o	of Bid	Proposal <u>Guaranty</u>	<u>Am</u>	ount c		roposal luaranty
Up to		\$5,000	\$150	\$2,000,000	to	\$3,000,000\$	\$100,000
\$5,000	to	\$10,000	\$300	\$3,000,000	to	\$5,000,000\$	\$150,000
\$10,000	to	\$50,000	\$1,000	\$5,000,000	to	\$7,500,000\$	250,000
\$50,000	to	\$100,000	\$3,000	\$7,500,000	to	\$10,000,000\$	3400,000
\$100,000	to	\$150,000	\$5,000	\$10,000,000	to	\$15,000,000\$	\$500,000
\$150,000	to	\$250,000	\$7,500	\$15,000,000	to	\$20,000,000\$	600,000
\$250,000	to	\$500,000	\$12,500	\$20,000,000	to	\$25,000,000\$	\$700,000
\$500,000	to	\$1,000,000	\$25,000	\$25,000,000	to	\$30,000,000\$	000,008
\$1,000,000	to	\$1,500,000	\$50,000	\$30,000,000	to	\$35,000,000\$	3900,000
\$1,500,000	to	\$2,000,000	\$75,000	over		\$35,000,000 \$1	,000,000

Bank cashier's checks or properly certified checks accompanying bid proposals will be made payable to the Treasurer, State of Illinois.

If a combination bid is submitted, the proposal guaranties which accompany the individual bid proposals making up the combination will be considered as also covering the combination bid.

The amount of the proposal guaranty check is	\$(	). If this proposal is accepted
and the undersigned will fail to execute a contract bond as required herein, it is hereby	y agreed that the amount of	the proposal guaranty will become the
property of the State of Illinois, and shall be considered as payment of damages due	e to delay and other causes	s suffered by the State because of the
failure to execute said contract and contract bond; otherwise, the bid bond will bec	ome void or the proposal	guaranty check will be returned to the
undersigned.		

undersigned.		sine told of the proposal guaranty officer, will be foldined to the
Attach Cashier's C	heck or Certif	ied Check Here
In the event that one proposal guaranty check is intended to cover two of the proposal guaranties which would be required for each individual proposal, state below where it may be found.		
The proposal guaranty check will be found in the bid proposal for:	Item	
	Section No.	
	County	

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

6.	following the comb proportion	combination bid not to the total contraction to the bic contraction	OS. The undersigned bidder further agrees that if awarded the on, he/she will perform the work in accordance with the requirement specified in the schedule below, and that the combination bid is submitted for the same. If an error is found to exist in the gross a combination, the combination bid shall be corrected as provide	ents of each individual contract comprising shall be prorated against each section in s sum bid for one or more of the individual
			combination bid is submitted, the schedule below must be cong the combination.	mpleted in each proposal
			te bids are submitted for one or more of the sections compri- tion bid must be submitted for each alternate.	sing the combination, a
			Schedule of Combination Bids	
Со	mbination No.	l	Sections Included in Combination	Combination Bid Dollars Cents
	110.		Geotions included in Combination	Donais Cents
7.	schedule all extens schedule is an erro will be man The sche provided	of prices f sions and are approx or in the ex ade only for eduled qual elsewhere	RICES. The undersigned bidder submits herewith, in accordant or the items of work for which bids are sought. The unit prices I summations have been made. The bidder understands that ximate and are provided for the purpose of obtaining a gross surtension of the unit prices, the unit prices will govern. Payment to ractual quantities of work performed and accepted or materials ntities of work to be done and materials to be furnished may be in the contract.	bid are in U.S. dollars and cents, and the quantities appearing in the bid in for the comparison of bids. If there is the contractor awarded the contract is furnished according to the contract. Increased, decreased or omitted as
8.	500/20-43	3) provides	O BUSINESS IN ILLINOIS. Section 20-43 of the Illinois Proceeds that a person (other than an individual acting as a sole proprieto state of Illinois prior to submitting the bid.	
9.	Departme and make Purchasin Neither	ent procure e payments ng Officer the CPO i	CONTRACT: The Department of Transportation will, in accements, execute the contract and shall be the sole entity having a under the contract. Execution of the contract by the Chief Pro (SPO) is for approval of the procurement process and execution or the SPO shall be responsible for administration of the coment there under except as otherwise permitted in the Code.	the authority to accept performance ocurement Officer (CPO) or the State n of the contract by the Department.
10.	The serv	ices of a s	subcontractor will be used.	
			′es □ lo □	
	their		contractors with subcontracts with an annual value of more than fress, general type of work to be performed, and the dollar allocat 0-120)	

-4-

STATE JOB #- C-94-049-08 ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 89496

ANSPORTATION ECMSOO2 DTGECMO3 ECMROO3 PAGE ES RUN DATE - 11/27/13 39496 RUN TIME - 183124

ROUTE FALL 67EG	TOTAL PRICE	S DOLLARS CTS		; ; ; ; ; ; ; ; ; ; ; ;			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ;				; ; ; ; ; ; ;	i i i i i i i			1 1 1 1 1 1 1 1 1 1	_
PROJECT NUMBER M-5093/132/000	RIC	NOULLARS CENTS		 					1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			: : : : : : : : : : : : : : : : : : : :	; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ;				
M-5	VITTING	4.000	1.000	1.000	670.000	76.000	108.000	62.000	177.000	15.000	275.000	243.000	7.000	747.000	0.250	22.500	
NUMBER (PEKIN)	UNIT OF	EACH	L SUM	L SUM	SQ FT	FOOT	LIND	LIND	CU YD	CU YD	CU YD	CU YD	cu yb	QY QS	ACRE	POUND	
COUNTY NAME CODE DIST SECTION TAZEWELL 179 04 07-00176-00-BR	ER PAY ITEM DESCRIPTION	ABOVE GRADE INL	216 TRAF CONT & PROT SPL	798 CONSTRUCTION LAYOUT	110 MECH ST EARTH RET WL	104 P UNDR FOR STRUCT 4	<b>-</b> !	10 TREE REMOV OVER 15	EARTH	OO ROCK EXCAVATION	CO CHANNEL EXCAVATION	<u>L</u>	50 TRENCH BACKFILL	10	OO SEEDING CL 3	OO NITROGEN FERT NUTR	
COUNT	ITEM	X2800520	X7010216	20013798	20034210	20046304	20100110	20100210	20200100	20200200	20300100	20400800	20800150	21101615	25000300	25000400	

(PEKIN)

N CTS ECMSOO2 DTGECMO3 ECMROO3 PAGE RUN DATE - 11/27/13 RUN TIME - 183124 TOTAL PRICE DOLLARS UNIT PRICE DOLLARS CENTS ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 89496 22.500 1,094.000 100.000 492.000 492.000 30.000 323,000 394.000 197.000 67.000 33.000 1,044.000 392.000 QUANTITY UNIT OF MEASURE POUND POUND POUND SQ YD FOOT FOOT NOL NO L SQ YD SQ YD SQ YD GALLON SQ YD SQ FT PAY ITEM DESCRIPTION HD EROS CONTR BLANKET PHOSPHORUS FERT NUTR TEMP EROS CONTR SEED P HMA BC IL19.0 N50 POTASSIUM FERT NUTR PERIMETER EROS BAR N50 PC CONC SIDEWALK 4 TEMP DITCH CHECKS P BIT MATLS PR CT STONE RIPRAP CL AGG BASE CSE A FILTER FABRIC P HMA SC "C" PAVEMENT REM FAU 6759 07-00176-00-BR 35100700 28000400 28000305 25000500 25000600 28000250 28200200 25100635 40600115 28100107 40603230 40603510 42400100 44000100 NUMBER TAZEWELL ITEM

1.000

EACH

REM EXIST STRUCT

50100100

(PEKIN)

ო

CTS ECMSOO2 DTGECMO3 ECMROO3 PAGE RUN DATE - 11/27/13 RUN TIME - 183124 TOTAL PRICE DOLLARS UNIT PRICE DOLLARS | CENTS ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 89496 134.300 63.600 1,940.000 9,870.000 12,440.000 52.000 46.000 1.000 105.000 360.000 39.000 2.000 1.000 3.000 QUANTITY UNIT OF MEASURE POUND POUND CU YD CU YD CU YD SQ FT FOOT EACH FOOT FOOT EACH EACH FOOT EACH FOOT PAY ITEM DESCRIPTION REINF BARS, EPOXY CTD STEEL RAIL TYPE 2399 FORM LINER TEX SURF COR STR PL ARCH 383 54213657 PRC FLAR END SEC 12 MAN TA 4 DIA T11F&G REINFORCEMENT BARS STORM SEW CL A 1 INLETS TA T11F&G COMB CC&G TB6.24 ROCK EXC STRUCT BICYCLE RAILING CONC SUP-STR CONC STRUCT NAME PLATES FAU 6759 07-00176-00-BR TAZEWELL 51500100 550A0050 50200400 50300255 50300285 50800105 50901720 54110383 50300225 50800205 50900200 ITEM NUMBER 60219300 60605000 60236800

ILLINDIS DEPARTMENT OF TRANSPORTATION ECMSOO2 DTGECMO3 ECMROO3 FAU 6759 07-00176-

ECMSOO2 DIGECMO3 ECMROO3 PAGE 4 RUN DATE - 11/27/13 RUN TIME - 183124	UNIT PRICE TOTAL PRICE												
PRICES R - 89496	OUANTITY	62.500 X	2.000 X	2.000 X	4.000 X	139.000 X		52.000 X	174.000 X	428.000 X	16.000 X	4.000 X	
SCHEDULE OF PRICES CONTRACT NUMBER - 89	UNIT OF MEASURE	FOOT	EACH	EACH	EACH	FOOT	T SUM	SQ FT	F007	FOOT	EACH	EACH	
O-BR (PEKIN)	PAY ITEM DESCRIPTION	63000001 SPBGR TY A 6FT POSTS	TRAF BAR TERM TG	63100087 TRAF BAR TERM TGA	63100167 TR BAR TRM T1 SPL TAN	66400205 CH LK FENCE 5	67100100 MOBILIZATION	72000100 SIGN PANEL T1	72900100 METAL POST TY A	78001110 PAINT PVT MK LINE 4	78200410 GUARDRAIL MKR TYPE A	78201000 TERMINAL MARKER - DA	
07-00176-00-BR TAZEWELL	ITEM	6300001	63100085	63100087	63100167	66400205	67100100	72000100	72900100	78001110	78200410	78201000	

NOTE: \*\*\* PLEASE TURN PAGE FOR IMPORTANT NOTES \*\*\*

TOTAL

FAU 6759
O7-00176-00-BR (PEKIN) SC
TAZEWELL CONT

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 89496

ECMSOO2 DTGECMO3 ECMROO3 PAGE RUN DATE - 11/27/13 RUN TIME - 183124

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.

- THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY. ζ,
  - 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
    - 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

ហ

## STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

#### I. GENERAL

- **A.** Article 50 of the Code establishes the duty of all State CPOs, SPOs, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. Except as otherwise required in subsection III, paragraphs J-M, by execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances have been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for the CPO to void the contract, and may result in the suspension or debarment of the bidder or subcontractor. If a false certification is made by a subcontractor the contractor's submitted bid and the executed contract may not be declared void unless the contractor refuses to terminate the subcontract upon the State's request after a finding that the subcontractor's certification was false.

	I acknowledge,	understand and	accept these	terms and	conditions.
--	----------------	----------------	--------------	-----------	-------------

#### II. ASSURANCES

The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

#### A. Conflicts of Interest

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois State Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois State Toll Highway Authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$177,412.00. Sixty percent of the salary is \$106,447.20.

The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code. Information concerning the exemption process is available from the Department upon request.

#### B. Negotiations

Section 50-15. Negotiations.

It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.

The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### C. Inducements

Section 50-25. Inducement.

Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### D. Revolving Door Prohibition

Section 50-30. Revolving door prohibition.

CPOs, SPOs, procurement compliance monitors, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### E. Reporting Anticompetitive Practices

Section 50-40. Reporting anticompetitive practices.

When, for any reason, any vendor, bidder, contractor, CPO, SPO, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offerors, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the CPO.

The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

#### F. Confidentiality

Section 50-45. Confidentiality.

Any CPO, SPO, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

#### G. Insider Information

Section 50-50. Insider information.

It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

☐ I acknowledge, understand and accept these terms and conditions for the above assurances.

#### **III. CERTIFICATIONS**

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. Section 50-2 of the Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible CPO whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

#### A. Bribery

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 2012.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

#### B. Felons

Section 50-10. Felons.

- (a) Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.
- (b) Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO may declare the related contract void if any of the certifications required by this Section are false.

#### C. Debt Delinquency

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The bidder or contractor or subcontractor, respectively, further acknowledges that the CPO may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

#### D. Prohibited Bidders, Contractors and Subcontractors

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontract is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

#### E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-14 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the CPO may declare the contract void if this certification is false.

#### F. Educational Loan

Section 3 of the Educational Loan Default Act provides no State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.

The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

#### G. Bid-Rigging/Bid Rotating

Section 33E-11 of the Criminal Code of 2012 provides:

- (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article.
- (b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

#### H. International Anti-Boycott

Section 5 of the International Anti-Boycott Certification Act provides every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.

The bidder makes the certification set forth in Section 5 of the Act.

#### I. Drug Free Workplace

The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.

The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace in compliance with the provisions of the

#### J. Disclosure of Business Operations in Iran

Chack the appropriate statement.

Section 50-36 of the Code, 30ILCS 500/50-36 provides that each bid, offer, or proposal submitted for a State contract shall include a disclosure of whether or not the Company acting as the bidder, offeror, or proposing entity, or any of its corporate parents or subsidiaries, within the 24 months before submission of the bid, offer, or proposal had business operations that involved contracts with or provision of supplies or services to the Government of Iran, companies in which the Government of Iran has any direct or indirect equity share, consortiums or projects commissioned by the Government of Iran and either of the following conditions apply:

- (1) More than 10% of the Company's revenues produced in or assets located in Iran involve oil-related activities or mineral-extraction activities; less than 75% of the Company's revenues produced in or assets located in Iran involve contracts with or provision of oil-related or mineral-extraction products or services to the Government of Iran or a project or consortium created exclusively by that government; and the Company has failed to take substantial action.
- (2) The Company has, on or after August 5, 1996, made an investment of \$20 million or more, or any combination of investments of at least \$10 million each that in the aggregate equals or exceeds \$20 million in any 12-month period, which directly or significantly contributes to the enhancement of Iran's ability to develop petroleum resources of Iran.

The terms "Business operations", "Company", "Mineral-extraction activities", "Oil-related activities", "Petroleum resources", and "Substantial action" are all defined in the Code.

Failure to make the disclosure required by the Code shall cause the bid, offer or proposal to be considered not responsive. The disclosure will be considered when evaluating the bid or awarding the contract. The name of each Company disclosed as doing business or having done business in Iran will be provided to the State Comptroller.

oricon the appro	phate statement.
//	Company has no business operations in Iran to disclose.
//	Company has business operations in Iran as disclosed the attached document.

#### K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

NA-FEDERAL		

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

#### L. Political Contributions and Registration with the State Board of Elections

Sections 20-160 and 50-37 of the Code regulate political contributions from business entities and any affiliated entities or affiliated persons bidding on or contracting with the state. Generally under Section 50-37, any business entity, and any affiliated entity or affiliated person of the business entity, whose current year contracts with all state agencies exceed an awarded value of \$50,000, are prohibited from making any contributions to any political committees established to promote the candidacy of the officeholder responsible for the awarding of the contracts or any other declared candidate for that office for the duration of the term of office of the incumbent officeholder or a period 2 years after the termination of the contract, whichever is longer. Any business entity and affiliated entities or affiliated persons whose state contracts in the current year do not exceed an awarded value of \$50,000, but whose aggregate pending bids and proposals on state contracts exceed \$50,000, either alone or in combination with contracts not exceeding \$50,000, are prohibited from making any political contributions to any political committee established to promote the candidacy of the officeholder responsible for awarding the pending contract during the period beginning on the date the invitation for bids or request for proposals is issued and ending on the day after the date of award or selection if the entity was not awarded or selected. Section 20-160 requires certification of registration of affected business entities in accordance with procedures found in Section 9-35 of The Election Code.

By submission of a bid, the contractor business entity acknowledges and agrees that it has read and understands Sections 20-160 and 50-37 of the Code, and that it makes the following certification:

The undersigned bidder certifies that it has registered as a business with the State Board of Elections and acknowledges a continuing duty to update the registration in accordance with the above referenced statutes. If the business entity is required to register, the CPO shall verify that it is in compliance on the date the bid or proposal is due. The CPO shall not accept a bid or proposal if the business entity is not in compliance with the registration requirements.

These requirements and compliance with the above referenced statutory sections are a material part of the contract, and any breach thereof shall be cause to void the contract under Section 50-60 of the Code. This provision does not apply to Federal-aid contracts.

#### M. Lobbyist Disclosure

Section 50-38 of the Code requires that any bidder or offeror on a State contract that hires a person required to register under the Lobbyist Registration Act to assist in obtaining a contract shall:

- (i) Disclose all costs, fees, compensation, reimbursements, and other remunerations paid or to be paid to the lobbyist related to the contract,
- (ii) Not bill or otherwise cause the State of Illinois to pay for any of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration, and
- (iii) Sign a verification certifying that none of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration were billed to the State.

This information, along with all supporting documents, shall be filed with the agency awarding the contract and with the Secretary of State. The CPO shall post this information, together with the contract award notice, in the online Procurement Bulletin.

Pursuant to Subsection (c) of this Section, no person or entity shall retain a person or entity to attempt to influence the outcome of a procurement decision made under the Code for compensation contingent in whole or in part upon the decision or procurement. Any person who violates this subsection is guilty of a business offense and shall be fined not more than \$10,000.

Bidder acknowledges that it is required to disclose the hiring of any person required to register pursuant to the Illinois Lobbyist Registration Act (25 ILCS 170) in connection with this contract.

	Bidder has not hired any person required to register pursuant to the Illinois Lobbyist Registration Act in connection with this contract.
Or	
	Bidder has hired the following persons required to register pursuant to the Illinois Lobbyist Registration Act in connection with the contract:
	l address of person:ees, compensation, reimbursements and other remuneration paid to said person:
☐ Lackn	owledge, understand and accept these terms and conditions for the above certifications.

#### IV. DISCLOSURES

A. The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The bidder further certifies that the Department has received the disclosure forms for each bid.

The CPO may void the bid, or contract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Code. Furthermore, the CPO may void the contract and the surety providing the performance bond shall be responsible for completion of the contract.

#### B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Code provides that all bids of more than \$25,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the contract. Furthermore, pursuant to Section 5-5, the Procurement Policy Board may review a proposal, bid, or contract and issue a recommendation to void a contract or reject a proposal or bid based on any violation of the Code or the existence of a conflict of interest as provided in subsections (b) and (d) of Section 50-35.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 200 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

The current annual salary of the Governor is \$177,412.00.

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. A separate Disclosure Form A must be submitted with the bid for each individual meeting the above requirements. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies and a total ownership certification. **The forms must be included with each bid.** 

#### C. Disclosure Form Instructions

#### Form A Instructions for Financial Information & Potential Conflicts of Interest

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 200 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YES NO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the bidding entity's or parent entity's distributive income? YES NO
4.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.)

A "YES" answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the bidding entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.

If the answer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

#### Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each bid submitted by the bidding entity. Note: Checking the <u>NOT APPLICABLE STATEMENT</u> on Form A <u>does not</u> allow the bidder to ignore Form B. Form B must be completed, checked, and dated or the bidder may be considered nonresponsive and the bid will not be accepted.

The Bidder shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following:

Option I: If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included. Bidders who submit Affidavits of Availability are suggested to use Option II.

Option II: If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type "See Affidavit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the Affidavit of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.

#### **ILLINOIS DEPARTMENT** OF TRANSPORTATION

#### Form A **Financial Information & Potential Conflicts of Interest Disclosure**

Contractor Name		
Legal Address		
O'the Otate 7's		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)

Disclosure of the information contained in this Form is required by the Section 50-35 of the Code (30 ILCS 500). Vendors desiring to enter into a contract with the State of Illinois must disclose the financial information and potential conflict of interest information as specified in this Disclosure Form. This information shall become part of the publicly available contract file. This Form A must be completed for bids in excess of \$25,000, and for all open-ended contracts. A publicly traded company may submit a 10K disclosure (or equivalent if applicable) in satisfaction of the requirements set forth in Form A. See Disclosure Form Instructions.

The current annual salary of the Governor is \$177,412.00.

#### DISCLOSURE OF FINANCIAL INFORMATION

1. Disclosure of Financial Information. The individual named below has an interest in the BIDDER (or its parent) in terms of ownership or distributive income share in excess of 5%, or an interest which has a value of more than 60% of the annual salary of the Governor. (Make copies of this form as necessary and attach a separate Disclosure Form A for each individual meeting these requirements)

FOR	NDIVIDUAL (	type or print information)		
	NAME:			
	ADDRESS			
	Type of owner	ship/distributable income share	:	
	stock	sole proprietorship	Partnership	other: (explain on separate sheet):
	% or \$ value of	ownership/distributable income sh	nare:	

- 2. Disclosure of Potential Conflicts of Interest. Check "Yes" or "No" to indicate which, if any, of the following potential conflict of interest relationships apply. If the answer to any question is "Yes", please attach additional pages and describe.
  - (a) State employment, currently or in the previous 3 years, including contractual employment of services. Yes No

If your answer is ves. please answer each of the following questions.

- 1. Are you currently an officer or employee of either the Capitol Development Board or the Illinois State Yes \_\_\_No \_\_ Toll Highway Authority?
- 2. Are you currently appointed to or employed by any agency of the State of Illinois? If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor provide the name the State agency for which you are employed and your annual salary.

3.	If you are currently appointed to or employed by any agency of the Salary exceeds 60% of the annual salary of the Governor, are you e (i) more than 7 1/2% of the total distributable income of your firm corporation, or (ii) an amount in excess of 100% of the annual salary	ntitled to receive n, partnership, association or
4.	If you are currently appointed to or employed by any agency of the Salary exceeds 60% of the annual salary of the Governor, are you a or minor children entitled to receive (i) more than 15% in aggregate of your firm, partnership, association or corporation, or (ii) an amount salary of the Governor?	nd your spouse of the total distributable income
	employment of spouse, father, mother, son, or daughter, including con previous 2 years.	
If your	answer is yes, please answer each of the following questions.	YesNo
1.	Is your spouse or any minor children currently an officer or employee Board or the Illinois State Toll Highway Authority?	of the Capitol Development YesNo
2.	Is your spouse or any minor children currently appointed to or employ of Illinois? If your spouse or minor children is/are currently appointed agency of the State of Illinois, and his/her annual salary exceeds 60 annual salary of the Governor, provide the name of the spouse and/of the State agency for which he/she is employed and his/her annual salary exceeds 60 annual salary of the Governor, provide the name of the spouse and/of the State agency for which he/she is employed and his/her annual salary exceeds 60 annual salary of the Governor, provide the name of the spouse and/of the State agency for which he/she is employed and his/her annual salary exceeds 60 annual salary exceeds 60 annual salary of the Governor, provide the name of the spouse and/of the State agency for which he/she is employed and his/her annual salary exceeds 60	d to or employed by any 0% of the or minor children, the name
3.	If your spouse or any minor children is/are currently appointed to or estate of Illinois, and his/her annual salary exceeds 60% of the annual are you entitled to receive (i) more than 71/2% of the total distributable firm, partnership, association or corporation, or (ii) an amount in excannual salary of the Governor?	I salary of the Governor, e income of your
4.	If your spouse or any minor children are currently appointed to or er State of Illinois, and his/her annual salary exceeds 60% of the annual and your spouse or any minor children entitled to receive (i) more that aggregate of the total distributable income from your firm, partnership (ii) an amount in excess of two times the salary of the Governor?	salary of the Governor, are you an 15% in the
		Yes No
unit of	e status; the holding of elective office of the State of Illinois, the govern local government authorized by the Constitution of the State of Illinoi currently or in the previous 3 years.	
	nship to anyone holding elective office currently or in the previous 2 ye daughter.	ears; spouse, father, mother, YesNo
Americ of the S	tive office; the holding of any appointive government office of the State a, or any unit of local government authorized by the Constitution of the State of Illinois, which office entitles the holder to compensation in exceptage of that office currently or in the previous 3 years.	State of Illinois or the statues
	nship to anyone holding appointive office currently or in the previous 2 daughter.	years; spouse, father, mother, YesNo
(g) Employ	yment, currently or in the previous 3 years, as or by any registered lob	byist of the State government. YesNo

son, or daughter.	YesNo
(i) Compensated employment, currently or in the previous committee registered with the Secretary of State or any caction committee registered with either the Secretary of State or any or action committee registered with either the Secretary of State or any or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary of State or action committee registered with either the Secretary or action committee registered with either the secretary or action committee registered with either the secretary or action committee registered wit	county clerk of the State of Illinois, or any political
(j) Relationship to anyone; spouse, father, mother, son, or clast 2 years by any registered election or re-election comcounty clerk of the State of Illinois, or any political action State or the Federal Board of Elections.	mittee registered with the Secretary of State or any committee registered with either the Secretary of
	Yes No
Communication Disclosure.	
Section 2 of this form, who is has communicated, is comemployee concerning the bid or offer. This disclosure is a	ner agent of the bidder or offeror who is not identified in municating, or may communicate with any State officer or continuing obligation and must be promptly supplemented erm of the contract. If no person is identified, enter "None"
Name and address of person(s):	

3.

**4. Debarment Disclosure.** For each of the persons identified under Sections 2 and 3 of this form, disclose whether any of the following has occurred within the previous 10 years: debarment from contracting with any governmental entity; professional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony convictions. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the procurement process and term of the contract. If no person is identified, enter "None" on the line below:

Name of person(s):	
Nature of disclosure:	
Track of displace of the second of the secon	
ADDU LOADUE OTATEMENT	
APPLICABLE STATEMENT  This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Und	lor
penalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of knowledge.	
Completed by:	
Signature of Individual or Authorized Representative Date	_
NOT APPLICABLE STATEMENT	
Under penalty of perjury, I have determined that no individuals associated with this organization the criteria that would require the completion of this Form A.	meet
This Disclosure Form A is submitted on behalf of the CONTRACTOR listed on the previous page	
Signature of Authorized Representative Date	_

The bidder has a continuing obligation to supplement these disclosures under Sec. 50-35 of the Code.

### ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form B Other Contracts & Financial Related Information Disclosure

Contractor Name			
Legal Address			
City, State, Zip			
Telephone Number	Email Address	Fax Number (if available)	
Disclosure of the information contained in this information shall become part of the public excess of \$25,000, and for all open-ended DISCLOSURE OF OTHER OF	licly available contract file. This For	m B must be completed for bi	ds
Identifying Other Contracts & Procure has any pending contracts (including leases	ement Related Information. The Bl s), bids, proposals, or other ongoing No	DDER shall identify whether i procurement relationship with	t
2. If "Yes" is checked. Identify each such information such as bid or project number (a INSTRUCTIONS:			
THE FOL	LOWING STATEMENT MUST BE	CHECKED	
	Signature of Authorized Representative	Date	_
	OWNERSHIP CERTIFICATION	<u>ON</u>	
Please certify that the following staten 100% of ownership.	nent is true if the individuals for all	submitted Form A disclosures	s do not total
	erest is held by individuals receivi outive income or holding less than a		the bidding
☐ Yes ☐ No ☐ N/A (F	Form A disclosure(s) established 10	0% ownership)	

#### **SPECIAL NOTICE TO CONTRACTORS**

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

#### CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



**PART I. IDENTIFICATION** 

**TRAINEES** 

Contract No. 89496 TAZEWELL County Section 07-00176-00-BR (Pekin) Project M-5093(132) Route FAU 6759 (Sheridan Road) District 4 Construction Funds

Dept. Human Rights #						_ Du	Duration of Project:										
Name of Bidder:																	
PART II. WORKE A. The undersigned which this contract we projection including a	d bidder ha	as analyz e perform	ed mir ed, an	d for th d fema	ne locat	ions fro	m whic	h the b	idder re	cruits	employe	ees, and he	reby subr	nits the foll	owii con	ng workfo	ı orce
		TOTA	AL Wo		Projec	tion for	Contra	ıct						CURRENT		1PLOYEE	ES .
				MINO	ORITY	EMPLO	YEES			TR/	AINEES			TO BE			
JOB CATEGORIES	EMPL	TAL OYEES		ACK	HISP	ANIC	*OTI		APPI TIC	ES	TRA	HE JOB INEES	EMP	OTAL LOYEES			OYEES
OFFICIALS (MANAGERS)	M	F	M	F	M	F	М	F	M	F	M	F	M	F		M	F
SUPERVISORS																	
FOREMEN																	
CLERICAL																	
EQUIPMENT OPERATORS																	
MECHANICS																	
TRUCK DRIVERS																	
IRONWORKERS																	
CARPENTERS																	
CEMENT MASONS																	
ELECTRICIANS																	
PIPEFITTERS, PLUMBERS																	
PAINTERS																	
LABORERS, SEMI-SKILLED																	
LABORERS, UNSKILLED																	
TOTAL																	
	TAE TOTAL Tr	BLE C	niectio	n for C	ontract				7		Γ	FOR	DEPART	MENT USE	0	NLY	
EMPLOYEES IN	TO	TAL OYEES		ACK		PANIC		ΓHER NOR.									
TRAINING APPRENTICES	M	F	М	F	М	F	M	F	-								
ON THE JOB																	

Note: See instructions on page 2

BC 1256 (Rev. 12/11/07)

Other minorities are defined as Asians (A) or Native Americans (N).
Please specify race of each employee shown in Other Minorities column.

Contract No. 89496 TAZEWELL County Section 07-00176-00-BR (Pekin) Project M-5093(132) Route FAU 6759 (Sheridan Road) District 4 Construction Funds

#### PART II. WORKFORCE PROJECTION - continued

B.	Included in "Total Employees" under Table A is the total event the undersigned bidder is awarded this contract.	number of <b>new hires</b> tha	at would be employed in the						
	The undersigned bidder projects that: (number)		new hires would be						
	recruited from the area in which the contract project is lonew hires would	cated; and/or (number)	ea in which the bidder's principal						
	office or base of operation is located.		·						
C. Included in "Total Employees" under Table A is a projection of numbers of persons to be employed undersigned bidder as well as a projection of numbers of persons to be employed by subcontractors									
	The undersigned bidder estimates that (number) be directly employed by the prime contractor and that (number) employed by subcontractors.	umber)	persons will be						
PART II	III. AFFIRMATIVE ACTION PLAN								
	The undersigned bidder understands and agrees that is utilization projection included under <b>PART II</b> is determined in any job category, and in the event that the undersign commencement of work, develop and submit a writte (geared to the completion stages of the contract) who utilization are corrected. Such Affirmative Action Plant the <b>Department of Human Rights</b> .	ed to be an underutilizat ned bidder is awarded n Affirmative Action Pla nereby deficiencies in n	ion of minority persons or women this contract, he/she will, prior to an including a specific timetable ninority and/or female employee						
	The undersigned bidder understands and agrees that the submitted herein, and the goals and timetable included uto be part of the contract specifications.								
Compa	pany	Telephone Numb	er						
Addres									
	NOTICE REGARDING	G SIGNATURE							
	Bidder's signature on the Proposal Signature Sheet will constitut completed only if revisions are required.	e the signing of this form.	The following signature block needs						
Signatu	uture:	Title:	Date:						
Instruction	tions: All tables must include subcontractor personnel in addition to	prime contractor personnel.							
Table A	A - Include both the number of employees that would be hired (Table B) that will be allocated to contract work, and include should include all employees including all minorities, apprentic	all apprentices and on-the-job	trainees. The "Total Employees" column						
Table B	<ul> <li>Include all employees currently employed that will be allocate currently employed.</li> </ul>	d to the contract work includin	g any apprentices and on-the-job trainees						
Table C	C - Indicate the racial breakdown of the total apprentices and on-	the-job trainees shown in Tabl	e A.						
			DO 1050 (D 10111107)						

#### **ADDITIONAL FEDERAL REQUIREMENTS**

In addition to the Required Contract Provisions for Federal-Aid Construction Contracts (FHWA 1273), all bidders make the following certifications.

- A. By the execution of this proposal, the signing bidder certifies that the bidding entity has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action, in restraint of free competitive bidding in connection with the submitted bid. This statement made by the undersigned bidder is true and correct under penalty of perjury under the laws of the United States.
- B. <u>CERTIFICATION, EQUAL EMPLOYMENT OPPORTUNITY:</u>

1.	Have you participated in any previous contracts or subcontracts subject to the equal opportunity clause. YES NO
2.	If answer to #1 is yes, have you filed with the Joint Reporting Committee, the Director of OFCC, any Federal agency, or the former President's Committee on Equal Employment Opportunity, all reports due under the applicable filing requirements of those organizations? YES NO

Contract No. 89496 TAZEWELL County Section 07-00176-00-BR (Pekin) Project M-5093(132) Route FAU 6759 (Sheridan Road) District 4 Construction Funds

#### PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 3 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name	
(IF AN INDIVIDUAL)		
	Firm Name	
(IF A CO-PARTNERSHIP)		
(II / 100 I / III III )	Dubiness / (duress	
		Name and Address of All Members of the Firm:
-		
	Corporate Name	
	Ву	Signature of Authorized Representative
(IF A CORPORATION)		
		Typed or printed name and title of Authorized Representative
	Attact	
	Allesi	Signature
(IF A JOINT VENTURE, USE THIS SECTION FOR THE MANAGING PARTY AND THE	Business Address	
SECOND PARTY SHOULD SIGN BELOW)		
	Corporate Name	
	Ву	
(IF A JOINT VENTURE)		Signature of Authorized Representative
		Typed or printed name and title of Authorized Representative
	Attest	Signature
	Dunings - Adds	· ·
	Business Address	
If more than two parties are in the joint venture,	please attach an addit	ional signature sheet.

# Illinois Department of Transportation

### Return with Bid (If Applicable)

#### Division of Highways Annual Proposal Bid Bond

This Annual Proposal Bid Bond shall become effective at 12:01 AM (CD	ST) on and shall be valid until 11:59 PM (CDST).			
KNOW ALL MEN BY THESE PRESENTS, That We				
as PRINCIPAL, and				
amount specified in the bid proposal under "Proposal Guaranty" in effe	TE OF ILLINOIS in the penal sum of 5 percent of the total bid price, or for the ct on the date of the Invitation for Bids, whichever is the lesser sum, well and hich we bind ourselves, our heirs, executors, administrators, successors and			
	at whereas, the PRINCIPAL may submit bid proposal(s) to the STATE OF mprovements published in the Transportation Bulletin during the effective term			
NOW, THEREFORE, if the Department shall accept the bid proposal(s) of the PRINCIPAL; and if the PRINCIPAL shall, within the time and as specified in the bidding and contract documents; and if, after award by the Department, the PRINCIPAL shall enter into a contract in accordance with the terms of the bidding and contract documents including evidence of the required insurance coverages and providing such bond as specified with good and sufficient surety for the faithful performance of such contract and for the prompt payment of labor and material furnished in the prosecution thereof; or if, in the event of the failure of the PRINCIPAL to enter into such contract and to give the specified bond, the PRINCIPAL pays to the Department the difference not to exceed the penalty hereof between the amount specified in the bid proposal and such larger amount for which the Department may contract with another party to perform the work covered by said bid proposal, then this obligation shall be null and void, otherwise, it shall remain in full force and effect.				
In TESTIMONY WHEREOF, the said PRINCIPAL has caused this instrument to be signed by its officer day of A.D.,	In TESTIMONY WHEREOF, the said SURETY has caused this instrument to be signed by its officer  day of A.D.,			
(Company Name)	(Company Name)			
By (Signature and Title)	By(Signature of Attorney-in-Fact)			
,				
Notary for PRINCIPAL	Notary for SURETY			
STATE OF	STATE OF			
COUNTY OF	COUNTY OF			
Signed and attested before me on (date) by	Signed and attested before me on (date)			
(Name of Person)	(Name of Person)			
(Seal) (Signature of Notary Public)	(Seal) (Signature of Notary Public)			
(Date Commission Expires)	(Date Commission Expires)			
	id Bond form, the Principal may file an Electronic Bid Bond. By signing bid bond has been executed and the Principal and Surety are firmly and as shown above.			
Electronic Bid Bond ID # Company/Bidder Name	Signature and Title			

# Illinois Department of Transportation

#### **Return with Bid**

### Division of Highways Proposal Bid Bond

		Item No.			
		Letting Dat	e		
(NOW ALL PERSONS BY T	HESE PRESENTS, That We				
as PRINCIPAL, and					
he amount specified in the b	lly, severally and firmly bound unto the ST id proposal under "Proposal Guaranty" in a STATE OF ILLINOIS, for the payment of	effect on the date of the Invitation fo	or Bids, whichever is the lesser sum, well		
	E FOREGOING OBLIGATION IS SUCH the Department of Transportation, for the impr				
specified in the bidding and of with the terms of the bidding with good and sufficient sure prosecution thereof; or if, in to pays to the Department the d	the Department shall accept the bid propo- contract documents; and if, after award be and contract documents including evidence ty for the faithful performance of such contract of the failure of the PRINCIPAL difference not to exceed the penalty hereof contract with another party to perform the vill force and effect.	y the Department, the PRINCIPAL ce of the required insurance coverage contract and for the prompt payment to enter into such contract and to between the amount specified in the	shall enter into a contract in accordance les and providing such bond as specified at of labor and material furnished in the give the specified bond, the PRINCIPAL bid proposal and such larger amount for		
hen Surety shall pay the per vithin such period of time, th	rtment determines the PRINCIPAL has fa nal sum to the Department within fifteen e Department may bring an action to colle irred in any litigation in which it prevails eit	(15) days of written demand thereforect the amount owed. Surety is liable	or. If Surety does not make full paymen		
n TESTIMONY WHEREOF, the said PRINCIPAL has caused this instrument to be signed by its officer day of A.D.,		In TESTIMONY WHEREOF, instrument to be signed by its day of	the said SURETY has caused this s officer  A.D.,		
(Con	npany Name)	(Com	npany Name)		
·	ipany Name)	·	ipany Name)		
By(Si	gnature and Title)	By(Signature of Attorney-in-Fact)			
Notary for PRINCIPAL		Notary for SURETY			
STATE OF		STATE OF			
COUNTY OF		COUNTY OF			
Signed and attested before me on (date) by (Name of Person)		Signed and attested before r	ne on (date)		
		(Name of Person)			
Seal)		(Seal)			
<del></del> /	(Signature of Notary Public)	_	(Signature of Notary Public)		
	(Date Commission Expires)	-	(Date Commission Expires)		
proposal the Principal is	bove section of the Proposal Bid Bon ensuring the identified electronic bid nois under the conditions of the bid b	bond has been executed and			

Company/Bidder Name

Electronic Bid Bond ID #

Signature and Title



#### **DBE Utilization Plan**

#### (1) Policy

It is public policy that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision shall have the maximum opportunity to participate in the performance of contracts financed in whole or in part with Federal or State funds. Consequently the requirements of 49 CFR Part 26 apply to this contract.

#### (2) Obligation

Date

The contractor agrees to ensure that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision have the maximum opportunity to participate in the performance of contracts or subcontracts financed in whole or in part with Federal or State funds. The contractor shall take all necessary and reasonable steps in accordance with 49 CFR Part 26 and the Special Provision to ensure that said businesses have the maximum opportunity to compete for and perform under this contract. The contractor shall not discriminate on the basis of race, color, national origin or sex in the award and performance of contracts.

(3) Project and Bid Identification			
Complete the following information concerning the project and bid:			
Route	Total Bid		_
Section	Contract DBE Goal		
Project		(Percent)	(Dollar Amount)
County			
Letting Date			
Contract No.			
Letting Item No.			
(4) Assurance			
Attached are the signed participation statements, forms suse of each business participating in this plan and assuring work of the contract.  Failed to meet contract award goals and has included good provided participation as follows:  Disadvantaged Business Participation per of the contract goals should be accordingly modified or was support of this request including good faith effort. Als required by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the Special Provision evidencing availability and the second participation is supported by the second participati	d documented participation as followers  SBE 2025, required by the Special of that each business will perform that each business will perform that each documentation to motion the second second are the signed participant use of each business participant.	al Provision evid n a commercially neet the goals ar ion required by rticipation stater	encing availability and vuseful function in the and that my company has the Special Provision in ments, forms SBE 2025,
business will perform a commercially useful function in the Company  By	The "as read" Low Bidder is red	for each project. Th	•
Title	submitted in accordance with the		ocal Let Projects

The Department of Transportation is requesting disclosure of information that is necessary to accomplish the purpose as outlined under State and Federal law. Disclosure of this information is **REQUIRED**. Failure to provide any information will result in the contract not being awarded. This form has been approved by the State Forms Manager Center.

2300 South Dirksen Parkway

Springfield, Illinois 62764

Submit forms to the

Local Agency

(P)	Illinois Department of Transportation			BE Participatio	n Statement
Subcontract		L	etting		
Participation	on Statement		lt	tem No.	
(1) Instruct	ions		C	Contract	
be submitte	nust be completed for each disadvantaged bused in accordance with the special provision and pace is needed complete an additional form fo	I will be attached t			
(2) Work					
Pay Item No.	Description	Qua	ıntity	Unit Price	Total
		Total			
	(3) Partial Payment Items For any of the above items which are partial pay items, specifically describe the work and subcontract dollar amount:				
(4) Commitment The undersigned certify that the information included herein is true and correct, and that the DBE firm listed below has agreed to perform a commercially useful function in the work of the contract item(s) listed above and to execute a contract with the prime contractor. The undersigned further understand that no changes to this statement may be made without prior approval from the Department's Bureau of Small Business Enterprises and that complete and accurate information regarding actual work performed on this project and the payment therefore must be provided to the Department.					
	Signature for Prime Contractor		Sig	nature for DBE Firm	
Title		Title			
Date		Date			
Contact		Contact Per	son _		
Phone	Phone				
Firm Name		Firm Name			
Address _					
City/State/Z	City/State/Zip				

The Department of Transportation is requesting disclosure of information that is necessary to accomplish the statutory purpose as outlined under the state and federal law. Disclosure of this information is **REQUIRED**. Failure to provide any information will result in the contract not being awarded. This form has been approved by the State Forms Management Center.

WC \_\_\_\_\_

E \_\_\_\_\_

# PROPOSAL ENVELOPE



# **PROPOSALS**

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

## Submitted By:

lame:	
address:	
Phone No.	

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

### **NOTICE**

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

# CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

## **NOTICE**

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. 89496 TAZEWELL County Section 07-00176-00-BR (Pekin) Project M-5093(132) Route FAU 6759 (Sheridan Road) District 4 Construction Funds



# **SUBCONTRACTOR DOCUMENTATION**

Public Acts 96-0795, 96-0920, and 97-0895 enacted substantial changes to the provisions of the Code (30 ILCS 500). Among the changes are provisions affecting subcontractors. The Contractor awarded this contract will be required as a material condition of the contract to implement and enforce the contract requirements applicable to subcontractors that entered into a contractual agreement with a total value of \$50,000 or more with a person or entity who has a contract subject to the Code and approved in accordance with article 108.01 of the Standard Specifications for Road and Bridge Construction.

If the Contractor seeks approval of subcontractors to perform a portion of the work, and approval is granted by the Department, the Contractor shall provide a copy of the subcontract to the Illinois Department of Transportation's CPO upon request within 15 calendar days after execution of the subcontract.

Financial disclosures required pursuant to Sec. 50-35 of the Code must be submitted for all applicable subcontractors. The subcontract shall contain the certifications required to be made by subcontractors pursuant to Article 50 of the Code. This Notice to Bidders includes a document incorporating all required subcontractor certifications and disclosures for use by the Contractor in compliance with this mandate. The document is entitled <u>State Required Ethical Standards Governing Subcontractors</u>.

# STATE ETHICAL STANDARDS GOVERNING SUBCONTRACTORS

Article 50 of the Code establishes the duty of all State CPOs, SPOs, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.

The certifications hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed should the Department approve the subcontractor. The CPO may terminate or void the contract approval if it is later determined that the bidder or subcontractor rendered a false or erroneous certification. If a false certification is made by a subcontractor the contractor's submitted bid and the executed contract may not be declared void unless the contractor refuses to terminate the subcontract upon the State's request after a finding that the subcontractor's certification was false.

Section 50-2 of the Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible CPO whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

### A. Bribery

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract to which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 2012.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

#### B. Felons

Section 50-10. Felons.

- (a) Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.
- (b) Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO may declare the related contract void if any of the certifications required by this Section are false.

#### C. <u>Debt Delinquency</u>

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The bidder or contractor or subcontractor, respectively, further acknowledges that the CPO may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

#### D. Prohibited Bidders, Contractors and Subcontractors

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the CPO shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

#### E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-14 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the CPO may declare the contract void if this certification is false.

Name of Subcontracting Company

Authorized Officer

Date

The undersigned, on behalf of the subcontracting company, has read and

#### SUBCONTRACTOR DISCLOSURES

#### I. DISCLOSURES

**A.** The disclosures hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed. The subcontractor further certifies that the Department has received the disclosure forms for each subcontract.

The CPO may void the bid, contract, or subcontract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Code. Furthermore, the CPO may void the contract.

#### B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Code provides that all subcontracts with a total value of \$50,000 or more, from subcontractors identified in Section 20-120 of the Code, shall be accompanied by disclosure of the financial interests of the subcontractor. This disclosed information for the subcontractor, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the Prime Contractor's contract. Furthermore, pursuant to this Section, the Procurement Policy Board may recommend to allow or void a contract or subcontract based on a potential conflict of interest.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the subcontracting entity or its parent entity, whichever is less, unless the subcontractor is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 200 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

The current annual salary of the Governor is \$177,412.00.

In addition, all disclosures shall indicate any other current or pending contracts, subcontracts, proposals, leases, or other ongoing procurement relationships the subcontracting entity has with any other unit of state government and shall clearly identify the unit and the contract, subcontract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. A separate Disclosure Form A must be submitted with the bid for each individual meeting the above requirements. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies and a total ownership certification. **The forms must be included with each bid.** 

#### C. <u>Disclosure Form Instructions</u>

#### Form A Instructions for Financial Information & Potential Conflicts of Interest

If the subcontractor is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 200 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a subcontractor is not subject to Federal 10K reporting, the subcontractor must determine if any individuals are required by law to complete a financial disclosure form. To do this, the subcontractor should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the subcontracting company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YES NO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the subcontracting entity's or parent entity's distributive income? YES NO
	(Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.)
4.	Does anyone in your organization receive greater than 5% of the subcontracting entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per subcontract</u> even if a specific individual would require a yes answer to more than one question.)
S"	answer to any of these questions requires the completion of Form A. The subcontractor must determine each individual in the

subcontracting entity or the subcontracting entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The subcontractor is responsible for the accuracy of any information provided.

If the answer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

#### Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each subcontract submitted by the subcontracting entity. *Note: Checking the <u>NOT APPLICABLE STATEMENT</u> on Form A <u>does not</u> allow the subcontractor to ignore Form B. Form B must be completed, checked, and dated or the subcontract will not be approved.* 

The Subcontractor shall identify, by checking Yes or No on Form B, whether it has any pending contracts, subcontracts, leases, bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the subcontractor only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the subcontractor must list all non-IDOT State of Illinois agency pending contracts, subcontracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts or subcontracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included.

# ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form A Subcontractor: Financial Information & Potential Conflicts of Interest Disclosure

Subcontractor Name		
Legal Address		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)

Disclosure of the information contained in this Form is required by the Section 50-35 of the Code (30 ILCS 500). Subcontractors desiring to enter into a subcontract of a State of Illinois contract must disclose the financial information and potential conflict of interest information as specified in this Disclosure Form. This information shall become part of the publicly available contract file. This Form A must be completed for subcontracts with a total value of \$50,000 or more, from subcontractors identified in Section 20-120 of the Code, and for all openended contracts. A publicly traded company may submit a 10K disclosure (or equivalent if applicable) in satisfaction of the requirements set forth in Form A. See Disclosure Form Instructions.

The current annual salary of the Governor is \$177,412.00.

FOR INDIVIDUAL (type or print information)

### DISCLOSURE OF FINANCIAL INFORMATION

1. Disclosure of Financial Information. The individual named below has an interest in the SUBCONTRACTOR (or its parent) in terms of ownership or distributive income share in excess of 5%, or an interest which has a value of more than 60% of the annual salary of the Governor. (Make copies of this form as necessary and attach a separate Disclosure Form A for each individual meeting these requirements)

NAN	re-
NAM	
ADD	RESS
Туре	of ownership/distributable income share:
stock % or	sole proprietorship Partnership other: (explain on separate shee
	sure of Potential Conflicts of Interest. Check "Yes" or "No" to indicate which, if any, of the following onflict of interest relationships apply. If the answer to any question is "Yes", please attach additional describe.
(a) State e	mployment, currently or in the previous 3 years, including contractual employment of services.  YesNo
If your a	answer is yes, please answer each of the following questions.
1.	Are you currently an officer or employee of either the Capitol Development Board or the Illinois State Toll Highway Authority?  YesNo
2.	Are you currently appointed to or employed by any agency of the State of Illinois? If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, provide the name the State agency for which you are employed and your annual salary.

	3.	If you are currently appointed to or employed by any agency of t salary exceeds 60% of the annual salary of the Governor, are yo (i) more than 7 1/2% of the total distributable income of your corporation, or (ii) an amount in excess of 100% of the annual salary	ou entitled to receive firm, partnership, association or
	4.	If you are currently appointed to or employed by any agency of the salary exceeds 60% of the annual salary of the Governor, are your minor children entitled to receive (i) more than 15% in the income of your firm, partnership, association or corporation, or the salary of the Governor?	ou and your spouse aggregate of the total distributable
(b)		employment of spouse, father, mother, son, or daughter, includir previous 2 years.	ng contractual employment services  YesNo
	If	your answer is yes, please answer each of the following question	
	1.	Is your spouse or any minor children currently an officer or empl Board or the Illinois State Toll Highway Authority?	oyee of the Capitol Development YesNo
		Is your spouse or any minor children currently appointed to or er of Illinois? If your spouse or minor children is/are currently agency of the State of Illinois, and his/her annual salary ex annual salary of the Governor, provide the name of your spouse of the State agency for which he/she is employed and his/her an	appointed to or employed by any ceeds 60% of the and/or minor children, the name
	3.	If your spouse or any minor children is/are currently appointed to State of Illinois, and his/her annual salary exceeds 60% of the are you entitled to receive (i) more than 71/2% of the total distribution, partnership, association or corporation, or (ii) an amount annual salary of the Governor?	nnual salary of the Governor, utable income of your
	4.	If your spouse or any minor children are currently appointed to State of Illinois, and his/her annual salary exceeds 60% of the are you and your spouse or minor children entitled to receive aggregate of the total distributable income of your firm, partner (ii) an amount in excess of two times the salary of the Governor?	nual salary of the Governor, (i) more than 15 % in the ship, association or corporation, or
(-)	<b>-</b> 1		YesNo
(C)	unit of	ve status; the holding of elective office of the State of Illinois, the glocal government authorized by the Constitution of the State of Illicurrently or in the previous 3 years.	
(d)		onship to anyone holding elective office currently or in the previour daughter.	s 2 years; spouse, father, mother, YesNo
(e)	Americ of the	ntive office; the holding of any appointive government office of the ca, or any unit of local government authorized by the Constitution State of Illinois, which office entitles the holder to compensation is charge of that office currently or in the previous 3 years.	of the State of Illinois or the statutes
		onship to anyone holding appointive office currently or in the previous daughter.	ous 2 years; spouse, father, mother, YesNo
(g)	Emplo	yment, currently or in the previous 3 years, as or by any registere	d lobbyist of the State government. YesNo

(h) Relationship to anyone who is or was a registered lobbyist son, or daughter.	in the previous 2 years; spouse, father, mother, YesNo
(i) Compensated employment, currently or in the previous 3 y committee registered with the Secretary of State or any contact action committee registered with either the Secretary of States	ounty clerk of the State of Illinois, or any political
(j) Relationship to anyone; spouse, father, mother, son, or data last 2 years by any registered election or re-election common county clerk of the State of Illinois, or any political action of State or the Federal Board of Elections.	ttee registered with the Secretary of State or any ommittee registered with either the Secretary of
	YesNo
Communication Disclosure.	
Disclose the name and address of each lobbyist and other a Section 2 of this form, who is has communicated, is communic employee concerning the bid or offer. This disclosure i supplemented for accuracy throughout the process and throidentified, enter "None" on the line below:	eating, or may communicate with any State officer or s a continuing obligation and must be promptly
Name and address of person(s):	

3

**4. Debarment Disclosure.** For each of the persons identified under Sections 2 and 3 of this form, disclose whether any of the following has occurred within the previous 10 years: debarment from contracting with any governmental entity; professional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony convictions. This disclosure is a continuing obligation and must be promptly

supplemented for accuracy throughout the procurement process and term of the contract. If no person is identified, enter "None" on the line below: Name of person(s): Nature of disclosure: APPLICABLE STATEMENT This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Under penalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of my knowledge. Completed by: Signature of Individual or Authorized Officer Date **NOT APPLICABLE STATEMENT** Under penalty of perjury, I have determined that no individuals associated with this organization meet the criteria that would require the completion of this Form A. This Disclosure Form A is submitted on behalf of the SUBCONTRACTOR listed on the previous page. Signature of Authorized Officer Date

# ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form B Subcontractor: Other Contracts & Financial Related Information Disclosure

Subcontractor Name			
Legal Address			
City, State, Zip			
Telephone Number	Email Address	Fax Number (if available)	
Disclosure of the information contained in information shall become part of the publicl a total value of \$50,000 or more, from subcontracts.	y available contract file. This Form	B must be completed for subcontracts	with
DISCLOSURE OF OTHER CONTRA	CTS, SUBCONTRACTS, AND PR	OCUREMENT RELATED INFORMATION	<u>NC</u>
1. Identifying Other Contracts & Procure any pending contracts, subcontracts, includ any other State of Illinois agency: Ye If "No" is checked, the subcontractor only	ing leases, bids, proposals, or othe s No	r ongoing procurement relationship with	
2. If "Yes" is checked. Identify each such information such as bid or project number (a INSTRUCTIONS:			<b>)</b>
THE FOLLO	WING STATEMENT MUST BE CH	ECKED	
•	Signature of Authorized Officer	Date	
	OWNERSHIP CERTIFICATION	<u>l</u>	
Please certify that the following statement is of ownership	s true if the individuals for all submi	tted Form A disclosures do not total 100	1%
Any remaining ownership interest is parent entity's distributive income o		than \$106,447.20 of the bidding entity's interest.	or
☐ Yes ☐ No ☐ N/A (Form	A disclosure(s) established 100% of	ownership)	

# Illinois Department of Transportation

### **NOTICE TO BIDDERS**

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation. Electronic bids are to be submitted to the electronic bidding system (ics-Integrated Contractors Exchange). Paper-based bids are to be submitted to the Chief Procurement Officer for the Department of Transportation in care of the Chief Contracts Official at the Harry R. Hanley Building, 2300 South Dirksen Parkway, in Springfield, Illinois until 10:00 o'clock a.mJanuary 17, 2014. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- **2. DESCRIPTION OF WORK**. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 89496
TAZEWELL County
Section 07-00176-00-BR (Pekin)
Project M-5093(132)
Route FAU 6759 (Sheridan Road)
District 4 Construction Funds

Project consists of replacing the structure carrying Sheridan Road over Lick Creek, located in the City of Pekin.

- 3. INSTRUCTIONS TO BIDDERS. (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
  - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Ann L. Schneider, Secretary

## **CONTRACT 89496**

# INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

# Adopted January 1, 2014

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS, frequently used RECURRING SPECIAL PROVISIONS, and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 1-1-12) (Revised 1-1-14)

# SUPPLEMENTAL SPECIFICATIONS

Std. S	Spec. Sec.	
101	1 Definition of Terms	ge No.
102	2 Advertisement, Bidding Award and Contract F	1
105	O Control of Work	2
106	Control of Materials	3
107	Legal Regulations and Responsibility 4- D. Lis	5
108	Prosecution and Progress	6
109	Measurement and Payment	14
202	Earth and Rock Excavation	15
211	Opsoil and Compost	17
253	Planting Woody Plants	18
280	lemporary Frosion and Sodiment Country	10
312	Stabilized Subhase	24
406	Hot-Mix Asphalt Binder and Surface Co-	22
407	HOT-IVIX Asphalt Pavement (Full Donth)	23
420	Portland Cement Concrete Dayon ant	26
424	FUNIANG Cement Concrete Sidowalk	30
440	Removal of Existing Payament and Asset	32
503	Concrete Structures	33
504	Precast Concrete Structures	3/
506	Cleaning and Painting New Stool Structure	37
512	Piling	38
516	United Shafts	30
521	bearings	40
540	Box Culverts	41
588	Bridge Relief Joint System	42
589	Elastic Joint Sealer	43
602	Catch Basin, Manhola, Inlet, Designation	15
	and Reconstruction, Adjustment.	
603	Adjusting Frames and Grates of Designation	46
606	Concrete Gutter Curh Median and David Division	47
610	Shoulder Inlets with Curh	49
639	Precast Prestressed Concrete Sight Sonor	50
642	Precast Prestressed Concrete Sight Screen Shoulder Rumble Strips Impact Attenuators	51
643	Impact Attenuators	52
644	TIGN Tension Cable Median Parrier	53
701	Work Zone Traffic Control and Protection	55
706	Impact Attenuators Temporors	57
707	Wovable Traffic Barrier	60
708	Movable Traffic Barrier Temporary Water Filled Barrier	63
730	Temporary Water Filled Barrier Wood Sign Support	65
780	Wood Sign Support	67
860	Pavement Striping	
		68 73
		13

1001 1003 1004 1006 1011 1017 1018 1019 1020 1024 1030 1040	Fine Aggregates Coarse Aggregates Metals Mineral Filler Packaged, Dry, Combined Materials for Mortar Packaged Rapid Hardening Mortar or Concrete Controlled Low-Strength Material Portland Cement Concrete Grout and Nonshrink Grout Hot-Mix Asphalt Drain Pine Tile Draingge Metal	75 77 81 83 84 85 86 87 126
1042 1070 1073	Frecast Concrete Products	132
1081 1082 1083 1095 1101 1102 1105 1106	Preformed Bearing Pads Elastomeric Bearings Pavement Markings General Equipment Hot-Mix Asphalt Equipment Pavement Marking Equipment Work Zone Traffic Control Devices	135 136 137 138 139
		1-77

# RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

CH	ECH	SHEET#	
1		Y Additional China	ACE NO
		(Eff. 2-1-69) (Rev. 1-1-10)	AGE NO.
2	)	(Eff. 2-1-69) (Rev. 1-1-10)	110
3	)	Y EEU (EII. 7-27-78) (Pay 11 10 00)	450
4		Specific Equal Employment Opportunity Possessing	152
5		Specific Equal Employment Opportunity Responsibilities Non Federal-Aid Contracts (Eff. 3-20-69) (Rev. 1-1-94)  Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1.1.12)	160
6		Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-13)	103
7		Asbestos Bearing Pad Removal (Eff. 11-1-03)  Asbestos Waterproofing Membrane and Asbestos Hot-Mix Asphalt Surface Removal (Eff. 6.1.90) (D. 1.1-1-103)	168
8		Asbestos Waterproofing Membrane and Asbestos Hot-Mix Asphalt Surface Removal (Eff. 6-1-89) (Rev. 1-1-09)  In Stream West, Stream Crossings, Other Temporary Stream Crossings, and	173
9		In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98)	477
10	Х	Construction Layout States Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07)	1/5
11		Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07)	1/6
12			
13			
14			
15			
16			
17			
18			
19			
20	X		
21			
22			
23			
24 25			
25 26			
27		Figure Suppliment of Matric Balta (Fit 7.4.00)	200
28			
29			
30			
31	Х		
32	^		
33			
34			
35			
36			
37		Preventive Maintenance – Cape Seal (Eff. 1-1-09) (Rev. 1-1-12)	. 249
38			
39		Temporary Raised Pavement Markers (Eff. 1-1-09) (Rev. 1-1-12)	. 275
		Restoring Bridge Approach Pavements Using High-Density Foam (Eff. 1-1-09) (Rev. 1-1-12)	. 285
		(	286

# LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS

The following LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

# Table of Contents

CHECK SHEET #	
IRS 1 Pagement	AGE NO.
LRS 2 Furnished Excavation  LRS 3 Work Zone Traffic Control Surveillance	290
LRS 3 Work Zone Traffic Control Surveillance	291
LRS 3 Work Zone Traffic Control Surveillance  LRS 4 Flaggers in Work Zones	292
LRS 4  Flaggers in Work Zones	293
LNS 0   Bidding Requirements and Condition of Conditions	204
LRS 6 Bidding Requirements and Conditions for Contract Proposals  LRS 7 Bidding Requirements and Conditions for Material Proposals	295
LRS 7 Bidding Requirements and Conditions for Contract Proposals  LRS 8 Reserved.	301
LRS 8 Reserved.  LRS 9 Bituminous Surface Treatments	307
LRS 9 Bituminous Surface Treatments LRS 10 Reserved	308
LRS 10 Reserved  LRS 11 Employment Practices	300
LNS 12 L Wages of Employees on Dublin W. J.	210
LRS 13   Selection of Labor	242
LRS 13 Selection of Labor	211
LRS 15 Partial Payments	215
LRS 14 Paving Brick and Concrete Paver Pavements and Sidewalks LRS 15 Partial Payments LRS 16 Protests on Local Lettings	210
LRS 16 Protests on Local Lettings LRS 17 Substance Abuse Prevention Program.	210
LRS 17 Substance Abuse Prevention Program.  LRS 18 Multigrade Cold Mix Asphalt	220
LRS 18  Multigrade Cold Mix Asphalt	32U 324
	321

FAU 6759 (Sheridan Road) Section 07-00176-00-BR City of Pekin Tazewell County

# **Index of Sheets**

<u>Description</u>	
Description of Work	Page No.
Road Open to Traffic	1
	1
Closure Date/Date of Completion (Plus Working Days)	1
Traffic Control Plan	2
Traffic Control and Protection (Special)	2
Existing Water Main	3
Borrow and Furnished Excavation	4
Embankment (Restrictions)	
Embankment	4
Proof Rolling	5
Subgrade Treatment	5
	5
Concrete Superstructure Aggregate Optimization	6
PCC QC/QA Electronic Report Submittal	6
PCC Automatic Batching Equipment	7
Corrugated Structural Plate Arch	8
Nationwide 404 Permit	10
Status of Utilities	
	14

# GUIDE BRIDGE SPECIAL PROVISION INDEX/CHECK SHEET Effective as of the: January 17, 2014 Letting

<u>Po</u> #		√ File Nan		Effective	Revised
	-	GBSP 4	Monthed Foliand Cement Mortar	Lune 7, 400	
		GBSP 12	2   Drainage System	June 7, 1994	
	+	GBSP 1		June 10, 199	, = 001
		GBSP 14	Jack and Remove Existing Bearings	Oct 13, 1988	
	-	GBSP 15	D   Three Sided Precast Concrete Structure	April 20, 199	1,200,
	-	GBSP 16	Jacking Existing Superstructure	July 12, 1994	
		GBSP 17	Bonded Preformed Joint Seal	Jan 11, 1993	-,,
		GBSP 18	Modular Expansion Joint	July 12, 1994	,
		GBSP 21	Cleaning and Painting Contact Surface Areas of Existing Steel Structures	May 19, 1994 June 30, 200	July 26, 201 May 18, 201
		GBSP 25	Cleaning and Pointing Full III Division		1114) 10, 201
		GBSP 26		Oct 2, 2001	April 19, 201
***********		GBSP 28	Containment and Disposal of Lead Paint Cleaning Residues  Deck Slab Repair	Oct 2, 2001	April 30, 201
		GBSP 29		May 15, 1995	Oct 15, 2011
-	1	GBSP 30	The second Contract C	May 15, 1995	
	+	GBSP 31	Bridge Deck Latex Concrete Overlay	May 15, 1995	Jan 18, 2011
	1	GBSP 32	Bridge Deck High-Reactivity Metakaolin (HRM) Conc Overlay	Jan 21, 2000	Oct 30, 2012
	+	GBSP 33	1 · Orrigordi v Olicel Fillini	Sept 2, 1994	Jan 31, 2012
	T	GBSP 34	Pedestrian Truss Superstructure	Jan 13, 1998	Aug 17, 2012
	$\vdash$	GBSP 35	Concrete Wearing Surface	June 23, 1994	
15	X		Silicone Bridge Joint Sealer	Aug 1, 1995	
	1	GBSP 42	Mechanically Stabilized Earth Retaining Walls	Feb 3, 1999	Oct 15, 2011
		GBSP 43	Drilled Soldier Pile Retaining Wall	Sept 20, 2001	July 26, 2013
	-	GBSP 44	Driven Soldier Pile Retaining Wall	Nov 13, 2002	Aug 17, 2012
		GBSP 45	Temporary Soil Retention System	Dec 30, 2002	Aug 17, 2012
		GBSP 46	Bridge Deck Thin Polymer Overlay	May 7, 1997	May 11, 2009
		GBSP 46 GBSP 47	Geotextile Retaining Walls	Sept 19, 2003	Feb 6, 2013
4	X		High Performance Concrete Structures	Aug 5, 2002	July 26, 2013
-	$\stackrel{\wedge}{\rightarrow}$	GBSP 51	Pipe Underdrain for Structures	May 17, 2000	Jan 1, 2007
		GBSP 53	Structural Repair of Concrete		Jan 22, 2010
		GBSP 55	Erection of Curved Steel Structures	Mar 15, 2006	July 26, 2013
$\dashv$	-	GBSP 56	Setting Piles in Rock	June 1, 2007	
-+	$\dashv$	GBSP 57	Temporary Mechanically Stabilized Earth Retaining Walls	Nov 14, 1996	April 19, 2012
$\dashv$		GBSP 59	Biamond Officing and Surface Lesting Bridge Sections	Jan 6, 2003	July 26, 2013
		GBSP 60	Containment and Disposal of Non-Lead Paint Cleaning Residues	Dec 6, 2004 Nov 25, 2004	July 9, 2008 Mar 6, 2009
	T	GBSP 61	Slipform Parapet		77.07 0, 2000
		GBSP 62	Concrete Deck Beams	June 1, 2007	Aug 17, 2012
		GBSP 64	Segmental Concrete Block Wall	June 13, 2008	Oct 9, 2009
		GBSP 65	Precast Modulor Poteinia William	Jan 7, 1999	Oct 30, 2012
		GBSP 66	Precast Modular Retaining Walls Wave Equation Applying & Pile	Mar 19, 2001	Oct 30, 2012
$\top$		GBSP 67	Wave Equation Analysis of Piles	Nov 14, 2008	00, 2012
_	$\perp$			Mar 6, 2009	
+		GBSP 70	Braced Excavation	Aug 0, 4005	
	(	GBSP 71	Aggregate Column Ground Improvement	Aug 9, 1995	May 18, 2011

		GBSP 72	Bridge Deck Fly Ash or GGBF Slag Concrete Overlay		
		GBSP 73	Cofferdams Concrete Overlay	Jan 18, 2011	Oct 15, 2011
		GBSP 74	Permanent Steel Sheet Piling (LRFD)	Oct 15, 2011	
		GBSP 75	Bond Breaker for Prestressed Concrete Bulb-T Beams	Jan 31, 2012	Aug 17, 2012
		GBSP 76	Granular Backfill for Structures	April 19, 2012	
		GBSP 77	Weep Hole Drains for Abutments, Wingwalls, Retaining Walls	April 19, 2012	Oct 30, 2012
			And Culverts	April 19, 2012	Oct 22, 2013
25	X	GBSP 78	Bridge Deck Construction		
			2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Oct 22, 2013	

LIST ANY ADDITIONAL SPECIAL PROVISIONS BELOW
----------------------------------------------

The following Guide Bridge Special Provisions have been incorporated into the 2012 S	
Specifications:	andard
File Title	

File	Title	
Name		Std Spec
GBSP22	Cleaning and Painting New Metal Structures	Location
GBSP36	Surface Preparation and Painting Reg. for Weathering Oc.	506
GBSP50	Removal of Existing Non-composite Bridge Decks	506
GBSP58	Mechanical Splicers	501
GBSP63	Demolition Plans for Removal of Existing Structures	508
BSP68	rining	501
BSP69	Freeze-Thaw Aggregates for Concrete Superstructures Poured on Grade	512
	on Grade	1004

The following Guide Bridge Special Provisions have been discontinued or have been superseded:

File	Title	Provisions have been discontinued or have been superseded:			
Name		Disposition:			
GBSP37	Underwater Structure Excavation Protection				
GBSP11	Permanent Steel Sheet Piling	Replaced by GBSP73			
GBSP52	Porous Granular Embankment (Special)	Replaced by GBSP74			
	Carlotte Carlotte (Capecial)	Replaced by GBSP76			

# INDEX LOCAL ROADS AND STREETS SPECIAL PROVISIONS

			ENDER EDUCE ROADS AND STREETS SPECIAL PROVI	SIONS	
<u>LR #</u>	Po	1#		<u> </u>	
LR SD12		#	Special Provision Title	Effortivo	<b>5</b>
LR SD13		<u> </u>	Slab Movement Detection Device	Effective	Revised
LR SD406	2	느	Required Cold Milled Surface Texture	Nov. 11, 1984	,
LR 102-2	)	느	I KESCINDED	Nov. 1, 1987	Jan. 1, 2007
		<u>_</u>	Bidding Requirements and Conditions for Contract Proposals		
LR 105	28	$\boxtimes$		Jan. 1, 2001	Jan. 1, 2014
LR 107-2			Railroad Protective Liability Incurrence (	Jan. 1, 1999	Jan. 1, 2007
LR 107-4	31	$\boxtimes$	Insurance Insurance	Mar. 1, 2005	Jan. 1, 2007
LR 107-7			Wages of Employees on Public Works	Feb. 1, 2007	Aug. 1, 2007
LR 108		$\Box$	Combination Bids	Jan. 1, 1999	
LR 109		Ħ	Equipment Devited D. (	Jan. 1, 1994	Jan. 1, 2014
LR 212		H	Equipment Rental Rates	Jan. 1, 2012	Mar. 1, 2005
LR 355-1		님	Shaping Roadway		
LR 355-2		님	Bituminous Stabilized Base Course, Road Mix or Traveling Plant Mix Bituminous Stabilized Base Course, Road Mix or Traveling Plant Mix	Aug. 1, 1969	Jan. 1, 2002
LR 400-1		님		Oct. 1, 1973	Jan. 1, 2007
LR 400-7 LR 400-2		닏	Diturnitious Treated Earth Surface	Feb. 20, 1963	Jan. 1, 2007
LR 400-2 LR 400-3		$\sqcup$	Bituminous Surface Plant Mix (Class R)	Jan. 1, 2007	Apr. 1, 2012
			HOURS HECKELING (HIR) - Surface Described	Jan. 1, 2008	
LR 400-4			I directly the ciamation (FLIR) with Emulais at A	Jan. 1, 2012	
LR 400-5			OUR THE LACE RECVEILED A LIPTANIES - 1 A LIPTA	Apr. 1, 2012	Jun. 1, 2012
LR 400-6			Cold In Place Recycling (CIR) with Foamed Asphalt	Apr. 1, 2012	Jun. 1, 2012
LR 400-7			Full-Depth Reclamation (EDD) with Foamed Asphalt	June 1, 2012	04.1. 1, 2012
LR 402			Full-Depth Reclamation (FDR) with Foamed Asphalt Salt Stabilized Surface Course	June 1, 2012	
LR 403-1		Ē	Surface Profile Million of Fig. 11	Feb. 20, 1963	lan 1 0007
			Surface Profile Milling of Existing, Recycled or Reclaimed Flexible Pavement	Apr. 1, 2012	Jan. 1, 2007
LR 403-2				7 pr. 1, 2012	Jun. 1, 2012
LR 406			Bituminous Hot Mix Sand Seal Coat	Aug. 1, 1969	
LR 420			Filling HMA Core Holes with Non-shrink Grout		Jan. 1, 2007
LR 442			1 OCT avertient (Special)	Jan. 1, 2008	
LR 451			Bituminous Patching Mixtures for Maintenance Use	May 12, 1964	Jan. 2, 2007
LR 503-1		닏	Order mind bituminous Pavement with Eiber Apple	Jan. 1, 2004	Jun. 1, 2007
			· MITIOURIU CIASS OI CONCERTA	Oct. 1, 1991	Jan. 1, 2007
LR 503-2			Furnishing Class SI Concrete (Short Lood)	Oct. 1, 1973	Jan. 1, 2002
LR 542			i pe Cuiverts, Type (Furnished)	Jan. 1, 1989	Jan. 1, 2002
LR 663			Calcium Chloride Applied	Sep. 1, 1964	Jan. 1, 2007
LR 702	32	$\boxtimes$	Construction and Maintenance Signs	Jun. 1, 1958	Jan. 1, 2007
LR 1000-1			Cold In-Place Recycling (CID) and 5 u.p.	Jan. 1, 2004	Jun. 1, 2007
			Cold In-Place Recycling (CIR) and Full Depth Reclamation (FDR) with	Apr. 1, 2012	
LR 1000-2			Emulsified Asphalt Mix Design Procedures	F. 1, 2012	Jun. 1, 2012
			Cold In-Place Recycling (CIR) and Full Depth Reclamation (FDR) with Foamed Asphalt Mix Design Procedures	June 1, 2012	
LR 1004				Jane 1, 2012	
LR 1030		H	Coarse Aggregate for Bituminous Surface Treatment	lan 1 0000	
LR 1032-1		H	O. Owith Chive	Jan. 1, 2002	Jan. 1, 2007
LR 1102			Emulsified Asphalts	Mar. 1, 2008	Jan. 1, 2010
LIX 1102			Road Mix or Traveling Plan Mix Equipment	Jan. 1, 2007	Feb. 7, 2008
				Jan. 1, 2007	

# BDE SPECIAL PROVISIONS For the January 17 and February 28, 2014 Lettings

The following special provisions indicated by an "x" are applicable to this contract. An \* indicates a new or revised special provision for the letting.

Eilo Maur					•
File Nam 80240		- Committee in	Special Provision Title	T-CC 11	_
* 80099	VI	3   /	Above Grade Inlet Protection	Effective	
80274		-	Accessible Pedestrian Signals (APS)	July 1, 2	
80192			Aggregate Subgrade Improvement	April 1, 2	
80173		-	Automated Flagger Assistance Device	April 1, 2	
80241			Bituminous Materials Cost Adjustments	Jan. 1, 2	
5024 i		-	Bridge Demolition Debris	Nov. 2, 2	
			Building Removal-Case I (Non-Friable and Friable Asbestos)	July 1, 2	
50481				Sept. 1, 1	, , , , , , , , ,
50491			Dullding Removal-Case III (Friable Ashestos)	Sept. 1, 19	, ,
50531			Building Removal-Case IV (No Ashestos)	Sept. 1, 19	
80292			Coarse Aggregate in Bridge Approach Slabs/Footings	Sept. 1, 19	1-11 11 2000
80310			Coaled Galvanized Steel Conduit	April 1, 20	
80198			_ Completion Date (via calendar days)	Jan. 1, 20	013
80199		-	Completion Date (via calendar days) Plus Working D	April 1, 20	
80293			Soliciete Box Culverts with Skews > 30 Degrees and David Silverts	April 1, 20	108
2222					112
80294			Concrete Box Culverts with Skews ≤ 30 Degrees Regardless of Design Fill and Skews > 30 Degrees with D		
00044				April 1, 20	12
80311					
00277	35	X	Concrete Mix Design - Department Provided	Jan. 1, 20	
00201			Construction Air Quality – Diesel Retrofit	Jan. 1, 20	
80029	36	X	Disadvantaged Business Enterprise Participation	June 1, 20	10 Jan. 1, 2014
80265	46	X	J Priction Aggregate	Sept. 1, 200	00 Aug. 2, 2011
80229	SARSON CONTRACTOR		Fuel Cost Adjustment	Jan. 1, 201	11
* 80329			Glare Screen	April 1, 200	9 July 1, 2009
80303	50	X	Granular Materials	Jan. 1, 201	4
80304			Grooving for Recessed Pavement Markings	Nov. 1, 201	
80246			HOLIVIX Asphalt - Density Testing of Longitudinal Late	Nov. 1, 201	2 Jan. 1, 2013
80322	51	X	Hot-Mix Asphalt – Mixture Design Composition and Volumetric	Jan. 1, 201	0 April 1, 2012
			· regar critchis	Nov 1, 201	3
80323	54	Χ	Hot-Mix Asphalt – Mixture Design Verification and Production		
80315			Insertion Lining of Culverts	Nov 1, 201	
80324	L		LRFD Pipe Culvert Burial Tables	Jan. 1, 201.	3 Nov 1, 2013
80325	57	X	LRFD Storm Sewer Burial Tables	Nov 1, 201:	3
80045			Material Transfer Device	Nov 1, 2013	3
80165			Moisture Cured Urethane Paint System	June 15, 1999	9 Jan. 1, 2009
* 80330	ſ		Pavement Marking for Bike Symbol	Nov. 1, 2006	
80298	Γ		Pavement Marking Tape Type IV	Jan. 1, 2014	1
80254			Pavement Patching	April 1, 2012	
	67	X	Payrolls and Payroll Records	Jan. 1, 2010	
* 80332	69	X	Portland Cement Congrete Control	Jan. 1, 2014	
80326		X	Portland Cement Concrete – Curing of Abutments and Piers Portland Cement Concrete Equipment	Jan. 1, 2014	
80300			The state of the control of the cont	Nov 1, 2013	
* 80328	71	X	Preformed Plastic Pavement Marking Type D - Inlaid Progress Payments	April 1, 2012	
		X (	Quality Control/Quality Assures	Nov. 2, 2013	
34261		F	Quality Control/Quality Assurance of Concrete Mixes	Jan. 1, 2012	
80157			Railroad Protective Liability Insurance	Dec. 1, 1986	
	*Posteriora Linux	and the second	Railroad Protective Liability Insurance (5 and 10)	Jan. 1, 2006	
	L			,	

<u>File Name</u> 80306 80327	Pg. 73 X 83 X	Special Provision Title Reclaimed Asphalt Pavement (RAP) and Reclaimed Asphalt Shingles (RAS) Reinforcement bars	Effective Nov. 1, 2012	<u>Revised</u> Nov. 1, 2013
80283 80319 80307 80127 80317	85 X 89 X 90 X	Removal and Disposal of Regulated Substances Removal and Disposal of Surplus Materials Seeding Steel Cost Adjustment Surface Testing of Hot-Mix Asphalt Overlages	Nov 1, 2013 Jan. 1, 2012 Nov. 2, 2012 Nov. 1, 2012 April 2, 2004	Nov. 2, 2012 April 1, 2009
80301 80333 20338 80318 80288 80302 80289	91 X 96 X	Tracking the Use of Pesticides  Traffic Control Setup and Removal Freeway/Expressway  Training Special Provisions  Traversable Pipe Grate  Warm Mix Asphalt  Weekly DBE Trucking Reports	Jan. 1, 2013 Aug. 1, 2012 Jan. 1, 2014 Oct. 15, 1975 Jan. 1, 2013 Jan. 1, 2012	April 1, 2013 Nov. 1, 2013
80071	special r	Wet Reflective Thermoplastic Pavement Marking Working Days	June 2, 2012 Jan. 1, 2012 Jan. 1, 2002	

The following special provisions are in the 2014 Supplemental Specifications and Recurring Special Provisions:

	and 2017 Cupplemental	Specifications and Recurring Spe	cial Provisions.	
File Nar	me Special Provision Title			
80309	Anchor Bolts	New Location	<b>Effective</b>	Douberd
	2010	Articles 1006.09, 1070.01	Jan. 1, 2013	Revised
80276	Bridge Relief Joint Sealer	and 1070.03	, oan. 1, 2013	
_	2. ago richer John Sealer	Article 503.19 and Sections	lan 1 2010	A
80312	Drain Pino Tilo Desi	588 and 589	Jan. 1, 2012	Aug. 1, 2012
00012	Drain Pipe, Tile, Drainage Mat, and Wall Drain	Article 101.01, 1040.03, and	lan 4 0040	
8 <b>03</b> 13	Fabria Pagging D. J.	1040.04	Jan. 1, 2013	
80169	and boaring raus	Article 1082.01	1- 4 00	
00103	High Tension Cable Median Barrier	0 - 41	Jan. 1, 2013	
80320	Liberatura a p	Section 644 and Article 1106.02	Jan. 1, 2007	Jan. 1, 2013
80297	- Janaaraa Daliilades	Article 108.09		
00297	Modified Urethane Pavement Marking	Section 780 Artistan 4005 on	April 1, 2013	
90050		Section 780, Articles 1095.09 and 1105.04	April 1, 2012	
80253	Moveable Traffic Barrier	Cart. wow		
00004	_	Section 707 and Article 1106.02	Jan. 1, 2010	Jan. 1, 2013
80231	Pavement Marking Removal			,
80321	Pavement Removal	Recurring CS #33	April 1, 2009	
80022	Payments to Subcontractors	Article 440.07	April 1, 2013	
80316	Placing and Consolidating Concrete	Article 109.11	June 1, 2000	Jan. 1, 2006
	and consider	Articles 503.06, 503.07, and	Jan. 1, 2013	1, 2000
80278	Planting Woody Plants	516.12	,	
		Section 253 and Article	Jan. 1, 2012	Aug. 1, 2012
80305	Polyurea Pavement Markings	1081.01	1, 2012	Aug. 1, 2012
80279	Portland Cement Concrete	Article 780.14	Nov. 1, 2012	lon 1 2012
	ounding Concrete	Sections 312, 503, 1003,		Jan. 1, 2013
80218	Preventive Maintenance – Bituminous Surface	1004, 1019, and 1020	odii. 1, 2012	Nov. 1, 2013
	Treatment Surface	Recurring CS #34	Jan. 1, 2009	A 11 /1 A 204 m
80219		•	Jan. 1, 2009	April 1, 2012
80220	Preventive Maintenance – Cape Seal	Recurring CS #35	lon 1 2000	A - D - A - A
80221	Preventive Maintenance – Micro Surfacing	Recurring CS #36		April 1, 2012
80224	Preventive Maintenance – Slurry Seal	Recurring CS #37	Jan. 1, 2009	April 1, 2012
JULET	Restoring Bridge Approach Pavements Using High-	Recurring CS #39		April 1, 2012
80255	Definity Foarr	300 #35	Jan. 1, 2009	Jan. 1, 2012
00200	Stone Matrix Asphalt	Sections 406, 1003, 1004,		
80143	Cuber term	1030, and 1011	Jan. 1, 2010 A	Aug. 1, 2013
00143	Subcontractor Mobilization Payments	Article 100 10	92	
	·	744016-108.12	April 2, 2005 🛭 🗚	April 1, 2011

File Name 80308 80286	Synthetic Fibers in Concrete Gutter, Curb, Median and Paved Ditch	New Location Articles 606.02 and 606.11	Effective Nov. 1, 2012	Revised
80225 80256	Temporary Erosion and Sediment Control Temporary Raised Pavement Marker Temporary Water Filled Barrier	Articles 280.04 and 280.08 Recurring CS #38 Section 708 and Article	Jan. 1, 2012 Jan. 1, 2009 Jan. 1, 2010	Jan. 1, 2013
80273 80270	Traffic Control Deficiency Deduction Utility Coordination and Conflicts	1106.02 Article 105.03 Articles 105.07, 107.19, 107.31, 107.37, 107.38, 107.39 and 107.40	Aug. 1, 2011 April 1, 2011	Jan. 1, 2012

The following special provisions require additional information from the designer. The Special Provisions are:

•	Bridge	Demolition	Debris
	C 11 11	_	

- Building Removal-Case I
- Building Removal-Case II
- Building Removal-Case III
- Building Removal-Case IV
- Completion Date
- Completion Date Plus Working Days
- DBE Participation

- Material Transfer Device
- Railroad Protective Liability Insurance
- Training Special Provisions
- Working Days

# **CITY OF PEKIN**

# SPECIAL PROVISION

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," Adopted January 1, 2012, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures of Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAU Route 6759 (Sheridan Road, Section 07-00176-00-BR in Tazewell County and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

## **DESCRIPTION OF WORK**

This work includes the removal and replacement of the structure on minor new alignment carrying Sheridan Road over Lick Creek in the city of Pekin in Tazewell County. The work on this project consists of earthwork, structure and pavement items and other collateral work as necessary to complete the project.

## **ROAD OPEN TO TRAFFIC**

As a general traffic control policy for this project, the roadway within the project limits shall be closed at all times throughout construction.

All commercial, private, field and entrances within the project limits shall have suitable access provided as determined by the Engineer at all times during construction. Any additional material or accommodations required to maintain access will be the responsibility of the Contractor and will not be paid for separately.

The Contractor shall notify the Engineer at least 2 weeks in advance of starting the project.

# CLOSURE DATE/DATE OF COMPLETION (PLUS WORKING DAYS)

The Contractor will not be allowed to close the roadway until June 2, 2014 and the Contractor shall schedule his operations so as to complete all work, except as specified below, and open all the roadway to traffic on or before August 19, 2014. The Contractor shall note that this completion date is based on an expedited work schedule. The Contractor will be allowed ten

FAU 6759 (Sheridan Road) Section 07-00176-00-BR City of Pekin Tazewell County

(10) working days, after the completion date, to complete any remaining striping, planting, seeding and sodding work or other items outside of the roadway.

## TRAFFIC CONTROL PLAN

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction," the applicable guidelines contained in the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to <u>Section 701</u> and Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701001 701006 701011 701301 701311 BLR 21 701901

Special attention is called to Section 1106 of the Standard Specifications.

# TRAFFIC CONTROL AND PROTECTION (SPECIAL)

This work shall consists of furnishing, installing, maintaining, relocating and removal of all traffic control required for the purpose of regulating, warning or directing traffic for all construction activities for the replacement of the Sheridan Road Structure over Lick Creek. This work shall be completed in accordance with Article 107.14 and Section 701 of the Standard Specifications, the details and notes in the plans, all applicable Highway Standards, the Special Provisions and as specified herein.

The plans details present a plan for implementing the necessary traffic control for this project. The plans do not attempt to detail or define all construction conditions which may require additional installation of traffic control items to meet unforeseen needs. The Contractor may revise or modify the traffic control as shown in the plans to address any unforeseen needs upon written approval of the Engineer.

Existing regulatory traffic signing shall be removed or covered as needed for construction. The Contractor shall furnish, install and maintain all temporary signing as specified in the plans and Highway Standards. This work will not be paid for separately but will be governed by Article 107.25 of the Standard Specifications.

Method of Measurement: All traffic control and protection required by this provision will be measured for payment on a lump sum basis. All traffic control necessary to construct the structure, pavement and marked route detour shall be considered included in the cost bid for this item. No additional compensation will be made for any alterations, modifications, or

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

additions necessary to accommodate the traffic control to construct the various work items shown in the plans.

Basis of Payment: This work shall be paid for at the contract price per lump sum for TRAFFIC CONTROL AND PROTECTION (SPECIAL) and shall be payment in full for all labor, materials, and equipment required to furnish and install the traffic control as described above and as shown on the plan detail sheets. No additional compensation will be paid.

# **EXISTING WATER MAIN**

There is an existing water line on the north side of the structure. It is 8" ductile iron. The water line will cross near the end of the proposed wingwalls. The intent is not to move the existing water line, but work around it during construction by either shortening a wingwall or pass the water line through a sleeve in the wingwall stem.

The work to accomplish this should be per the approval of the Engineer.

Any additional work required will be paid in accordance with Article 104.09 of the Standard Specification.

### **BORROW AND FURNISHED EXCAVATION**

Effective March 7, 2000 Revised April 27, 2007

Add the following to the requirements of Article 204:

"Soils which demonstrate the following properties shall be restricted to the interior of the embankment and shall be covered on both sides and top with a minimum of 3 feet (900mm) of non-restricted soil not considered detrimental in terms of erosion potential or excess volume change. A restricted soil is defined as having any one of the following properties:"

A grain size distribution with less than 35% passing the number 75um (#200) sieve.

A plasticity index of less than 12.

A liquid limit in excess of 50.

"All restricted and non-restricted embankment materials shall have the following minimum strengths for the indicated moistures:"

Immediate Bearing Value	Shear Strength At 95% Density *	Moisture
3.0	1000PSF (50 Kpa)	120%
4.0	1300 PSF (62 Kpa)	110%

<sup>\*</sup>Granular Soils φ=35°

## **EMBANKMENT (RESTRICTIONS)**

Effective January 21, 2005 Revised August 3, 2007

Add the following to the requirements of Article 205.04:

Gravel, crushed stone or soils having less than 35% passing the number 200 sieve and other materials as allowed by Article 202.03 of the standard specifications are further restricted. These further restricted materials are also limited to the interior of the embankment and shall have a minimum cover of 3' (1 m) of non-restricted soil (see "Borrow and Furnished Excavation" Special Provision). Alternating layers of further restricted material and cohesive soil will not be permitted. The further restricted materials may only be incorporated into the embankment by using one of the following procedures:

- a. The further restricted materials shall be placed in 4" lifts and disked with the underlying lift material until a uniform and homogenous material is formed having more than 35% passing the number 200 sieve.
- b. Sand, gravel or crushed stone embankment when placed on the existing ground surface will be drained using a 10' (3 m) by 10' (3 m) french drain consisting of nonwoven geotechnical fabric with 12" (0.3 m) of B-3 riprap. This shall be constructed on both sides of the embankment at the toe of the foreslope spaced 150' (46 m) apart. At locations requiring a French drain the 3' (1 m) cohesive cap shall not be installed within

the 10' by 10' riprap area. If the Engineer determines that the existing ground is a granular free draining soil, the french drain may be deleted.

c. Sand, gravel or crushed stone embankment when placed on top of a cohesive embankment will be drained with a permanent 4" (100 mm) underdrain system. The underdrain system shall consist of a longitudinal underdrain on both sides of the embankment and transverse underdrains spaced at 250' (75 m) centers. The underdrain shall consist of a 2' (0.6 m) deep by 1' (0.3 m) wide trench, backfilled with FA4 sand and a 4" (100 mm) diameter underdrain. In addition, both sides of the embankment will have a 6" (150 mm) diameter pipe drain which will drain the underdrain system and outletted into a permanent drainage structure or outletted by a headwall at the toe of the embankment.

The above work will not be paid for separately but shall be included in the cost of Earth Excavation, Furnished Excavation, or Borrow Excavation.

#### **EMBANKMENT**

Effective: July 1, 1990 Revised: November 1, 2007

Revise the third paragraph of Article 205.06 of the Standard Specifications to read:

All embankment shall be constructed with not more than 110% of optimum moisture content, determined according to AASHTO T 99 (Method C). The 110% of optimum moisture limit may be waived in free draining granular material when approved by the Engineer.

The Contractor may, at his option, add a drying agent to lower the moisture content as specified above. The drying agent must be approved by the Engineer prior to use. Extra compensation will not be allowed for the use of a drying agent but will be considered included in the cost of the various items of excavation.

## **PROOF ROLLING**

Effective April 23, 2004 Revised January 1, 2007

This work shall consist of proof rolling the subgrade with a fully loaded tandem axle dump truck and driver at the direction of the Engineer. The truck shall travel the subgrade in all of the proposed lanes of traffic in the presence of the Engineer.

This work will not be paid for separately, but considered included in the various earthwork pay items.

## SUBGRADE TREATMENT

Effective July 1, 1990 Revised December 31, 2012

Revise first sentence of first paragraph of Article 301.04 as follows:

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

"When compacted, the subgrade shall have a minimum dry density of 95 percent of the standard laboratory dry density and a minimum immediate bearing value (IBV) of 4.0."

Delete the second paragraph (including subparagraphs a, b, and c) of Article 301.04 of the Standard Specifications and replace it with the following:

"In cut sections the contractor responsible for the rough grading shall obtain not less than 95% of the standard laboratory density and not more than 110% of the optimum moisture for the top 1' (300mm) of the subgrade.

The Contractor may, at his/her option, add a drying agent to lower the moisture content as specified. The drying agent must be approved by the Engineer prior to use. Additional compensation will not be allowed for the use of a drying agent, but will be considered as included in the cost of the various earthwork items."

In the first sentence of the third paragraph delete "above steps have" and replace with "work has."

# CONCRETE SUPERSTRUCTURE AGGREGATE OPTIMIZATION

Effective: August 4, 2006 Revised: August 3, 2012

Delete Note 8/ of Article 1004.01(c) and replace Article 1004.02(d)(1) with the following:

For the bridge superstructure and bridge approach slab, the Class BS concrete shall be uniformly graded.

This may be accomplished by using a uniformly graded single coarse aggregate, or by blending two or more coarse aggregate sizes. As a minimum for multiple coarse aggregate sizes, CA 7 or CA 11 shall be blended with CA 13, CA 14, or CA 16. The final single coarse aggregate or combined coarse aggregate gradation shall have minimum 45 percent and maximum 60 percent passing the 1/2 in. (12.5 mm) sieve. However, the Contractor may propose for approval by the Engineer an alternate uniformly graded concrete mixture using the information in the "Portland Cement Concrete Level III Technician Course – Manual of Instructions for Design of Concrete Mixtures".

Concrete Superstructures Aggregate Optimization will not be paid for separately, but shall be considered as included in the unit cost of CONCRETE SUPERSTRUCTURES.

# PCC QC/QA ELECTRONIC REPORT SUBMITTAL

Effective April 26, 2013

The Contractor's QC personnel shall be responsible for electronically submitting PRO and IND MI 654 Air, Slump, Quantity and PRO MI 655 PCC Strength Reports to the Department. The format for the electronic submittals will be the PCC QC/QA reporting program, which will be

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

provided by the Department. Microsoft Office 2007 or newer is required for this program which must be provided by the Contractor.

# PCC AUTOMATIC BATCHING EQUIPMENT

Effective April 23, 2010

Portland cement concrete provided shall be produced from batch plants that conform to the requirements of Article 1103.03 (a) and (b) of the Standard Specifications for Road and Bridge Construction. Semi-automatic batching will not be allowed.

In addition, the batching plant shall be a computerized plant interfaced with a printer and shall print actual batch weights, added water, tempering water, mixing time, and amount of each additive per batch. At the discretion of the Engineer, archived electronic versions of batch proportions will be acceptable. Truck delivery tickets will still be required as per Article 1020.11 (a)(7).

# CORRUGATED STRUCTURAL PLATE ARCH

This work shall consist of furnishing and installing a corrugated structural plate arch according to the dimensions shown on the plans. Specific effective flow areas shall meet the requirements shown on the plans.

The design and installation shall conform to AASHTO LRFD Bridge Design Specifications "Buried Structures and Tunnel Liners", Section 12.8, "Long Span Structural Plate Structures", and AASHTO LRFD Bridge Construction Specifications, Section 26, "Metal Culverts", and Section 8, "Concrete Structures."

Materials for corrugated metal structural plate for pipe arches shall conform to the requirements of the Standard Specifications for structural Plate Pipe – Arches AASHTO M-167. Bolts and nuts shall meet the provisions of ASTM A 449, Type 1 and ASTM A 563, Grade C, Respectively. The steel anchor bolts shall conform to ASTM A 307, Grade A.

Shop drawings for shall be submitted according to Article 105.04 of the Standard Specifications. The supplier selected by the Contractor shall submit complete design calculations and shop drawings, prepared, sealed and certified for structural adequacy based on AASHTO LRFD design by an Illinois Licensed Structural Engineer, for approval by the Engineer.

The Contractor shall be responsible for diverting the water from the construction area using a method meeting the approval of the Engineer. The cost of diverting the water shall be considered as included in the contract unit price bid for the arch structure being constructed and no additional compensation will be allowed.

The corrugated Structural Plate Arch shall be installed on concrete footings per the design shown in the plans in strict accordance with the manufacturer's specifications, instructions and approved shop drawings. The corrugated structural plate arch shall be placed according to applicable requirements of Article 541.06(b) of the Standard Specifications. Bolts shall be tightened using an applied torque meeting the manufacturer's specification.

Shoring shall be placed inside the arch to prevent deformation until backfilling is complete. Backfilling and shape monitoring shall be per the manufacturers' specifications. A 30 mil PVC plastic membrane 10 feet wider than the arch shall be supplied and installed to prevent de-icing salts and chemicals from reaching the arch. The membrane shall be a single sheet or shall be overlapped and fused to form a water tight seam. A 4" perforated PVC drain pipe shall be placed on each side of the arch as shown on the details. The drain pipe shall slope no less than 1.0% and shall outlet through the downstream wingwalls.

Anchor bolts with double nuts shall be installed on both ends at the locations along each headwall per the details shown in the plans.

Prior approval by the Department for the structural feasibility and adequacy of proprietary systems will enhance the approval process of the final structure design but in no case shall relieve the Contractor of the design or QC/QA requirements stated herein. The following proprietary systems have been previously approved for the structural feasibility and adequacy only:

- 1) Contech Construction Products, Inc.
- 2) Illowa Culvert and Supply
- Metal Culverts, Inc.

The system chosen by the contractor shall provide a hydraulically equivalent waterway opening to that specified on the plans. Evidence of equivalency shall also be provided in writing to the Engineer for review and approval prior to ordering any materials.

Any required concrete thrust blocks and reinforcement shall be installed per the manufacturer's design as shown on the approved shop drawings.

The excavation and backfill for the corrugated structural plate arch shall be according to Section 502 of the Standard Specifications and any additional backfilling requirements based on the supplier's design. All construction inspection and material certification necessary to verify these additional backfilling requirements in the field shall be the responsibility of the contractor. The rigid pavement over the structure must be in place before the arch is subjected to design loads. Heavy construction equipment that exceeds legal highway loads will not be allowed over the structure. Light construction equipment meeting the manufacturer's requirements may cross over the arch during the construction process only when the manufacturer's minimum cover over the structure is obtained. Final cover over the structure shall be at least the minimum shown on the manufacturer's shop drawings.

The manufacturer shall be required to be on-site to conduct a pre-construction conference. In addition, the manufacturer shall have a qualified representative on site during the assembly and installation process. The qualified representative shall be a licensed engineer and will be required to submit a resume prior to acceptance of bid.

**Method of Measurement**. Corrugated structural plate arch structures will be measured in feet. The overall length shall be measured from out to out of headwalls along the centerline of the span of the structure.

Basis of Payment. This work will be paid for at the contract unit price per foot for CORRUGATED STRUCTURAL PLATE ARCHES of the area specified.

Excavation and backfill required for the structure except as stated below will not be paid for separately.

Rock excavation will be paid for separately according to Article 502.13 of the Standard Specifications.

The method of connection between the corrugated structural plate arch and the concrete footings will not be paid for separately.

The reinforced concrete thrust blocks will not be paid for separately.

The cost of specified cast-in-place headwalls, wingwalls and footings will not be included in this item but will be paid for separately.



# DEPARTMENT OF THE ARMY CORPS OF ENGINEERS, ROCK ISLAND DISTRICT PO BOX 2004 CLOCK TOWER BUILDING ROCK ISLAND, ILLINOIS 61204-2004

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County


February 4, 2013

Operations Division

SUBJECT: CEMVR-OD-P-2010-0095-1

Mr. George Merkle Mauer-Stutz, Inc. 3116 N. Dries Lane, Suite 100 Peoria, Illinois 61604

Dear Mr. Merkle:



Your project is covered under Nationwide Permit No. 14, as published in the enclosed Fact Sheet No. 7 (IL), provided you meet the permit conditions for the nationwide permits, which are also included in the Fact Sheet. The Corps has also made a determination of no effect on federally threatened and endangered species or critical habitat. The Illinois Environmental Protection Agency (IEPA) also issued Section 401 Water Quality Certification with conditions for this nationwide permit. Please note these additional conditions included in the Fact Sheet. The decision regarding this action is based on information found in the administrative record, which documents the District's decision-making process, the basis for the decision, and the final decision.

You are encouraged to conduct your construction activities during a period of low flow. You are required to remove all fill material used as a temporary crossing to an upland, non-wetland site, to seed all disturbed areas with native grasses and to implement appropriate measures to insure that sediments are not introduced into waters of the United States during construction of this project.

Bank and shoreline protection shall consist of suitable clean materials, free from debris, trash, and other deleterious materials. If broken concrete is used as riprap, all reinforcing rods must be cut flush with the surface of the concrete, and individual pieces of concrete shall not exceed 3 feet in any dimension. Asphalt and broken concrete containing asphalt are specifically excluded from this authorization.

Debris created by any bridge repair activities must be captured before it enters the river or stream. If debris inadvertently falls into the river or stream, it must be promptly remove and disposed to an upland non-wetland location.

This verification is valid for two years from the date of this letter unless the nationwide permit is modified, reissued or revoked. It is your responsibility to remain informed of changes to the nationwide permit program. We will issue a public notice announcing any changes if and when they occur. Furthermore, if you commence or are under contract to commence this activity before the date the nationwide permit is modified or revoked, you will have twelve months from this date to complete your activity under the present terms and conditions of this nationwide permit. If your project plans change, you should contact our office for another determination.

Our office has completed a Preliminary Jurisdictional Determination concerning your project area. A Preliminary Jurisdictional Determination is not appealable, and it is applicable only to the permit program administered by the Corps of Engineers.

This authorization does not eliminate the requirement that you must still acquire other applicable Federal, state, and local permits. If you have not already coordinated your project with the Illinois Department of Natural Resources – Office of Water Resources, please contact them at 217/782-3863 to determine if a floodplain development permit is required for your project. You may contact the IEPA Facility Evaluation Unit at 217/782-3362 to determine whether additional authorizations are required from the IEPA. Please send any electronic correspondence to EPA.401.bow@illinois.gov.

This delineation/determination has been conducted to identify the limits of the Corps of Engineers' Clean Water Act jurisdiction for the particular site identified in this request. This delineation/determination may not be valid for the Food Security Act of 1985. If you or your tenant are USDA program participants, or anticipate participation in USDA programs, you should coordinate with the local office of the Natural Resources Conservation Service prior to starting work.

The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the free navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

You are required to complete and return the enclosed "Completed Work Certification" upon completion of your project, in accordance with General Condition No. 30 of the nationwide permits.

The Rock Island District Regulatory Branch is committed to providing quality and timely service to our customers. In an effort to improve customer service, please take a moment to complete the attached postcard and return it or go to our Customer Service Survey found on our web site at <a href="http://per2.nwp.usace.army.mil/survey.html">http://per2.nwp.usace.army.mil/survey.html</a>. (Be sure to select "Rock Island District" under the area entitled: Which Corps office did you deal with?)

Should you have any questions, please contact our Regulatory Branch by letter, or telephone me at 309/794-5369.

Sincerely,

Jeffrey W. Sniadach Project Manager

Enforcement Section

When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.

Transferee Date

**Enclosures** 

Copies Furnished: (w/o enclosures)

Mr. Mike Diedrichsen, P.E. Office of Water Resources IL Department of Natural Resources One Natural Resources Way Springfield, Illinois 62701-1271

Mr. Dan Heacock
Illinois Environmental Protection Agency
Watershed Management Section, Permit Sec. 15
1021 North Grand Avenue East
Post Office Box 19276
Springfield, Illinois 62794-9276
Epa.401.bow@illinois.gov (email copy)

U.S. Army Corps of Engineers Illinois Waterway Project Office 257 Grant Street Peoria, Illinois 61603

Mr. Peter J. Frantz/Ms. Kathy Ames Bureau of Location and Environment Illinois Department of Transportation Division of Highways 2300 South Dirksen Parkway Springfield, Illinois 62754

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

## COMPLETED WORK CERTIFICATION

Permit Number:	CEMVR-OD-P-2010-0095-1
Name of Permittee:	Pekin, Illinois
Date of Issuance:	February 4, 2013
Upon completion of t permit, sign this certif	he activity authorized by this permit and any mitigation required by the fication and return it to the following address:
	U.S. Army Engineer District, Rock Island ATTN: Regulatory Branch Clock Tower Building Post Office Box 2004 Rock Island, Illinois 61204-2004
Please note that your p of Engineers represent suspension, modification	ermitted activity is subject to a compliance inspection by a U.S. Army Corps ative. If you fail to comply with this permit, you are subject to permit on, or revocation.
I hereby certify that the accordance with the ter in accordance with the	e work authorized by the above reference permit has been completed in ms and conditions of the said permit, and required mitigation was completed permit conditions.
Signature of Permittee	Date

JS

FAU 6759 (Sheridan Road) Section 07-00176-00-BR City of Pekin Tazewell County

## STATUS OF UTILITIES/UTILITIES TO BE ADJUSTED

The following utilities are located within the project limits. For relocations, the utility companies have provided the estimated dates.

Name, Contact, Address and Phone Number of Utility	Туре	Location	Relocation Needed	Estimated  Date Relocation  Completed
Christian Volz Illinois American Water 7500 N. Harker Drive Peoria, IL 61615 Tel. (309)566-4114 Fax (309)673-8495 Cell (309)222-4103 Christian.volz@amwater.com	Water	U.G.	No	Work Around During Construction
Darrell Schmidt Centurylink 416 Margaret St. Pekin, IL 61554 Tel. (309)477-0284 Cell (309)477-0255 Darrell.schmidt@centurylink.co.	Telephone <u>m</u>	U.G./ Attached to Structure	Yes	Before Construction

The above represents the best information of the COUNTY and is only included for the convenience of the bidder. The applicable provisions of Recurring Special Provisions LRS6, and Articles 105.07, 107.20, 107.31 and 108.02 of the Standard Specifications for Road and Bridge Construction shall apply.

The estimated utility relocation dates should be part of the progress schedule submitted by the Contractor. If any utility adjustments or relocations have not been completed by the above dates specified and when required by the Contractor's operations after these dates, the Contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's critical path schedule is affected.

## MECHANICALLY STABILIZED EARTH RETAINING WALLS

Effective: February 3, 1999 Revised: July 26, 2013

<u>Description</u>. This work shall consist of preparing the design, furnishing the materials, and constructing the mechanically stabilized earth (MSE) retaining wall to the lines, grades and dimensions shown in the contract plans and as directed by the Engineer.

General. The MSE wall consists of a concrete leveling pad, precast concrete face panels, a soil reinforcing system, select fill and concrete coping (when specified). The soil reinforcement shall have sufficient strength, quantity, and pullout resistance, beyond the failure surface within the select fill, as required by design. The material, fabrication, and construction shall comply with this Special Provision and the requirements specified by the supplier of the wall system selected by the Contractor for use on the project.

The MSE retaining wall shall be one of the following pre-approved wall systems:

Company Name: Wall System

Earth Tec International, LLC: EarthTrac HA

Sanders Pre-Cast Concrete Systems Company: Sanders MSE Wall

Shaw Technologies: Strengthened Soil

Sine Wall, LLC: Sine Wall

SSL Construction Products: MSE Plus

Vist-A-Wall Systems, LLC: Vist-A-Wall

Tensar Earth Technologies: ARES Wall

The Reinforced Earth Company: GeoMega System

The Reinforced Earth Company: Reinforced Earth

The Reinforced Earth Company: Retained Earth

Tricon Precast: Tricon Retained Soil

Tricon Precast: Tri-Web Retained Soil

Pre-approval of the wall system does not include material acceptance at the jobsite.

<u>Submittals</u>. The wall system supplier shall submit complete design calculations and shop drawings to the Engineer according to Article 1042.03(b) of the Standard Specifications no later than 90 days prior to beginning construction of the wall. No work or ordering of materials for the structure shall be done by the Contractor until the submittal has been approved in writing by the Engineer. All submittals shall be sealed by an Illinois Licensed Structural Engineer and shall include all details, dimensions, quantities and cross sections necessary to construct the wall and shall include, but not be limited to, the following items:

- Plan, elevation and cross section sheet(s) for each wall showing the following:
  - (1) A plan view of the wall indicating the offsets from the construction centerline to the face of the wall at all changes in horizontal alignment. The plan view shall show the limits of soil reinforcement and stations where changes in length and/or size of

- reinforcement occur. The centerline shall be shown for all drainage structures or pipes behind or passing through and/or under the wall.
- (2) An elevation view of the wall indicating the elevations of the top of the panels. These elevations shall be at or above the top of exposed panel line shown on the contract plans. This view shall show the elevations of the top of the leveling pads, all steps in the leveling pads and the finished grade line. Each panel type, the number, size and length of soil reinforcement connected to the panel shall be designated. The equivalent uniform applied service (unfactored) nominal bearing pressure shall be shown for each designed wall section.
- (3) A listing of the summary of quantities shall be provided on the elevation sheet of each wall.
- (4) Typical cross section(s) showing the limits of the reinforced select fill volume included within the wall system, soil reinforcement, embankment material placed behind the select fill, precast face panels, and their relationship to the right-of-way limits, excavation cut slopes, existing ground conditions and the finished grade line.
- (5) All general notes required for constructing the wall.
- (b) All details for the concrete leveling pads, including the steps, shall be shown. The top of the leveling pad shall be located at or below the theoretical top of the leveling pad line shown on the contract plans. The theoretical top of leveling pad line shall be 3.5 ft. (1.1 m) below finished grade line at the front face of the wall, unless otherwise shown on the plans.
- (c) Where concrete coping or barrier is specified, the panels shall extend up into the coping or barrier as shown in the plans. The top of the panels may be level or sloped to satisfy the top of exposed panel line shown on the contract plans. Cast-in-place concrete will not be an acceptable replacement for panel areas below the top of exposed panel line. As an alternative to cast in place coping, the Contractor may substitute a precast coping, the details of which must be included in the shop drawings and approved by the Engineer.
- (d) All panel types shall be detailed. The details shall show all dimensions necessary to cast and construct each type of panel, all reinforcing steel in the panel, and the location of soil reinforcement connection devices embedded in the panels. These panel embed devices shall not be in contact with the panel reinforcement steel.
- (e) All details of the wall panels and soil reinforcement placement around all appurtenances located behind, on top of, or passing through the soil reinforced wall volume such as parapets with anchorage slabs, coping, foundations, and utilities etc. shall be clearly indicated. Any modifications to the design of these appurtenances to accommodate a particular system shall also be submitted.

- (f) When specified on the contract plans, all details of architectural panel treatment, including color, texture and form liners shall be shown.
- (g) The details for the connection between concrete panels, embed devices, and soil reinforcement shall be shown.
- (h) When pile sleeves are specified, the pile sleeve material, shape, and wall thickness shall be submitted to the Engineer for approval. It shall have adequate strength to withstand the select fill pressures without collapse until after completion of the wall settlement. The annulus between the pile and the sleeve shall be as small as possible while still allowing it to be filled with loose dry sand after wall erection.

The initial submittal shall include three sets of shop drawings and one set of calculations. One set of drawings will be returned to the Contractor with any corrections indicated. After approval, the Contractor shall furnish the Engineer with ten (10) sets of corrected plan prints for distribution by the Department. No work or ordering of materials for the structure shall be done until the submittal has been approved by the Engineer.

<u>Materials</u>. The MSE walls shall conform to the supplier's standards as previously approved by the Department, and the following:

- (a) The soil reinforcing system, which includes the soil reinforcement, and all connection devices, shall be according to the following:
  - (1) <u>Inextensible Soil Reinforcement</u>. Steel reinforcement shall be according ASTM A 572 Grade 65 (450), ASTM A 1011 or ASTM A 463 Grade 50 (345). The steel strips shall be either epoxy coated, aluminized Type 2, or galvanized. Epoxy coatings shall be according to Article 1006.10(a)(2), except the minimum thickness of epoxy coating shall be 18 mils (457 microns). No bend test will be required. Aluminized Type 2-100 shall be according to ASTM A 463. Galvanizing shall be according to AASHTO M 111 or ASTM A 653 with touch up of damage according to ASTM A 780.
  - (2) <u>Extensible Soil Reinforcement</u>. Geosynthetic reinforcement shall be monolithically fabricated from virgin high density polyethylene (HDPE) or high tenacity polyester (HTPET) resins having the following properties verified by mill certifications:

Property for Geosynthetic Reinforcement Minimum Tensile Strength	<u>Value</u> **	<u>Test</u> ASTM D 6637
------------------------------------------------------------------	--------------------	----------------------------

<sup>\*\*</sup> as specified in the approved design calculations and shown on the shop drawings.

Property for HDPE Melt Flow Rate (g/cm) Density (g/cu m) Carbon Black	<u>Value</u> 0.060 – 0.150 0.941 – 0.965 2% (min)	<u>Test</u> ASTM D 1238, Procedure B ASTM D 792 ASTM D 4218
-----------------------------------------------------------------------	------------------------------------------------------------	----------------------------------------------------------------------

Property for HTPET Carboxyl End Group (max) (mmol/kg) Molecular Weight (Mn)	<u>Value</u> <30 >25,000	<u>Test</u> GRI-GG7 GRI-GG8
3 ()	~25,000	GRI-GG8

- (3) <u>Panel Embed/Connection Devices.</u> Panel embeds and connection devices shall be according to the following.
  - a. Metallic panel embed/connection devices and connection hardware shall be galvanized according to AASHTO M 232 and shall be according to the following.

Mesh and Loop Embeds ASTM A 706 (A 706M)

Tie Strip Embeds AASHTO M 270/M 270M Grade 50 (345) or ASTM A 1011 HSLAS Grade 50 (345) Class 2

b. Non metallic panel embed/connection devices typically used with geosynthetic soil reinforcement shall be manufactured from virgin or recycled polyvinyl chloride having the following properties:

Property for Polyvinyl Chloride Heat Deflection Temperature (°F) Notched IZOD 1/8 inch @ 73°F (ft-lb/in) Coefficient of Linear Exp. (in/in/°F) Hardness, Shore D	<u>Value</u> 155 - 164 4 – 12 3.5 – 4.5 79	<u>Test</u> ASTM D 1896 ASTM D 256 ASTM D 696 ASTM D 2240
------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------	-----------------------------------------------------------------------

Property for Polypropylene Melt Flow Rate (g/cm) Density (g/cu m)	<u>Value</u> 0.060 – 0.150 0.88 – 0.92	<u>Test</u> ASTM D 1238, Procedure B ASTM D 792
-------------------------------------------------------------------	----------------------------------------------	-------------------------------------------------------

- (b) The select fill, defined as the material placed in the reinforced volume behind the wall, shall be according to Sections 1003 and 1004 of the Standard Specifications and the following:
  - (1) Select Fill Gradation. Either a coarse aggregate or a fine aggregate may be used. For coarse aggregate, gradations CA 6 thru CA 16 may be used. If an epoxy coated reinforcing is used, the coarse aggregate gradations shall be limited to CA 12 thru CA 16. For fine aggregate, gradations FA 1, FA 2, or FA 20 may be used.
  - (2) Select Fill Quality. The coarse or fine aggregate shall have a maximum sodium sulfate (Na<sub>2</sub>SO<sub>4</sub>) loss of 15 percent according to Illinois Modified AASHTO T 104.
  - (3) Select Fill Internal Friction Angle. The effective internal friction angle for the coarse or fine aggregate shall be a minimum 34 degrees according to AASHTO T 236 on samples compacted to 95 percent density according to Illinois Modified AASHTO T 99. The AASHTO T 296 test with pore pressure measurement may be used in lieu of AASHTO T

236. If the vendor's design uses a friction angle higher than 34 degrees, as indicated on the approved shop drawings, this higher value shall be taken as the minimum required.

- (4) Select Fill and Steel Reinforcing. When steel reinforcing is used, the select fill shall meet the following requirements.
  - a. The pH shall be 5.0 to 10.0 according to Illinois Modified AASHTO T 289.
  - b. The resistivity according to Illinois Modified AASHTO T 288 shall be greater than 3000 ohm centimeters for epoxy coated and galvanized reinforcement, and 1500 ohm centimeters for Aluminized Type 2. However, the resistivity requirement is not applicable to CA 7, CA 8, CA 11, CA 13, CA 14, CA 15, and CA 16.
  - c. The chlorides shall be less than 100 parts per million according to Illinois Modified AASHTO T 291 or ASTM D 4327. For either test, the sample shall be prepared according to Illinois Modified AASHTO T 291.
  - d. The sulfates shall be less than 200 parts per million according to Illinois Modified AASHTO T 290 or ASTM D 4327. For either test, the sample shall be prepared according to Illinois Modified AASHTO T 290.
  - e. The organic content shall be a maximum 1.0 percent according to Illinois Modified AASHTO T 267.
- (5) Select Fill and Geosynthetic Reinforcing. When geosynthetic reinforcing is used, the select fill pH shall be 4.5 to 9.0 according to Illinois Modified AASHTO T 289.
- (6) Test Frequency. Prior to start of construction, the Contractor shall provide internal friction angle and pH test results, to show the select fill material meets the specification requirements. In addition, resistivity, chlorides, sulfates, and organic content test results will be required if steel reinforcing is used. The laboratory performing the Illinois Modified AASHTO T 288 test shall be approved by the Department according to the current Bureau of Materials and Physical Research Policy Memorandum "Minimum Laboratory Requirements for Resistivity Testing". All test results shall not be older than 12 months. In addition, a sample of select fill material will be obtained for testing and approval by the Department. Thereafter, the minimum frequency of sampling and testing by the department at the jobsite will be one per 40,000 tons (36,300 metric tons) of select fill material. Testing to verify the internal friction angle will be required when the wall design utilizes a minimum effective internal friction angle greater than 34 degrees, or when crushed coarse aggregate is not used.
- (c) The embankment material behind the select fill shall be according to Section 202 and/or Section 204. An embankment unit weight of 120 lbs/cubic foot (1921 kg/cubic meter) and an effective friction angle of 30 degrees shall be used in the wall system design, unless otherwise indicated on the plans.
- (d) The geosynthetic filter material used across the panel joints shall be either a non-woven needle punch polyester or polypropylene or a woven monofilament polypropylene with a minimum width of 12 in. (300 mm) and a minimum non-sewn lap of 6 in. (150 mm) where

- (e) The bearing pads shall be rubber, neoprene, polyvinyl chloride, or polyethylene of the type and grade as recommended by the wall supplier.
- (f) All precast panels shall be manufactured with Class PC concrete according to Section 504, Article 1042.02, Article 1042.03, and the following requirements:
  - (1) The minimum panel thickness shall be 5 1/2 in. (140 mm).
  - (2) The minimum reinforcement bar cover shall be 1 1/2 in. (38 mm).
  - (3) The panels shall have a ship lap or tongue and groove system of overlapping joints between panels designed to conceal joints and bearing pads.
  - (4) The panel reinforcement shall be according to Article 1006.10(a)(2) or 1006.10(b)(1) except the welded wire fabric shall be epoxy coated according to ASTM A884.
  - (5) All dimensions shall be within 3/16 in. (5 mm).
  - (6) Angular distortion with regard to the height of the panel shall not exceed 0.2 inches in 5 ft (5 mm in 1.5 m).
  - (7) Surface defects on formed surfaces measured on a length of 5 ft. (1.5 m) shall not be more than 0.1 in. (2.5 mm).
  - (8) The panel embed/connection devices shall be cast into the facing panels with a tolerance not to exceed 1 in. (25 mm) from the locations specified on the approved shop drawings.

Unless specified otherwise, concrete surfaces exposed to view in the completed wall shall be finished according to Article 503.15(a). The back face of the panel shall be roughly screeded to eliminate open pockets of aggregate and surface distortions in excess of 1/4 in. (6 mm).

<u>Design Criteria</u>. The design shall be according to the appropriate AASHTO Design Specifications noted on the plans for Mechanically Stabilized Earth Walls except as modified herein. The wall supplier shall be responsible for all internal stability aspects of the wall design and shall supply the Department with computations for each designed wall section. The analyses of settlement, bearing capacity and overall slope stability will be the responsibility of the Department.

External loads, such as those applied through structure foundations, from traffic or railroads, slope surcharge etc., shall be accounted for in the internal stability design. The presence of all appurtenances behind, in front of, mounted upon, or passing through the wall volume such as drainage structures, utilities, structure foundation elements or other items shall be accounted for in the internal stability design of the wall.

The design of the soil reinforcing system shall be according to the applicable AASHTO or AASHTO LRFD Design Specifications for "Inextensible" steel or "Extensible" geosynthetic reinforcement criteria. The reduced section of the soil reinforcing system shall be sized to allowable stress levels at the end of a 75 year design life.

Steel soil reinforcing systems shall be protected by one of the following; epoxy coating, galvanizing or aluminizing. The design life for epoxy and aluminizing shall be assumed to be 16 years. The corrosion protection for the balance of the 75 year total design life shall be provided using a sacrificial steel thickness computed for all exposed surfaces according to the applicable AASHTO or AASHTO LRFD Design Specifications.

Geosynthetic soil reinforcing systems shall be designed to account for the strength reduction due to long-term creep, chemical and biological degradation, as well as installation damage.

To prevent out of plane panel rotations, the soil reinforcement shall be connected to the standard panels in at least two different elevations, vertically spaced no more than 30 in. (760 mm) apart.

The panel embed/soil reinforcement connection capacity shall be determined according to the applicable AASHTO or AASHTO LRFD Design Specifications.

The factor of safety for pullout resistance in the select fill shall not be less than 1.5, based on the pullout resistance at 1/2 in. (13 mm) deformation. Typical design procedures and details, once accepted by the Department, shall be followed. All wall system changes shall be submitted in advance to the Department for approval.

For aesthetic considerations and differential settlement concerns, the panels shall be erected in such a pattern that the horizontal panel joint line is discontinuous at every other panel. This shall be accomplished by alternating standard height and half height panel placement along the leveling pad. Panels above the lowest level shall be standard size except as required to satisfy the top of exposed panel line shown on the contract plans.

At locations where the plans specify a change of panel alignment creating an included angle of 150 degrees or less, precast corner joint elements will be required. This element shall separate the adjacent panels by creating a vertical joint secured by means of separate soil reinforcement.

Isolation or slip joints, which are similar to corner joints in design and function, may be required to assist in differential settlements at locations indicated on the plans or as recommended by the wall supplier. Wall panels with areas greater than 30 sq. ft. (2.8 sq. m) may require additional slip joints to account for differential settlements. The maximum standard panel area shall not exceed 60 sq. ft. (5.6 sq. m).

<u>Construction.</u> The Contractor shall obtain technical assistance from the supplier during wall erection to demonstrate proper construction procedures and shall include any costs related to this technical assistance in the unit price bid for this item.

The foundation soils supporting the structure shall be graded for a width equal to or exceeding the length of the soil reinforcement. Prior to wall construction, the foundation shall be compacted with a smooth wheel vibratory roller. Any foundation soils found to be unsuitable shall be removed and replaced, as directed by the Engineer, and shall be paid for separately according to Section 202.

When structure excavation is necessary, it shall be made and paid for according to Section 502 except that the horizontal limits for structure excavation shall be from the rear limits of the soil reinforcement to a vertical plane 2 ft. (600 mm) from the finished face of the wall. The depth shall be from the top of the original ground surface to the top of the leveling pad. The additional excavation necessary to place the concrete leveling pad will not be measured for payment but shall be included in this work.

The concrete leveling pads shall have a minimum thickness of 6 in. (150 mm) and shall be placed according to Section 503.

As select fill material is placed behind a panel, the panel shall be maintained in its proper inclined position according to the supplier specifications and as approved by the Engineer. Vertical tolerances and horizontal alignment tolerances shall not exceed 3/4 in. (19 mm) when measured along a 10 ft. (3 m) straight edge. The maximum allowable offset in any panel joint shall be 3/4 in. (19 mm). The overall vertical tolerance of the wall, (plumbness from top to bottom) shall not exceed 1/2 in. per 10 ft. (13 mm per 3 m) of wall height. The precast face plan offset at any location to insure that they are located within 1 in. (25 mm) from the contract this tolerance may cause the Engineer to require the Contractor to disassemble and re-erect the affected portions of the wall. A 3/4 in. (19 mm) joint separation shall be provided between all adjacent face panels to prevent direct concrete to concrete contact. This gap shall be maintained by the use of bearing pads and/or alignment pins.

The back of all panel joints shall be covered by a geotextile filter material attached to the panels with a suitable adhesive. No adhesive will be allowed directly over the joints.

The select fill and embankment placement shall closely follow the erection of each lift of panels. At each soil reinforcement level, the fill material should be roughly leveled and compacted before placing and attaching the soil reinforcing system. The soil reinforcement and the maximum lift thickness shall be placed according to the supplier's recommended procedures except, the lifts for select fill shall not exceed 10 in. (255 mm) loose measurement or as approved by the Engineer. Embankment shall be constructed according to Section 205.

At the end of each day's operations, the Contractor shall shape the last level of select fill to permit runoff of rainwater away from the wall face. Select fill shall be compacted according to the project specifications for embankment except the minimum required compaction shall be 95 percent of maximum density as determined by Illinois Modified AASHTO T 99. Select fill compaction shall be accomplished without disturbance or distortion of soil reinforcing system and panels. Compaction in a strip 3 ft. (1 m) wide adjacent to the backside of the panels shall

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

be achieved using a minimum of 3 passes of a light weight mechanical tamper, roller or vibratory system. The Engineer will perform one density test per 5000 cu yd (3800 cu m) and not less than one test per 2 ft (0.6 m) of lift.

<u>Method of Measurement</u>. Mechanically Stabilized Earth Retaining Wall will be measured for payment in square feet (square meters). The MSE retaining wall will be measured from the top of exposed panel line to the theoretical top of leveling pad line for the length of the wall as shown on the contract plans.

<u>Basis of Payment</u>. This work, including placement of the select fill within the soil reinforced wall volume shown on the approved shop drawings, precast face panels, soil reinforcing system, concrete leveling pad and accessories will be paid for at the contract unit price per square foot (square meter) for MECHANICALLY STABILIZED EARTH RETAINING WALL.

Concrete coping when specified on the contract plans will be included for payment in this work. Other concrete appurtenances such as anchorage slabs, parapets, abutment caps, etc. will not be included in this work, but will be paid for as specified elsewhere in this contract, unless otherwise noted on the plans.

Excavation necessary to place the select fill for the MSE wall shall be paid for as STRUCTURE EXCAVATION and/or ROCK EXCAVATION FOR STRUCTURES as applicable, according to Section 502.

Fill placed within the foot print of the reinforced soil mass, above the top layer of soil reinforcement and below the bottom of the subgrade or top soil, shall be included in the cost of the MSE wall.

Embankment placed outside of the select fill volume will be measured and paid for according to Sections 202 and/or 204 as applicable.

### PIPE UNDERDRAINS FOR STRUCTURES

Effective: May 17, 2000 Revised: January 22, 2010

<u>Description</u>. This work shall consist of furnishing and installing a pipe underdrain system as shown on the plans, as specified herein, and as directed by the Engineer.

Materials. Materials shall meet the requirements as set forth below:

The perforated pipe underdrain shall be according to Article 601.02 of the Standard Specifications. Outlet pipes or pipes connecting to a separate storm sewer system shall not be perforated.

The drainage aggregate shall be a combination of one or more of the following gradations, FA1, FA2, CA5, CA7, CA8, CA11, or CA13 thru 16, according to Sections 1003 and 1004 of the Standard Specifications.

The fabric surrounding the drainage aggregate shall be Geotechnical Fabric for French Drains according to Article 1080.05 of the Standard Specifications.

<u>Construction Requirements.</u> All work shall be according to the applicable requirements of Section 601 of the Standard Specifications except as modified below.

The pipe underdrains shall consist of a perforated pipe drain situated at the bottom of an area of drainage aggregate wrapped completely in geotechnical fabric and shall be installed to the lines and gradients as shown on the plans.

Method of Measurement. Pipe Underdrains for Structures shall be measured for payment in feet (meters), in place. Measurement shall be along the centerline of the pipe underdrains. All connectors, outlet pipes, elbows, and all other miscellaneous items shall be included in the measurement. Concrete headwalls shall be included in the cost of Pipe Underdrains for Structures, but shall not be included in the measurement for payment.

<u>Basis of Payment.</u> This work will be paid for at the contract unit price per foot (meter) for PIPE UNDERDRAINS FOR STRUCTURES of the diameter specified. Furnishing and installation of the drainage aggregate, geotechnical fabric, forming holes in structural elements and any excavation required, will not be paid for separately, but shall be included in the cost of the pipe underdrains for structures.

### **BRIDGE DECK CONSTRUCTION**

Effective: October 22, 2013

## Revise the Second Paragraph of Article 503.06(b) to read as follows.

"When the Contractor uses cantilever forming brackets on exterior beams or girders, additional requirements shall be as follows."

## Revise Article 503.06(b)(1) to read as follows.

"(1) Bracket Placement. The spacing of brackets shall be per the manufacture published design specifications for the size of the overhang and the construction loads anticipated. The resulting force of the leg brace of the cantilever bracket should bear on the web. In addition, for beams or girders where the rail supporting the finishing machine is supported outside the exterior girder by a distance of more than half the girder depth, the bracket should bear on the web within 6 inches (150 mm) from the top of the bottom flange of the girder."

## Revise Article 503.06(b)(2) to read as follows.

"(2) Beam Ties. The top flange of the beams or girders supporting the cantilever forming brackets shall be tied to the bottom flange of the next interior beam. The ties shall be spaced at 4 ft (1.2 m) centers maximum. Ties shall be a minimum of 1/4 inch (6 mm) diameter threaded rod with a mechanism for drawing the tie taut. The ties shall utilize hanger brackets or clips which hook onto the flange without the assistance of welding or drilling to the any part of the beam."

## Revise Article 503.06(b)(3) to read as follows.

"(3) Beam Blocks. Suitable beam blocks of 4 x 4 (100 x 100 mm) timbers or metal structural shapes of equivalent strength or better, acceptable to the Engineer, shall be wedged between the webs of the two beams tied together, within 6 inches (150 mm) of the leg brace of the cantilever brackets is required to but cannot be transmitted to the web within 6 inches (150 mm) of the bottom flange, then additional blocking shall be utilized resulting force to within 6 inches (150 mm) of the bottom flange of the next interior beam or girder."

## Delete the last paragraph of Article 503.06(b).

## Revise the third paragraph of Article 503.16 to read as follows.

"Fogging equipment shall be in operation unless the evaporation rate is less than 0.1 Lb/sq ft/hour (0.5kg/sq m/hour) and the Engineer gives permission to stop. The evaporation rate shall be determined according to the following formula.

$$E = (T_c^{2.5} - rT_a^{2.5})(1 + 0.4V)x10^{-6} (English)$$
  

$$E = 5[(T_c + 18)^{2.5} - r(T_a + 18)^{2.5}](V + 4)x10^{-6} (Metric)$$

#### Where:

E = Evaporation Rate, lb/ft2/h (kg/sq m/h)

 $T_c$  = Concrete temperature, °F (°C)

 $T_a$  = Air temperature, °F (°C)

r = Relative humidity in percent/100

V = Wind velocity, mph (km/h)

The Contractor shall provide temperature, relative humidity, and wind speed measuring equipment. Fogging equipment shall be to adequate to reach or cover the entire pour from behind the finishing machine or vibrating screed to the point of curing covering application, and shall be operated in a manner which shall not accumulate water on the deck until the curing covering has been placed."

## Revise the first sentence of the third paragraph of Article 503.16(a)(1) to read as follows.

"At the Contractors option, a vibrating screed may be used in lieu of the finishing machine for superstructures with a pour width less than 24 ft.(7.3 m)"

Delete the fifth paragraph of 503.16(a)(1).

Replace the second sentence of the first paragraph of Article 1020.13(a)(5) with the follows.

"Cotton mats in poor condition will not be allowed. The cotton mats shall be placed in a manner which will not create indentations greater than 1/4 inch (6 mm) in the concrete surface. Minor marring of the surface is tolerable and is secondary to the importance of timely curing."

## Revise the Article 1020.14(b) to read as follows.

"(b) Concrete in Structures. Concrete may be placed when the air temperature is above 40 °F (4 °C) and rising, and concrete placement shall stop when the falling temperature reaches 45 °F (7 °C) or below, unless otherwise approved by the Engineer.

- (1) Superstructure Concrete. For concrete in superstructures the Contractor shall schedule placing and finishing of the concrete during hours in which the ambient Air temperature will be lower than 85 °F (30 °C). The temperature of the concrete immediately before placement shall be a minimum of 50 °F (10 °C) and a maximum of 85 °F (30 °C).
- (2) Non-Superstructure Concrete. The temperature of the concrete immediately before placement shall be a minimum of 50 °F (10 °C) and a maximum of 90 °F (32 °C). If concrete is pumped, the temperature of the concrete at point of placement shall be a minimum of 50 °F (10 °C) and a maximum of 90 °F (32 °C).

When insulated forms are used according to Article 1020.13(d)(1), the maximum temperature of the concrete mixture immediately before placement shall be 80  $^{\circ}$ F (25  $^{\circ}$ C).

When concrete is placed in contact with previously placed concrete, the temperature of the freshly mixed concrete may be increased to 80 °F (25 °C) by the Contractor to offset anticipated heat loss."

## Revise Article 1103.13(a) to read as follows.

"(a) Bridge Deck. The finishing machine shall be equipped with: (1) a mechanical strike off device; (2) either a rotating cylinder(s) or a longitudinal oscillating screed which transversely finishes the surface of the concrete. The Contractor may attach other equipment to the finishing machine to enhance the final finish when approved by the Engineer. The finishing machine shall produce a floor surface of uniform texture, free from porous areas, and with the required surface smoothness.

The finishing machine shall be operated on rails or other supports that will not deflect under the applied loads. The maximum length of rails support on top of existing beams and within the pour shall be 10 ft (3 m). The supports shall be adjustable for elevation and shall be completely in place for the full length of the area to be finished. The supports shall be approved by the Engineer before placing of the concrete is started."

### Revise Article 1103.17(k) to read as follows.

"(k) Fogging Equipment. Fogging equipment shall be hand held fogging equipment for humidity Control. The equipment shall be capable of atomizing water to produce a fog blanket by the use of pressure 2500 psi minimum (17.24 MPa) and an industrial fire hose fogging nozzle or equivalent. Fogging equipment attached to the finishing machine will not be permitted."

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR

LR Giffy of Pekin
Page for Security

State of Illinois
Department of Transportation
Bureau of Local Roads and Streets

#### SPECIAL PROVISION FOR COOPERATION WITH UTILITIES

Effective: January 1, 1999 Revised: January 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

Replace Article 105.07 of the Standard Specifications with the following:

"105.07 Cooperation with Utilities. The adjustment of utilities consists of the relocation, removal, replacement, rearrangements, reconstruction, improvement, disconnection, connection, shifting, new installation or altering of an existing utility facility in any manner.

When the plans or special provisions include information pertaining to the location of underground utility facilities, such information represents only the opinion of the Department as to the location of such utilities and is only included for the convenience of the bidder. The Department assumes no responsibility in respect to the sufficiency or the accuracy of the information shown on the plans relative to the location of the underground utility facilities.

Utilities which are to be adjusted shall be adjusted by the utility owner or the owner's representative or by the Contractor as a contract item. Generally, arrangements for adjusting existing utilities will be made by the Department prior to project construction; however, utilities will not necessarily be adjusted in advance of project construction and, in some cases, utilities will not be removed from the proposed construction limits. When utility adjustments must be performed in conjunction with construction, the utility adjustment work will be shown on the plans and/or covered by Special Provisions.

When the Contractor discovers a utility has not been adjusted by the owner or the owner's representative as indicated in the contract documents, or the utility is not shown on the plans or described in the Special Provisions as to be adjusted in conjunction with construction, the Contractor shall not interfere with said utility, and shall take proper precautions to prevent damage or interruption of the utility and shall promptly notify the Engineer of the nature and location of said utility.

All necessary adjustments, as determined by the Engineer, of utilities not shown on the plans or not identified by markers, will be made at no cost to the Contractor except traffic structures, light poles, etc., that are normally located within the proposed construction limits as hereinafter defined will not be adjusted unless required by the proposed improvement.

- (a) Limits of Proposed Construction for Utilities Paralleling the Roadway. For the purpose of this Article, limits of proposed construction for utilities extending in the same longitudinal direction as the roadway, shall be defined as follows:
  - (1) The horizontal limits shall be a vertical plane, outside of, parallel to, and 600 mm (2 ft) distant at right angles from the plan or revised slope limits.
  - In cases where the limits of excavation for structures are not shown on the plans, the horizontal limits shall be a vertical plane 1.2 m (4 ft) outside the edges of structure footings or the structure where no footings are required.
  - (2) The upper vertical limits shall be the regulations governing the roadbed clearance for the specific utility involved.
  - (3) The lower vertical limits shall be the top of the utility at the depth below the proposed grade as prescribed by the governing agency or the limits of excavation, whichever is less.
- (b) Limits of Proposed Construction for Utilities Crossing the Roadway. For the purpose of this Article, limits of proposed construction for utilities crossing the roadway in a generally transverse direction shall be defined as follows:
  - (1) Utilities crossing excavations for structures that are normally made by trenching such as sewers, underdrains, etc. and all minor structures such as manholes, inlets, foundations for signs, foundations for traffic signals, etc., the limits shall be the space to be occupied by the proposed permanent construction unless otherwise required by the regulations governing the specific utility involved.
  - (2) For utilities crossing the proposed site of major structures such as bridges, sign trusses, etc., the limits shall be as defined above for utilities extending in the same general direction as the roadway.

The Contractor may make arrangements for adjustment of utilities outside of the limits of proposed construction provided the Contractor furnishes the Department with a signed agreement with the utility owner covering the adjustments to be made. The cost of any adjustments made outside the limits of proposed construction shall be the responsibility of the Contractor unless otherwise provided.

The Contractor shall request all utility owners to field locate their facilities according to Article 107.31. The Engineer may make the request for location from the utility after receipt of notice from the Contractor. On request, the Engineer will make an inspection to verify that the utility company has field located its facilities, but will not assume responsibility for the accuracy of such work. The Contractor shall be responsible for maintaining the excavations or markers provided by the utility owners. This field location procedure may be waived if the utility owner has stated in writing to the Department it is satisfied the construction plans are sufficiently accurate. If the utility owner does not submit such statement to the Department, and they do not field locate their facilities in both horizontal and vertical alignment, the Engineer will authorize the Contractor in writing to proceed to locate the facilities in the most economical and reasonable manner, subject to the approval of the Engineer, and be paid according to Article 109.04.



FAU 6759 (Sheridan Road)
Section 07-00176-00-BR

LR Giffy of Pekin
Page 3 01 3

The Contractor shall coordinate with any planned utility adjustment or new installation and the Contractor shall take all precautions to prevent disturbance or damage to utility facilities. Any failure on the part of the utility owner, or their representative, to proceed with any planned utility adjustment or new installation shall be reported promptly by the Contractor to the Engineer orally and in writing.

The Contractor shall take all necessary precautions for the protection of the utility facilities. The Contractor shall be responsible for any damage or destruction of utility facilities resulting from neglect, misconduct, or omission in the Contractor's manner or method of execution or nonexecution of the work, or caused by defective work or the use of unsatisfactory materials. Whenever any damage or destruction of a utility facility occurs as a result of work performed by the Contractor, the utility company will be immediately notified. The utility company will make arrangements to restore such facility to a condition equal to that existing before any such damage or destruction was done.

It is understood and agreed that the Contractor has considered in the bid all of the permanent and temporary utilities in their present and/or adjusted positions.

No additional compensation will be allowed for any delays, inconvenience, or damage sustained by the Contractor due to any interference from the said utility facilities or the operation of relocating the said utility facilities.

FAU 6759 (Sheridan Road) Section 07-00176-00-BR LR10714V of Pekin Page Toller County

State of Illinois
Department of Transportation
Bureau of Local Roads and Streets

#### SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

City of Pekin

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR

LR Gity of Pekin
Page Toll

State of Illinois
Department of Transportation
Bureau of Local Roads and Streets

# SPECIAL PROVISION FOR CONSTRUCTION AND MAINTENANCE SIGNS

Effective: January 1, 2004 Revised: June 1, 2007

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

701.14. Signs. Add the following paragraph to Article 701.14:

All warning signs shall have minimum dimensions of 1200 mm x 1200 mm (48" x 48") and have a black legend on a fluorescent orange reflectorized background, meeting, as a minimum, Type AP reflectivity requirements of Table 1091-2 in Article 1091.02.

### ABOVE GRADE INLET PROTECTION (BDE)

Effective: July 1, 2009 Revised: January 1, 2012

Add the following to Article 280.02 of the Standard Specifications:

Add the following paragraph after the second paragraph of Article 280.04(c) of the Standard Specifications:

"When above grade inlet filters are specified, they shall be of sufficient size to completely span and enclose the inlet structure. Prior to ordering materials, the Contractor shall determine the size of the various drainage structures being protected."

Add the following paragraph after the second paragraph of Article 280.08(d) of the Standard Specifications:

"Protection of drainage structures with rigid inlet protection assemblies will be paid for at the contract unit price per each for ABOVE GRADE INLET FILTERS."

Add the following to Article 1081.15 of the Standard Specifications:

- "(j) Above Grade Inlet Filters. Above grade inlet filters shall consist of a rigid polyethylene frame covered with a fitted geotextile filter. A clean, used fitted filter and a used rigid polyethylene frame in good condition meeting the approval of the Engineer may be substituted for new materials. Materials for the above grade inlet filter assembly shall be according to the following.
  - (1) Frame Construction. Frame shall be constructed of a high density polyethylene copolymer. The design of the frame shall allow the structure to fit completely over the sewer inlet. The frame shall be a minimum of 26 in. (650 mm) tall and the top of the frame shall be designed with an opening to allow large volumes of water to pass through under high flow events. The frame shall conform to the following requirements:

	Frame	
Material Property	Test Method	Value
Tensile Yield Strength	ASTM D 638	3600 psi (24.82 MPa)
Elongation at Break	ASTM D 638	>600%
Tensile-Impact Strength	ASTM D 1822	170 ft lb/sq in (230 J)
Brittleness Temperature	ASTM D 746	<-105°F (-76.11°C)
Environmental Stress Cracking	ASTM D 1693	>800 hours
Durometer Hardness,	ASTM D 2240	68

Shore A		T
Vicat Softening		
Temperature	ASTM D 1525	254°F (123.33°C)
Deflection Temperature	ASTM D 648	157°F (69.44°C)
Coefficient of Linear Thermal Expansion	ASTM D 696	7x10 <sup>-5</sup> in/in/°F (12.6x10 <sup>-5</sup> m/m/°C)
Bulk Density	ASTM D 1895	37 lbs/cu ft (592.7 kg/cu m)

(2) Fitted Geotextile Filter. The sides of the fitted geotextile filter shall be constructed of 100 percent continuous polyester needle-punched fabric. The filter shall be fabricated to provide a direct fit to the frame. The top of the filter shall integrate a coarse screening to allow large volumes of water to pass through in the event of heavy flows. This screening shall have a minimum apparent opening of 1/2 in. (13 mm). The filter shall have integrated anti-buoyancy pockets capable of holding no less than 3.0 cu ft (0.08 cu m) of stabilization material. Each filter shall have a label with the following information sewn to or otherwise permanently adhered to the outside: manufacturer's name, product name, and lot, model or serial number. The fitted geotextile filter shall conform to the following requirements:

Fitted Geotextile Filter				
Material Property	Test Method	Minimum Avg. Roll Value		
Weight	ASTM D 3776	3.0 oz/sq yd +/- 10%		
Grab Tensile Strength	ASTM D 4632	(71.1 grams/sq m) 80 lb min. (36.29 kg)		
Grab Tensile Elongation	ASTM D 4632	50%		
Bursting Strength	ASTM D 3786	150 psi min. (1.03 MPa)		
Puncture Resistance	ASTM D 4833	50 lb min. (22.68 kg)		
Trapezoid Tearing Strength	ASTM D 4533	30 lb min. (13.61 kg)		
Apparent Opening Size	ASTM D 4751	Sieve No. 70 (0.212 mm)		
Permittivity	ASTM D 4491	2.0/sec		
Water Permeability	ASTM D 4491	102 gal/min/sq ft (4150 liter/min/sq m)		
UV Resistance	ASTM D 4355	70% at 500 hours		

(3) Certification. The manufacturer shall furnish a certificate with each shipment of above grade inlet filter assemblies, stating the amount of product furnished and that the material complies with these requirements."

FAU 6759 (Sheridan Road) Section 07-00176-00-BR City of Pekin Tazewell County

## CONCRETE MIX DESIGN - DEPARTMENT PROVIDED (BDE)

Effective: January 1, 2012 Revised: January 1, 2014

For the concrete mix design requirements in Article 1020.05(a) of the Supplemental Specifications and Recurring Special Provisions, the Contractor has the option to request the Engineer determine mix design material proportions for Class PV, PP, RR, BS, DS, SC, and SI concrete. A single mix design for each class of concrete will be provided. Acceptance by the Contractor to use the mix design developed by the Engineer shall not relieve the Contractor from meeting specification requirements.

80277

### DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: August 2, 2011

<u>FEDERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR Part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR Part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor.

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR Part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. The determination is

based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 11.00 % of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set for in this Special Provision:

- (a) The bidder documents that enough DBE participation has been obtained to meet the goal: or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

DBE LOCATOR REFERENCES. Bidders shall consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's website at <a href="https://www.dot.il.gov">www.dot.il.gov</a>.

<u>BIDDING PROCEDURES</u>. Compliance with this Special Provision is a material bidding requirement. The failure of the bidder to comply will render the bid not responsive.

- (a) The bidder shall submit a Disadvantaged Business Utilization Plan on Department forms SBE 2025 and 2026 with the bid.
- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. For bidding purposes, submission of the completed SBE 2025 forms, signed by the DBEs and faxed to the bidder will be acceptable as long as the original is available and provided upon request. All elements of information indicated on the said form shall be provided, including but not limited to the following:
  - The names and addresses of DBE firms that will participate in the contract;

- (2) A description, including pay item numbers, of the work each DBE will perform;
- (3) The dollar amount of the participation of each DBE firm participating. The dollar amount of participation for identified work shall specifically state the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
- (4) DBE Participation Commitment Statements, form SBE 2025, signed by the bidder and each participating DBE firm documenting the commitment to use the DBE subcontractors whose participation is submitted to meet the contract goal;
- (5) if the bidder is a joint venture comprised of DBE companies and non-DBE companies, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s); and,
- (6) If the contract goal if not met, evidence of good faith efforts.

GOOD FAITH EFFORT PROCEDURES. The contract will not be awarded until the Utilization Plan submitted by the apparent successful bidder is approved. All information submitted by the bidder must be complete, accurate and adequately document that enough DBE participation has been obtained or document that good faith efforts of the bidder, in the event enough DBE participation has not been obtained, before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan documents sufficient commercially useful DBE work performance to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR Part 26, Appendix A. The Utilization Plan will not be approved by the Department if the Utilization Plan does not document sufficient DBE participation to meet the contract goal unless the apparent successful bidder documented in the Utilization Plan that it made a good faith effort to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere pro forma efforts, in other words, efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

(a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.

- (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
- (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
- (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
- (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
  - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.
- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.

- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the apparent successful bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that the bidder has failed to meet the requirements of this Special Provision or that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification shall include a statement of reasons for the determination.
- (c) The bidder may request administrative reconsideration of a determination adverse to the bidder within the five working days after the receipt of the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issues raised in the determination statement of reasons, provided the documentation and arguments address efforts made prior to submitting the bid. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of documentation and whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for consideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is

generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR Part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR Part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contract. Credit will be given for the following:
  - (1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
  - (2) The DBE may also lease trucks from a non-DBE firm, including from an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission is receives as a result of the lease arrangement.
- (e) DBE as a material supplier:
  - (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
  - (2) 100 percent goal credit for the cost of materials of supplies obtained from a DBE manufacturer.
  - (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal. All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement.

- (a) NO AMENDMENT. No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217)785-4611. Telefax number (217)785-1524.
- (b) <u>TERMINATION OR REPLACEMENT</u>. The Contractor shall not terminate or replace a DBE listed on the approved Utilization Plan, or perform with other forces work designated for a listed DBE except as provided in the Special Provision.
- (c) <u>CHANGES TO WORK</u>. Any deviation from the DBE condition-of-award or contract plans, specifications, or special provisions must be approved, in writing, by the Department as provided elsewhere in the Contract. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract. Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A, must be signed and submitted. If the commitment of work is in the form of additional tasks assigned to an existing subcontract, than a new Request for Approval of Subcontractor shall not be required. However, the Contractor must document efforts to assure that the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.
- (d) <u>ALTERNATIVE WORK METHODS</u>. In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractorinitiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:

- (1) That the replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or
- (2) That the DBE is aware that its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or
- (3) That the DBE is not capable of performing the replacement work or has declined to perform the work at a reasonable competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.
- (e) TERMINATION AND REPLACEMENT PROCEDURES. The Contractor shall not terminate or replace a DBE subcontractor listed in the approved Utilization Plan without prior written consent. This includes, but is not limited to, instances in which the Contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm. Written consent will be granted only if the Bureau of Small Business Enterprises agrees, for reasons stated in its concurrence document, that the Contractor has good cause to terminate or replace the DBE firm. Before transmitting to the Bureau of Small Business Enterprises any request to terminate and/or substitute a DBE subcontractor, the Contractor shall give notice in writing to the DBE subcontractor, with a copy to the Bureau, of its intent to request to terminate and/or substitute, and the reason for the request. The Contractor shall give the DBE five days to respond to the Contractor's notice. The DBE so notified shall advise the Bureau and the Contractor of the reasons, if any, why it objects to the proposed termination of its subcontract and why the Bureau should not approve the Contractor's action. If required in a particular case as a matter of public necessity, the Bureau may provide a response period shorter than five days.

For purposes of this paragraph, good cause includes the following circumstances:

- (1) The listed DBE subcontractor fails or refuses to execute a written contract;
- (2) The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the prime contractor;
- (3) The listed DBE subcontractor fails or refuses to meet the prime Contractor's reasonable, nondiscriminatory bond requirements;

- (4) The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness;
- (5) The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1,200 or applicable state law.
- (6) You have determined that the listed DBE subcontractor is not a responsible contractor;
- (7) The listed DBE subcontractor voluntarily withdraws from the projects and provides to you written notice of its withdrawal;
- (8) The listed DBE is ineligible to receive DBE credit for the type of work required;
- (9) A DBE owner dies or becomes disabled with the result that the listed DBE contractor is unable to complete its work on the contract;
- (10) Other documented good cause that compels the termination of the DBE subcontractor. Provided, that good cause does not exist if the prime Contractor seeks to terminate a DBE it relied upon to obtain the contract so that the prime Contractor can self-perform the work for which the DBE contractor was engaged or so that the prime Contractor can substitute another DBE or non-DBE contractor after contract award.

When a DBE is terminated, or fails to complete its work on the Contract for any reason the Contractor shall make a good faith effort to find another DBE to substitute for the original DBE to perform at least the same amount of work under the contract as the terminated DBE to the extent needed to meet the established Contract goal.

(f) PAYMENT RECORDS. The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the BDE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

reconsideration of any amount deducted as damages pursuant to subsection (h) of this part.

- (g) ENFORCEMENT. The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (h) <u>RECONSIDERATION</u>. Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor my request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

80029

#### FRICTION AGGREGATE (BDE)

Effective: January 1, 2011

Revise Article 1004.01(a)(4) of the Standard Specifications to read:

- "(4) Crushed Stone. Crushed stone shall be the angular fragments resulting from crushing undisturbed, consolidated deposits of rock by mechanical means. Crushed stone shall be divided into the following, when specified.
  - a. Carbonate Crushed Stone. Carbonate crushed stone shall be either dolomite or limestone. Dolomite shall contain 11.0 percent or more magnesium oxide (MgO). Limestone shall contain less than 11.0 percent magnesium oxide (MgO).
  - b. Crystalline Crushed Stone. Crystalline crushed stone shall be either metamorphic or igneous stone, including but is not limited to, quartzite, granite, rhyolite and diabase."

Revise Article 1004.03(a) of the Standard Specifications to read:

"1004.03 Coarse Aggregate for Hot-Mix Asphalt (HMA). The aggregate shall be according to Article 1004.01 and the following.

(a) Description. The coarse aggregate for HMA shall be according to the following table.

Use	Mixture	Aggregates Allowed
Class A	Seal or Cover	Allowed Alone or in Combination:
		Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag Crushed Concrete
HMA All Other	Stabilized Subbase or Shoulders	Allowed Alone or in Combination:  Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag <sup>1/</sup> Crushed Concrete

Use	Mixture	Aggregates Allowed	
HMA High ESAL Low ESAL	Binder IL-25.0, IL-19.0, or IL-19.0L SMA Binder	Allowed Alone or in Crushed Gravel Carbonate Crushed Crystalline Crushed Crushed Sandstone	Stone <sup>2/</sup>
HMA	0.0.1	Crushed Slag (ACBF Crushed Concrete <sup>3/</sup>	
High ESAL Low ESAL	C Surface and Leveling Binder IL-12.5,IL-9.5, or IL-9.5L SMA Ndesign 50 Surface	Allowed Alone or in Combination:  Crushed Gravel Carbonate Crushed Stone <sup>2/</sup> Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag <sup>4/</sup> Crushed Concrete <sup>3/</sup>	
HMA High ESAL	D Surface and Leveling Binder IL-12.5 or IL-9.5 SMA Ndesign 50 Surface	Allowed Alone or in Combination:  Crushed Gravel Carbonate Crushed Stone (other than Limestone) <sup>2/</sup> Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) <sup>5/</sup> Crushed Steel Slag <sup>4/5/</sup> Crushed Concrete <sup>3/</sup>	
		Other Combinations Allowed:	
		Up to	With
		25% Limestone 50% Limestone	Any Mixture D aggregate other than Dolomite
		75% Limestone	Crushed Slag (ACBF) <sup>5/</sup> or Crushed Sandstone

Use	Mixture	Aggregates Allowed	
HMA High ESAI	E Surface L-12.5 or IL-9.5 SMA Ndesign 80 Surface	Allowed Alone or in Combination:  Crushed Gravel Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) <sup>5/</sup> Crushed Steel Slag <sup>5/</sup> Crushed Concrete <sup>3/</sup> No Limestone.	
		Other Combinations Allowed:	
		Up to	With
		50% Dolomite <sup>2/</sup>	Any Mixture E aggregate
		75% Dolomite <sup>2/</sup>	Crushed Sandstone, Crushed Slag (ACBF) <sup>5/</sup> , Crushed Steel Slag <sup>5/</sup> , or Crystalline Crushed Stone
		75% Crushed Gravel or Crushed Concrete <sup>3/</sup>	Crushed Sandstone, Crystalline Crushed Stone, Crushed Slag (ACBF) <sup>5/</sup> , or Crushed Steel Slag <sup>5/</sup>
HMA High ESAL	F Surface IL-12.5 or IL-9.5 SMA Ndesign 80 Surface	Allowed Alone or in Combination:	
		Crushed Sandstone	Crushed Slag (ACBF) <sup>5/</sup> Crushed Steel Slag <sup>5/</sup>
		Other Combinations Allowed:	
		Up to	With

Use	Mixture	Aggregates Allowed	
		50% Crushed Gravel, Crushed Concrete <sup>3/</sup> , or Dolomite <sup>2/</sup>	Crushed Sandstone, Crushed Slag (ACBF) <sup>5/</sup> , Crushed Steel Slag <sup>5/</sup> , or Crystalline Crushed Stone

- 1/ Crushed steel slag allowed in shoulder surface only.
- 2/ Carbonate crushed stone shall not be used in SMA Ndesign 80. In SMA Ndesign 50, carbonate crushed stone shall not be blended with any of the other aggregates allowed alone in Ndesign 50 SMA binder or Ndesign 50 SMA surface.
- 3/ Crushed concrete will not be permitted in SMA mixes.
- 4/ Crushed steel slag shall not be used as leveling binder.
- 5/ When either slag is used, the blend percentages listed shall be by volume."

### **GRANULAR MATERIALS (BDE)**

Effective: November 1, 2012

Revise the title of Article 1003.04 of the Standard Specifications to read:

"1003.04 Fine Aggregate for Bedding, Trench Backfill, Embankment, Porous Granular Backfill, Sand Backfill for Underdrains, and French Drains."

Revise Article 1003.04(c) of the Standard Specifications to read:

"(c) Gradation. The fine aggregate gradations for granular embankment, granular backfill, bedding, and trench backfill for pipe culverts and storm sewers shall be FA 1, FA 2, or FA 6 through FA 21.

The fine aggregate gradation for porous granular embankment, porous granular backfill, french drains, and sand backfill for underdrains shall be FA 1, FA 2, or FA 20, except the percent passing the No. 200 (75 µm) sieve shall be 2±2."

Revise Article 1004.05(c) of the Standard Specifications to read:

"(c) Gradation. The coarse aggregate gradations shall be as follows.

Application	Gradation
Blotter	CA 15
Granular Embankment, Granular Backfill, Bedding, and Trench Backfill for Pipe Culverts and Storm Sewers	CA 6, CA 9, CA 10, CA 12, CA17, CA18, and CA 19
Porous Granular Embankment, Porous Granular Backfill, and French Drains	CA 7, CA 8, CA 11, CA 15, CA 16 and CA 18"



# HOT-MIX ASPHALT - MIXTURE DESIGN COMPOSITION AND VOLUMETRIC REQUIREMENTS (BDE)

Effective: November 1, 2013

Revise Article 406.14(b) of the Standard Specifications to read.

"(b) If the HMA placed during the initial test strip (1) is determined to be unacceptable to remain in place by the Engineer, and (2) was not produced within 2.0 to 6.0 percent air voids or within the individual control limits of the JMF, the mixture and test strip will not be paid for and the mixture shall be removed at the Contractor's expense. An additional test strip and mixture will be paid for in full, if produced within 2.0 to 6.0 percent air voids and within the individual control limits of the JMF."

Revise Article 406.14(c) of the Standard Specifications to read.

"(c) If the HMA placed during the initial test strip (1) is determined to be unacceptable to remain in place by the Engineer, and (2) was produced within 2.0 to 6.0 percent air voids and within the individual control limits of the JMF, the mixture shall be removed. Removal will be paid in accordance to Article 109.04. This initial mixture and test strip will be paid for at the contract unit prices. The additional mixture will be paid for at the contract unit price, and any additional test strips will be paid for at one half the unit price of each test strip."

Revise Article 1030.04(a)(1) of the Standard Specifications to read.

"(1) High ESAL Mixtures. The Job Mix Formula (JMF) shall fall within the following limits.

	High ESAL, MIXTURE COMPOSITION (% PASSING) 1/									
Sieve		.0 mm		0 mm		5 mm		5 mm	IL-4.7	5 mm
Size	min	max	min	max	min	max	min	max	min	max
1 1/2 in (37.5 mm)		100								
1 in. (25 mm)	90	100		100						
3/4 in. (19 mm)		90	82	100		100				
1/2 in. (12.5 mm)	45	75	50	85	90	100		100		100
3/8 in. (9.5 mm)						89	90	100		100
#4 (4.75 mm)	24	42 <sup>2/</sup>	24	50 <sup>2/</sup>	28	65	32	69	90	100
#8 (2.36 mm)	16	31	20	36	28	48 <sup>3/</sup>	32	52 <sup>3/</sup>	70	90
#16 (1.18 mm)	10	22	10	25	10	32	10	32	50	65
#50 (300 µm)	4	12	4	12	4	15	4	15	15	30
#100 (150 µm)	3	9	3	9	3	10	3	10	10	18
#200 (75 µm)	3	6	3	6	4	6	4	6	7	9

Ratio					
Dust/Asphalt	1.0	1.0	1.0	1.0	1.0 1/4
Binder	1 1				

- 1/ Based on percent of total aggregate weight.
- 2/ The mixture composition shall not exceed 40 percent passing the #4 (4.75 mm) sieve for binder courses with Ndesign  $\geq$  90.
- 3/ The mixture composition shall not exceed 44 percent passing the #8 (2.36 mm) sieve for surface courses with Ndesign ≥ 90.
- 4/ Additional minus No. 200 (0.075 mm) material required by the mix design shall be mineral filler, unless otherwise approved by the Engineer."

Delete Article 1030.04(a)(4) of the Standard Specifications.

Revise Article 1030.04(b)(1) of the Standard Specifications to read.

"(1) High ESAL Mixtures. The target value for the air voids of the HMA shall be 4.0 percent at the design number of gyrations. The VMA and VFA of the HMA design shall be based on the nominal maximum size of the aggregate in the mix, and shall conform to the following requirements.

VOLUMETRIC REQUIREMENTS High ESAL						
		Voids in th		Aggregat		Voids Filled
		(VMA), % minimum				with Asphalt Binder
Ndesign	IL-25.0	IL-19.0	IL-12.5	IL-9.5	IL-4.75 <sup>1/</sup>	(VFA), %
50					18.5	65 – 78 <sup>2/</sup>
70 90 105	12.0	13.0	14.0	15.0		65 - 75

- 1/ Maximum Draindown for IL-4.75 shall be 0.3 percent
- 2/ VFA for IL-4.75 shall be 76-83 percent"

Delete Article 1030.04(b)(4) of the Standard Specifications.

Revise the Control Limits Table in Article 1030.05(d)(4) of the Standard Specifications to read.

"CONTROL LIMITS
OOIVITOL EIIVITO

Parameter	High ESAL Low ESAL	High ESAL Low ESAL	All Other	IL-4.75	IL-4.75
	Individual	Moving Avg.	Individual	Individual	Moving
	Test	of 4	Test	Test	Avg. of 4
% Passing: 1/					
1/2 in. (12.5 mm)	±6%	±4%	± 15 %		
No. 4 (4.75 mm)	±5%	±4%	± 10 %		
No. 8 (2.36 mm)	±5%	± 3 %			
No. 16 (1.18 mm)				±4%	±3%
No. 30 (600 µm)	±4%	± 2.5 %			
Total Dust Content No. 200 (75 µm)	± 1.5 %	± 1.0 %	± 2.5 %	± 1.5 %	± 1.0 %
Asphalt Binder Content	± 0.3 %	± 0.2 %	± 0.5 %	± 0.3 %	± 0.2 %
Voids	± 1.2 %	± 1.0 %	± 1.2 %	± 1.2 %	± 1.0 %
VMA	-0.7 % <sup>2/</sup>	-0.5 % <sup>2/</sup>		-0.7 % <sup>2/</sup>	-0.5 % <sup>2/</sup>

## 1/ Based on washed ignition oven

2/ Allowable limit below minimum design VMA requirement"

## HOT-MIX ASPAHLT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (BDE)

Effective: November 1, 2013

<u>Description</u>. This special provision provides the requirements for Hamburg Wheel and tensile strength testing for High ESAL, IL-4.75, and Stone Matrix Asphalt (SMA) hot-mix asphalt (HMA) mixes during mix design verification and production. This special provision also provides the plant requirements for hydrated lime addition systems used in the production of High ESAL, IL-4.75, and SMA mixes.

Mix Design Testing. Add the following to Article 1030.04 of the Standard Specifications:

"(d) Verification Testing. High ESAL, IL-4.75, and SMA mix designs submitted for verification will be tested to ensure that the resulting mix designs will pass the required criteria for the Hamburg Wheel Test (Illinois Modified AASHTO T 324) and the Tensile Strength Test (Illinois Modified AASHTO T 283). The Department will perform a verification test on gyratory specimens compacted by the Contractor. If the mix fails the Department's verification test, the Contractor shall make necessary changes to the mix and provide passing Hamburg Wheel and tensile strength test results from a private lab. The Department will verify the passing results.

All new and renewal mix designs shall meet the following requirements for verification testing.

(1) Hamburg Wheel Test Criteria. The maximum allowable rut depth shall be 0.5 in. (12.5 mm). The minimum number of wheel passes at the 0.5 in. (12.5 mm) rut depth criteria shall be based on the high temperature binder grade of the mix as specified in the mix requirements table of the plans.

Illinois Modified AASHTO	T 324	Requirements	1/
--------------------------	-------	--------------	----

PG Grade	Number of Passes
PG 58-xx (or lower)	5,000
PG 64-xx	7,500
PG 70-xx	15,000
PG 76-xx (or higher)	20,000

- 1/ When produced at temperatures of 275 ± 5 °F (135 ± 3 °C) or less, loose Warm Mix Asphalt shall be oven aged at 270 ± 5 °F (132 ± 3 °C) for two hours prior to gyratory compaction of Hamburg Wheel specimens.
- (2) Tensile Strength Criteria. The minimum allowable conditioned tensile strength shall be 415 kPa (60 psi) for non-polymer modified performance graded (PG) asphalt binder and 550 kPa (80 psi) for polymer modified PG asphalt binder. The maximum allowable unconditioned tensile strength shall be 1380 kPa (200 psi)."

Production Testing. Revise Article 1030.06(a) of the Standard Specifications to read:

"(a) High ESAL, IL-4.75 and SMA Mixtures. For each contract, a 300 ton (275 metric tons) test strip will be required at the beginning of HMA production for each mixture with a quantity of 3000 tons (2750 metric tons) or more according to the Manual of Test Procedures for Materials "Hot Mix Asphalt Test Strip Procedures".

Before start-up, target values shall be determined by applying gradation correction factors to the JMF when applicable. These correction factors shall be determined from previous experience. The target values, when approved by the Engineer, shall be used to control HMA production. Plant settings and control charts shall be set according to target values.

Before constructing the test strip, target values shall be determined by applying gradation correction factors to the JMF when applicable. After any JMF adjustment, the JMF shall become the Adjusted Job Mix Formula (AJMF). Upon completion of the first acceptable test strip, the JMF shall become the AJMF regardless of whether or not the JMF has been adjusted. If an adjustment/plant change is made, the Engineer may require a new test strip to be constructed. If the HMA placed during the initial test strip is determined to be unacceptable to remain in place by the Engineer, it shall be removed and replaced.

The limitations between the JMF and AJMF are as follows.

Parameter	Adjustment
1/2 in. (12.5 mm)	± 5.0 %
No. 4 (4.75 mm)	± 4.0 %
No. 8 (2.36 mm)	± 3.0 %
No. 30 (600 μm)	*
No. 200 (75 μm)	*
Asphalt Binder	± 0.3 %
Content	

<sup>\*</sup> In no case shall the target for the amount passing be greater than the JMF.

Any adjustments outside the above limitations will require a new mix design.

Mixture sampled to represent the test strip shall include additional material sufficient for the Department to conduct Hamburg Wheel testing according to Illinois Modified AASHTO T324 (approximately 60 lb (27 kg) total).

The Contractor shall immediately cease production upon notification by the Engineer of failing Hamburg Wheel test. All prior produced material may be paved out provided all other mixture criteria is being met. No additional mixture shall be produced until the Engineer receives passing Hamburg Wheel tests.

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

The Department may conduct additional Hamburg Wheel tests on production material as determined by the Engineer."

Revise the title of Article 1030.06(b) of the Standard Specifications to read:

"(b) Low ESAL and All Other Mixtures."

<u>System for Hydrated Lime Addition</u>. Revise the fourth sentence of the third paragraph of Article 1030.04(c) of the Standard Specifications to read:

"The method of application shall be according to Article 1102.01(a)(10)."

Replace the first three sentences of the second paragraph of Article 1102.01(a)(10) of the Standard Specifications to read:

"When hydrated lime is used as the anti-strip additive, a separate bin or tank and feeder system shall be provided to store and accurately proportion the lime onto the aggregate either as a slurry, as dry lime applied to damp aggregates, or as dry lime injected onto the hot aggregates prior to adding the liquid asphalt cement. If the hydrated lime is added either as a slurry or as dry lime on damp aggregates, the lime and aggregates shall be mixed by a power driven pugmill to provide a uniform coating of the lime prior to entering the dryer. If dry hydrated lime is added to the hot dry aggregates in a dryer-drum plant, the lime shall be added in such a manner that the lime will not become entrained into the air stream of the dryer-drum and that thorough dry mixing shall occur prior to the injection point of the liquid asphalt. When a batch plant is used, the hydrated lime shall be added to the mixture in the weigh hopper or as approved by the Engineer."

<u>Basis of Payment</u>. Replace the seventh paragraph of Article 406.14 of the Standard Specifications with the following:

"For mixes designed and verified under the Hamburg Wheel criteria, the cost of furnishing and introducing anti-stripping additives in the HMA will not be paid for separately, but shall be considered as included in the contract unit price of the HMA item involved.

If an anti-stripping additive is required for any other HMA mix, the cost of the additive will be paid for according to Article 109.04. The cost incurred in introducing the additive into the HMA will not be paid for separately, but shall be considered as included in the contract unit price of the HMA item involved.

No additional compensation will be awarded to the Contractor because of reduced production rates associated with the addition of the anti-stripping additive."



### LRFD STORM SEWER BURIAL TABLES (BDE)

Effective: November 1, 2013

Revise Article 550.02 of the Standard Specifications to read as follows:

"Item	Article Section
(a) Clay Sewer Pipe	1040.02
(b) Extra Strength Clay Pipe	1040.02
(c) Concrete Sewer, Storm Drain, and Culvert Pipe	1042
(d) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe	1042
(e) Reinforced Concrete Elliptical Culvert, Storm Drain, and Sewer Pipe (Note	1)1042
(f) Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe (Note 1)	
(g) Polyvinyl Chloride (PVC) Pipe	1040.03
(h) Corrugated Polyvinyl Chloride (PVC) Pipe with a Smooth Interior	1040.03
(i) Corrugated Polypropylene (CPP) Pipe with Smooth Interior	1040.07
(j) Rubber Gaskets and Preformed Flexible Joint Sealants for Concrete Pipe	
(k) Mastic Joint Sealer for Pipe	1055
(I) External Sealing Band	1057
(m) Fine Aggregate (Note 2)	1003.04
(n) Coarse Aggregate (Note 3)	1004.05
(o) Reinforcement Bars and Welded Wire Fabric	1006.10
(p) Handling Hole Plugs	1042.16
(q) Polyethylene (PE) Pipe with a Smooth Interior	1040.04
(r) Corrugated Polyethylene (PE) Pipe with a Smooth Interior	1040.04

Note 1. The class of elliptical and arch pipe used for various storm sewer sizes and heights of fill shall conform to the requirements for circular pipe.

- Note 2. The fine aggregate shall be moist.
- Note 3. The coarse aggregate shall be wet."



Revise the table for permitted materials in Article 550.03 of the Standard Specifications as follows:

"Class	Materials
Α	Rigid Pipes:
	Clay Sewer Pipe
	Extra Strength Clay Pipe
	Concrete Sewer, Storm Drain, and Culvert Pipe
	Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
	Reinforced Concrete Elliptical Culvert, Storm Drain, and Sewer Pipe
	Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe
В	Rigid Pipes:
	Clay Sewer Pipe
	Extra Strength Clay Pipe
	Concrete Sewer, Storm Drain, and Culvert Pipe
	Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
	Reinforced Concrete Elliptical Culvert, Storm Drain, and Sewer Pipe
	Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe
	Flexible Pipes:
	Polyvinyl Chloride (PVC) Pipe
	Corrugated Polyvinyl Chloride Pipe (PVC) with a Smooth Interior
	Polyethylene (PE) Pipe with a Smooth Interior
	Corrugated Polyethylene (PE) Pipe with a Smooth Interior
	Corrugated Polypropylene (CPP) Pipe with a Smooth Interior"

Replace the storm sewers tables in Article 550.03 of the Standard Specifications with the following:

Nominal   FILE AND OF MATERIAL PERMITTED AND STRENGTH REQUIRED   Type 1   Type 1   Type 1   Type 2   Type 2   Type 1   Type 2   Type 3		Т			т-									T			_			_			_				1
Type 1				CPP	¥	×	×	×	¥	×	Ϋ́	×	¥	×	ž	Ϋ́	AN	×	Ϋ́	A	Ä	Ϋ́	A	Ϋ́	¥	Α̈́	
FOR A GIVEN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF THE PIPE   Type 1				CPE	×	×	×	×	Ϋ́	×	¥	×	₹	¥	¥	¥	¥	Š	Ϋ́	¥	Š	Š	¥	Ϋ́	ž	Ϋ́	
FOR A GIVEN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF THE PIPE   Type 1				PE	×	×	¥	×	¥	×	¥	×	¥	×	×	×	¥	¥	Ą	¥	¥	₹	ΑĀ	¥	ž	Ϋ́	
Type			iter than 3 ng 10'	CPVC	×	×	×	×	×	×	¥	×	ž	×	¥	¥	¥	¥	¥	ΑĀ	¥	¥	¥	¥	¥	¥	
Type	PIPE	Type 2	ight: Great	PVC	×	×	×	×	×	×	ΑN	×	¥	×	×	×	ΑN	¥	₹	¥	₹	₹	ΑN	¥	ΑN	Ϋ́	
Peter   Pete	RED OF THE		E He	ESCP	×	×	×	×	×	×	×	×	×	×	×	×	¥	¥	¥	¥	₹	¥	¥	¥	¥	¥	
Peter   Pete	H REQUI			CSP	-	<del>-</del>	<b>—</b>	2	7	7	3	ო	¥	¥	¥	¥	₹	¥	¥	ΑA	¥	¥	ΑA	¥	¥	NA	
Peter   Pete	S STRENGT HTS OVER			RCCP	ž	=	=	=	=	=	=	=	=	=	=	=	  =	=	=	=	=	=	=	=	=	=	
Peter   Pete	SEWER ED AND LL HEIGH			CPP	ž	×	×	×	¥	×	ΑA	×	NA	×	¥	×	¥	×	N A	NA	¥	¥	NA	₹	¥	A	
Peter   Pete	STORN ERMITT S AND FI			CPE	×	×	×	×	¥	×	¥	×	NA	×	×	×	Α̈́	¥	ΑA	NA	¥	NA	AN	¥	ž	AA	
Peter   Pete	ERIAL F METERS			Д	×	×	AA	×	ž	×	¥	×	NA	×	×	×	ΑĀ	¥	N A	¥	¥	AA	¥	¥	ž	A	e e
Peter   Pete	D OF MAT	-	and less um cover	CPVC	×	×	×	×	×	×	₹	×	¥	×	₹	NA	ΑĀ	¥	Ä	¥	¥	NA	¥	¥	¥	¥	Sewer Pi
Peter   Pete	KIN A GIVEN	Type	leight: 3' 1' minim	PVC	×	×	×	×	×	×	₹	×	¥	×	×	×	¥	₹	Ā	¥	₹	Ā	¥	ž	¥	Ā	rain, and
	FOR		Fill H	ESCP	×	×	ΑĀ	¥	₹	Ϋ́	¥	ž	ΑĀ	ΑN	×	×	NA	₹	ΑĀ	¥	¥	ΑĀ	ΑĀ	¥ Z	Ϋ́	ΑĀ	
				CSP	က	Ν	ΑĀ	ΑN	ž	ΑĀ	ž	¥	ΝA	¥	¥	ΑĀ	Ϋ́	ž	¥	¥	¥	ΑA	ž	ž	¥	ΑĀ	ete Culve
				RCCP	ΑĀ	≥	2	≥	=	=	=		=	=	=	=	=	=	=	=	=	=	=	=	=	=	ced Concr
			Nominal Diameter in		10	12	15	18	21	24	27	30	33	36	42	48	54	09	99	72	78	84	06	96	102	108	

Corrugated Polyethylene Pipe Polyethylene Pipe Polyethylene Pipe Polyethylene Pipe Polyethylene Pipe Corrugated Polyethylene Pipe Extra Strength Clay Pipe Polyethylene Pipe with a Smooth Interior Corrugated Polyethylene Pipe with a Smooth Interior Corrugated Polyethylene Pipe with a Smooth Interior

This material may be used for the given pipe diameter and fill height. This material is Not Acceptable for the given pipe diameter and fill height. May also use Standard Strength Clay Pipe CSP CPVC ESCP CPE CPE CPE NA

			Ođ	K A GIVE	STORM S KIND OF MATERIAL PERMIT FOR A GIVEN PIPE DIAMETERS AND	S ATERIAL IAMETEF	STORM SEWERS (Metric) L PERMITTED AND STRE RS AND FILL HEIGHTS (	EWERS TED AN	EWERS (Metric) TED AND STRENGTH REQUIRED FILL HEIGHTS OVER THE TOP OF	STH REQ	EWERS (Metric) TTED AND STRENGTH REQUIRED FILL HEIGHTS OVER THE TOP OF THE PIPE	E PIPE				
				Type 1	9 1							Type 2	e 2			
Nominal Diameter in			Fill F With 3	Height: 1 00 mm m	II Height: 1 m' and less n 300 mm minimum cover	s ver					F⊪	leight: Greater thai not exceeding 3 m	Fill Height: Greater than 1 m not exceeding 3 m	1 m		
	RCCP	CSP	ESCP	PVC	CPVC	PE	CPE	СРР	RCCP	CSP	ESCP	PVC	CPVC	PE	CPE	CPP
250	Ą	3	×	×	×	×	×	¥	A	-	×	×	×	×	×	¥
300	≥ 2	Ž:	×	×:	× :	×	×	××	==	<del>,</del> ,	* ;	×	×:	×	××	××
3/5	≥	Y Y	ž	×	×	ž	×	×	=		×	×	×	NA	×	×
450	≥	Ϋ́	₹	×	×	×	×	×	=	7	×	×	×	×	×	×
525	=	¥	¥	×	×	¥	¥	¥	==	7	×	×	×	¥	Ϋ́	₹
900	=	A A	₹	×	×	×	×	×	=	7	×	×	×	×	×	×
675	=	Α	¥	₹	ΑĀ	¥	ΑĀ	¥	=	က	×	ΑN	NA	ΑN	¥	¥
750	≥	¥	¥	×	×	×	×	×	=	က	×	×	×	×	×	×
825	=	¥	¥	≨	¥	¥	¥	Ϋ́	=	Ϋ́	×	₹	¥	Ϋ́	ž	¥
006	=	Ą	¥	×	×	×	×	×	=	ΑĀ	×	×	×	×	ΑĀ	×
1050	=	¥	×	×	Ϋ́	×	×	¥	=	ž	×	×	Α×	×	¥	ž
1200	=	¥	×	×	Ϋ́	×	×	×	=	Ϋ́	×	×	Ϋ́	×	¥	¥
1350	=	NA	Ϋ́	¥	ΑN	¥	ΑN	¥	=	¥	¥	¥	AN	¥	ΑĀ	NA
1500	=	Ą	₹	¥	Ϋ́	¥	¥	×	=	¥	¥	¥	Ϋ́	Ϋ́	¥	×
1650	=	Ϋ́	¥	¥	¥	ž	¥	¥	=	Ϋ́	Ϋ́	Ϋ́	¥	¥	ΑĀ	¥
1800	=	AN	Ā	¥	ΑN	¥	ΑN	Ϋ́	=	¥	¥	¥	ΑN	¥	Ϋ́	Ą
1950	=	Ϋ́	₹	ž	Ϋ́	ž	¥	ž	=	¥	Ϋ́	₹	ΑN	Ϋ́	¥	¥
2100	=	ΑN	¥	¥	A	AA	Α	NA	=	NA	NA	ΑN	NA	NA	¥	NA
2250	=	¥ V	₹	≨	Ϋ́	ž	NA	AA	=	NA	ΑA	¥	ΑN	NA	ΝA	ΑĀ
2400	=	₹	₹	ž	ΑN	¥	Ϋ́	ž	=	¥	¥	¥	¥ Z	¥	¥	ΑĀ
2550	=	¥	₹	₹	Ϋ́	ž	¥	Ϋ́	=	Ϋ́	¥	¥	Ϋ́	¥	ž	¥
2700	=	ΑN	Ā	¥	AA	Ą	ΑN	NA	=	NA	NA	ΑN	ΑN	NA	NA	NA
RCCP Reinfo	Reinforced Concrete Culvert, Stor	crete Culv	ert, Storm	m Drain, and	d Sewer Pipe	ipe										
	ete Sewer	, Storm di	Concrete Sewer, Storm drain, and Culvert Pipe	ulvert Pip	je Je											
	Polyvinyl Chloride Pipe	te Pipe														
CPVC Corruc	Corrugated Polyvinyl Chloride Pip	vinyl Chlo	oride Pipe													
	ことと	2														

Extra Strength Clay Pipe
Polyethylene Pipe with a Smooth Interior
Corrugated Polyethylene Pipe with a Smooth Interior
Corrugated Polypropylene pipe with a Smooth Interior
This material may be used for the given pipe diameter and fill height.
This material is Not Acceptable for the given pipe diameter and fill height.
May also use Standard Strength Clay Pipe ESCP PE CPE CPP X NA



STORM SEWERS KIND OF MATERIAL PERMITTED AND STRENGTH REQUIRED FOR A GIVEN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF THE PIPE	Type 4	Fill Height: Greater than 15' not exceeding 20'	ESCP PVC CPVC PE CPP	×	× × ×	×	×	× ×	× × ×	AN AN	× × ×	AN AN	×	×	NA X AN X	NA NA	NA AN AN	NA NA NA	NA NA NA	AN AN AN	AN AN AN	NA NA	NA NA NA	AN AN AN	NA AN
STORM SEWERS KIND OF MATERIAL PERMITTED AND STRENGTH REQUIRED FIL HEIGHTS OVER THE TOP OF			RCCP CSP	H						-			_		¥ ≥					•••••					
WERS AND STREN EIGHTS OV			CPP R	╀						L					- V								_		
STORM SEWERS ERMITTED AND S AND FILL HEIGHT			CPE	×	¥	¥	¥	¥	¥	¥Σ	¥	¥	¥	≨	ΑĀ	ΑN	¥	ΑA	ΑN	ž	Ϋ́	¥	ž	¥	¥
ST SIAL PER TERS AN		, 0	ЪЕ	×	×	ž	×	ž	×	ΑΝ	×	₹	×	×	×	¥	¥	A	Ϋ́	₹	¥	¥	¥	¥	¥
F MATEF	3	Fill Height: Greater than 10 not exceeding 15'	CPVC	×	×	×	×	×	×	¥	×	¥	×	¥	Α	ΑN	¥	Α	¥	Α	¥	ΑN	¥	¥	¥
KIND O	Type 3	eight: Greater than not exceeding 15'	PVC	×	×	×	×	×	×	¥	×	¥	×	×	X	Ν	¥	NA	Ϋ́	¥	ΑĀ	NA	≨	₹	Ν
FOR A G		Fill He	ESCP	×	×	×	×	A	Α	ΑN	Ϋ́	¥	NA	¥	NA	ΑN	¥	NA	¥	ΑĀ	NA	N	¥	¥	Α
			CSP	2	2	က	AA	Α	NA	NA	Ϋ́	Ϋ́	NA	A A	NA	AA	¥	AA	¥	¥	NA	AA	¥	N A	NA
			RCCP	¥	=	=	=	=	=	=	=	=	=	=	=	=	=	=	=	=	=	=	=	≥	1360
		Nominal Diameter	:	10	12	15	18	21	24	27	30	33	36	42	48	54	09	99	72	78	84	06	96	102	108

Concrete Sewer, Storm drain, and Culvert Pipe Polyvinyl Chloride Pipe

CSP PVC CPVC ESCP CPE CPE CPE NA NA

Corrugated Polyvinyl Chloride Pipe
Extra Strength Clay Pipe
Extra Strength Clay Pipe
Polyethylene Pipe with a Smooth Interior
Corrugated Polypropylene pipe with a Smooth Interior
Corrugated Polypropylene pipe with a Smooth Interior
This material as be used for the given pipe diameter and fill height.
This material is Not Acceptable for the given pipe diameter and fill height.
May also use Standard Strength Clay Pipe
RCCP with a number instead of a Roman numeral shall be furnished according to AASHTO M170 Section 6. This number represents the D-load to produce a 0.01 in crack.

Nominal					KIND OF	≤		(/)	(metric) VD STRE	EWERS (metric) TTED AND STRENGTH REQUIRED	QUIRED					
Height: Greater than 3 m		-		FOR A GI	VEN PIPE	DIAMETE	AND	킖	IGHTS C	VER THE	TOP OF	THE PIPE				
Height: Greater than 3 m					Type :	3							Type 4			
CSP	minal meter in			Fill Hei	ght: Grea t exceedin	ter than 3 i g 4.5 m	E				Ľ.			than 4.5 m 6 m		
	=	RCCP	CSP	ESCP	PVC	CPVC	ЭE	CPE	СРР	RCCP	CSP	ESCP	PVC	CPVC	PE	СРР
	250	¥	2	×	×	×	×	×	Ϋ́	ΑN	3	×	×	×	×	Ą
	300	=	7	×	×	×	×	₹	×	≥	¥	¥	×	×	×	¥
	375	≡	3	×	×	×	¥	¥	×	≥	¥	¥	×	×	₹	×
	150	Ξ	A	×	×	×	×	ΑĀ	×	2	¥	¥	×	×	×	NA
	525	=	Ϋ́	₹ Z	×	×	¥	₹	¥	≥	¥	¥	×	×	ΑĀ	Ą
	000	=	¥	¥	×	×	×	¥	NA	2	ΑA	ΑN	×	×	×	¥
	375	=	¥	¥	¥	Š	Α×	ΑĀ	ΑN	2	¥	Ą	A	ΑN	ΑN	AA
	.50	=	¥	Υ Υ	×	×	×	¥	×	≥	¥	¥.	×	×	×	Α
	125	=	Ā	ΑN	¥	Α	ΑĀ	ΑĀ	NA	2	NA	A A	Ϋ́	≨	ΑN	ΑA
	8	=	Α̈́	ΑN	×	×	×	¥	AA	2	N.A.	AN	×	×	×	NA
	050	=	Ϋ́	Ϋ́	×	¥	×	₹	¥	≥	Ž Z	ΑN	×	Ϋ́	×	Ą
	200	=	AA	ΑN	×	NA	×	¥	ΑN	≥	ΑA	N A	×	ΑĀ	×	ΑA
	350	=	ž	¥	Α̈́	¥	¥	¥	Ϋ́	2	ΑĀ	ΑN	¥	¥	ΑN	ΑA
	200		¥	₹ Z	ΑĀ	Š	≨	ž	≨	≥	ž	¥	¥	ž	¥	ΑA
	650	=	¥	¥	¥	¥	¥	₹	ΑĀ	2	ΑĀ	NA	NA	NA	NA	NA
	800	=	¥	¥ Z	ž	Ϋ́	¥	¥	¥	≥	A	¥.	ΑN	ΑN	٩N	AA
	920	=	¥	¥ Z	₹	₹	₹	¥	ž	≥	¥	¥	¥	¥	ž	ΑN
NA	100	=	¥	Ϋ́	ΑĀ	Υ Δ	ž	¥	Ϋ́	2	A	NA	ΑĀ	Š	¥	ΑN
	250	=	¥	¥ Z	₹	<b>∀</b>	ž	₹	₹	80	ž	A A	¥	Ϋ́	ΑĀ	NA
1V NA	400	=	¥ ×	¥ X	₹	₹	₹	¥	₹	80	ž	Α V	¥	ž	ž	¥
70 NA	550	≥	¥	₹	≨	≨	ž	¥	₹	80	¥	¥	¥	¥	ž	Α̈́
	700	70	ΑĀ	NA	Ν	ΑN	¥	¥	¥	80	ž	V ∀ V	¥	¥	¥	¥

Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe Concrete Sewer, Storm drain, and Culvert Pipe Polyvinyl Chloride Pipe RCCP CSP PVC CPVC ESCP ESCP CPE CPE NA

Corrugated Polyvinyl Chloride Pipe
Extra Strength Clay Pipe
Polyethylene Pipe with a Smooth Interior
Corrugated Polyethylene Pipe with a Smooth Interior
Corrugated Polypropylene pipe with a Smooth Interior

This material may be used for the given pipe diameter and fill height.

This material is Not Acceptable for the given pipe diameter and fill height.

May also use Standard Strength Clay Pipe

RCCP with a number instead of a Roman numeral shall be furnished according to AASHTO M170 Section 6. This number represents the metric D-load to produce a 25.4 micro-meter crack.



	Τ-	1		l	Т			Т			т-			Г			Т			Г			Γ-				1
PE	Type 7	Fill Height: Greater than 30'	not exceeding 35'	CPVC	×	×	×	×	×	×	¥	×	¥	×	Ν V	¥	AN	Υ Y	Ą	ΑN	Ϋ́	Ą	NA	Ž	¥	AN	
STORM SEWERS KIND OF MATERIAL PERMITTED AND STRENGTH REQUIRED FOR A GIVEN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF THE PIPE	Ty	Fill Height:	not exce	RCCP	¥	>	>	>	>	>	^	>	>	>	>	>	>	>	>	^	2730	2740	2750	2750	2760	2770	
STORM SEWERS KIND OF MATERIAL PERMITTED AND STRENGTH REQUIRED FIN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF		r than 25' 1 30'		CPVC	×	×	×	×	×	×	₹	×	₹	×	¥	₹	ΑN	ž	Ϋ́	ΑN	¥ Z	Υ Y	Ϋ́N	¥	Ϋ́	ΝΑ	
VERS IND STRE EIGHTS C	Type 6	Fill Height: Greater than 25' not exceeding 30'		PVC	×	×	×	×	×	×	¥	×	¥	×	×	×	ΑN	Š	ΝA	Ν	¥	ΑĀ	ΥN	Ϋ́	Ϋ́	NA	er Pipe
STORM SEWERS ERMITTED AND S AND FILL HEIGH		Fill Heigl		RCCP	Ϋ́	>	>	>	>	>	>	>	>	>	>	>	>	>	^	>	2370	2380	2390	2400	2410	2410	n, and Sew
S ERIAL PEF AETERS A		than 20' 25'		CPVC	×	×	×	×	×	×	Ą	×	NA	×	¥	Ą	ΑN	¥	ΑĀ	ΝΑ	ΑN	ΑN	¥	¥ Z	¥	ΑN	Storm Drain
OF MATE	Type 5	Fill Height: Greater than 20' not exceeding 25'		PVC	×	×	×	×	×	×	ΑĀ	×	ΑA	×	×	×	¥	¥	¥	¥	¥	ΝΑ	₹	Ϋ́	¥	Ą	Culvert, S
KIND R A GIVEN I		Fill Height not e		RCCP	ΑN	≥	≥	≥	≥	2	Α	≥	2	≥	≥	Ν	2	≥	≥	>	2020	2020	2030	2040	2050	2060	Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
FO		Nominal Diameter	É		10	12	15	18	21	24	27	30	33	36	42	48	54	99	99	72	78	84	06	96	102	$\sim$ 1	RCCP Reinford

Polyvinyl Chloride Pipe.
Corrugated Polyvinyl Chloride Pipe.
Extra Strength Clay Pipe.
Extra Strength Clay Pipe.
This material may be used for the given pipe diameter and fill height.
This material is Not Acceptable for the given pipe diameter and fill height.
RCCP with a number instead of a Roman numeral shall be furnished according to AASHTO M170 Section 6. This number represents the D-load to produce a 0.01 in crack. PVC CPVC ESCP X NA Note

	r	T		1	_			т						_			T						T			
12.1	5.7	reater than	r' ding 35'	CPVC	×	×	×	×	×	×	¥	×	¥	×	¥	¥	ž	¥	¥	¥	₹	¥	Ą	Ϋ́	Ϋ́	Ą
RED P OF THE PIPE	Type 7	Fill Height: Greater than	30' not exceeding 35'	RCCP	AN	>	>	^	>	>	>	>	>	>	>	>		>	>	>	130	130	130	130	130	130
STORM SEWERS (metric) KIND OF MATERIAL PERMITTED AND STRENGTH REQUIRED FOR A GIVEN PIPE DIAMETERS AND FILL HEIGHTS OVER THE TOP OF		er than	30,	CPVC	×	×	×	×	×	×	AA	×	ž	×	¥	₹	Ą	¥	¥	₹	Ϋ́	¥	ΑN	Ϋ́	Ϋ́	ΑN
(metric) ND STRENC IGHTS OVE	Type 6	ght: Greater than	25' not exceeding 30'	PVC	×	×	×	×	×	×	ΑN	×	Ϋ́	×	×	×	ΑN	Ϋ́	Š	Ą	¥	Š	NA	¥	¥	A A
STORM SEWERS (metric) L PERMITTED AND STRE ERS AND FILL HEIGHTS (		Fill Height:	not	RCCP	¥	>	>	>	>	>	>	>	>	>	>	>	>	>	>	>	110	110	110	120	120	120
STOR ERIAL PEF AETERS AI		er than	25'	CPVC	×	×	×	×	×	×	₹	×	NA	×	₹	NA	AN	¥	ΝA	ΝΑ	Ϋ́	ΝΑ	ž	ž	¥	¥
O OF MATI PIPE DIAN	Type 5	Fill Height: Greater than	20' not exceeding 25'	PVC	×	×	×	×	×	×	₹ Z	×	NA	×	×	×	ΑN	Ϋ́	NA	NA	Ϋ́	NA	Ϋ́	₹	Š	ΑA
KINI R A GIVEN		Fill Heig	not e	RCCP	Α	≥	2	≥	≥	≥	≥	≥	≥	2	≥	2	≥	≥	2	>	100	100	100	100	100	100
FO		Nominal	Diameter in.		250	300	375	450	525	009	675	750	825	006	1050	1200	1350	1500	1650	1800	1950	2100	2250	2400	2550	2700

RCCP PVC CPVC ESCP X NA Note

Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
Polyvinyl Chloride Pipe
Corrugated Polyvinyl Chloride Pipe
Extra Strength Clay Pipe
This material may be used for the given pipe diameter and fill height.
This material is Not Acceptable for the given pipe diameter and fill height.
RCCP with a number instead of a Roman numeral shall be furnished according to AASHTO M170 Section 6. This number represents the metric D-load to produce a 25.4 micro-meter crack.

Revise the sixth paragraph of Article 550.06 of the Standard Specifications to read:

"PVC, PE and CPP pipes shall be joined according to the manufacturer's specifications."

Revise the first and second paragraphs of Article 550.08 of the Standard Specifications to read:

"550.08 Deflection Testing for Storm Sewers. All PVC, PE, and CPP storm sewers shall be tested for deflection not less than 30 days after the pipe is installed and the backfill compacted. The testing shall be performed in the presence of the Engineer.

For PVC, PE, and CPP storm sewers with diameters 24 in. (600 mm) or smaller, a mandrel drag shall be used for deflection testing. For PVC, PE, and CPP storm sewers with diameters over 24 in. (600 mm), deflection measurements other than by a mandrel shall be used."

Revise the fifth paragraph of Article 550.08 to read as follows.

"The outside diameter of the mandrel shall be 95 percent of the base inside diameter. For all PVC pipe the base inside diameter shall be defined using ASTM D 3034 methodology. For all PE and CPP pipe, the base inside diameter shall be defined as the average inside diameter based on the minimum and maximum tolerances specified in the corresponding ASTM or AASHTO material specifications."

Revise the first paragraph of Article 1040.03 of the Standard Specifications to read:

"1040.03 Polyvinyl Chloride (PVC) Pipe. Acceptance testing of PVC pipe and fittings shall be accomplished during the same construction season in which they are installed. The section properties shall be according to the manufacturer pre-submitted geometric properties on file with the Department. The manufacturer shall submit written certification that the material meets those properties. The pipe shall meet the following additional requirements."

Delete Articles 1040.03(e) and (f) of the Standard Specifications.

Revise Articles 1040.04(c) and (d) of the Standard Specifications to read:

- "(c) PE Profile Wall Pipe for Insertion Lining. The pipe shall be according to ASTM F 894. When used for insertion lining of pipe culverts, the pipe liner shall have a minimum pipe stiffness of 46 psi (317 kPa) at five percent deflection for nominal inside diameters of 42 in. (1050 mm) or less. For nominal inside diameters of greater than 42 in. (1050 mm), the pipe liner shall have a minimum pipe stiffness of 32.5 psi (225 kPa) at five percent deflection. All sizes shall have wall construction that presents essentially smooth internal and external surfaces.
- (d) PE Pipe with a Smooth Interior. The pipe shall be according to ASTM F 714 (DR 32.5) with a minimum cell classification of PE 335434 as defined in ASTM D 3350. The section properties shall be according to the manufacturer pre-submitted geometric properties on file with the Department. The manufacturer shall submit written



certification that the material meets those properties and the resin used to manufacture the pipe meets or exceeds the minimum cell classification requirements."

Add the following to Section 1040 of the Standard Specifications:

"1040.08 Polypropylene (PP) Pipe. Storage and handling shall be according to the manufacturer's recommendations, except in no case shall the pipe be exposed to direct sunlight for more than six months. Acceptance testing of the pipe shall be accomplished during the same construction season in which it is installed. The section properties shall be according to the manufacturer pre-submitted geometric properties on file with the Department. The manufacturer shall submit written certification that the material meets those properties. The pipe shall meet the following additional requirements.

- (a) Corrugated PP Pipe with a Smooth Interior. The pipe shall be according to AAHSTO M 330 (nominal size 12 to 60 in. (300 to 1500 mm)). The pipe shall be Type S or D.
- (b) Perforated Corrugated PP Pipe with A Smooth Interior. The pipe shall be according to AASHTO M 330 (nominal size – 12 to 60 in. (300 to 1500 mm)). The pipe shall be Type SP. In addition, the top centerline of the pipe shall be marked so that it is readily visible from the top of the trench before backfilling, and the upper ends of the slot perforations shall be a minimum of ten degrees below the horizontal."



### PAYROLLS AND PAYROLL RECORDS (BDE)

Effective: January 1, 2014

<u>FEDERAL AID CONTRACTS</u>. Revise the following section of Check Sheet #1 of the Recurring Special Provisions to read:

### "STATEMENTS AND PAYROLLS

The payroll records shall include the worker's name, the worker's address, the worker's telephone number when available, the worker's social security number, the worker's classification or classifications, the worker's gross and net wages paid in each pay period, the worker's number of hours worked each day, the worker's starting and ending times of work each day. However, any Contractor or subcontractor who remits contributions to a fringe benefit fund that is not jointly maintained and jointly governed by one or more employers and one or more labor organization must additionally submit the worker's hourly wage rate, the worker's hourly overtime wage rate, the worker's hourly fringe benefit rates, the name and address of each fringe benefit fund, the plan sponsor of each fringe benefit, if applicable, and the plan administrator of each fringe benefit, if applicable.

The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work, except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead, the payrolls shall include an identification number for each employee (e.g., the last four digits of the employee's social security number). In addition, starting and ending times of work each day may be omitted from the payroll records submitted to the Engineer. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form."

<u>STATE CONTRACTS</u>. Revise Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

### "IV. COMPLIANCE WITH THE PREVAILING WAGE ACT

- 1. Prevailing Wages. All wages paid by the Contractor and each subcontractor shall be in compliance with The Prevailing Wage Act (820 ILCS 130), as amended, except where a prevailing wage violates a federal law, order, or ruling, the rate conforming to the federal law, order, or ruling shall govern. The Contractor shall be responsible to notify each subcontractor of the wage rates set forth in this contract and any revisions thereto. If the Department of Labor revises the wage rates, the Contractor will not be allowed additional compensation on account of said revisions.
- Payroll Records. The Contractor and each subcontractor shall make and keep, for a period of five years from the later of the date of final payment under the contract or completion of the contract, records of the wages paid to his/her workers. The payroll



records shall include the worker's name, the worker's address, the worker's telephone number when available, the worker's social security number, the worker's classification or classifications, the worker's gross and net wages paid in each pay period, the worker's number of hours worked each day, the worker's starting and ending times of work each day. However, any contractor or subcontractor who remits contributions to a fringe benefit fund that is not jointly maintained and jointly governed by one or more employers and one or more labor organization must additionally submit the worker's hourly wage rate, the worker's hourly overtime wage rate, the worker's hourly fringe benefit rates, the name and address of each fringe benefit fund, the plan sponsor of each fringe benefit, if applicable, and the plan administrator of each fringe benefit, if applicable. Upon seven business days' notice, these records shall be available at a location within the State, during reasonable hours, for inspection by the Department or the Department of Labor; and Federal, State, or local law enforcement agencies and prosecutors.

3. Submission of Payroll Records. The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work, except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall include an identification number for each employee (e.g., the last four digits of the employee's social security number). In addition, starting and ending times of work each day may be omitted from the payroll records submitted to the Engineer. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form.

Each submittal shall be accompanied by a statement signed by the Contractor or subcontractor, or an officer, employee, or officer thereof, which avers that: (i) he or she has examined the records and such records are true and accurate; (ii) the hourly rate paid to each worker is not less than the general prevailing rate of hourly wages required by the Act; and (iii) the Contractor or subcontractor is aware that filing a payroll record that he/she knows to be false is a Class A misdemeanor.

4. Employee Interviews. The Contractor and each subcontractor shall permit his/her employees to be interviewed on the job, during working hours, by compliance investigators of the Department or the Department of Labor."

# PORTLAND CEMENT CONCRETE - CURING OF ABUTMENTS AND PIERS (BDE)

Effective: January 1, 2014

Revise Note 7/ of the Index Table of Curing and Protection of Concrete Construction of Article 1020.13 of the Standard Specifications to read:

"7/ Asphalt emulsion for waterproofing may be used in lieu of other curing methods when specified and permitted according to Article 503.18. The top surfaces of abutments and piers shall be cured according to Article 1020.13(a)(3) or (5)."



# PORTLAND CEMENT CONCRETE EQUIPMENT (BDE)

Effective: November 1, 2013

Add the following to the first paragraph of Article 1103.03(a)(5) of the Standard Specifications to read:

"As an alternative to a locking key, the start and finish time for mixing may be automatically printed on the batch ticket. The start and finish time shall be reported to the nearest second."



### PROGRESS PAYMENTS (BDE)

Effective: November 2, 2013

Revise Article 109.07(a) of the Standard Specifications to read:

"(a) Progress Payments. At least once each month, the Engineer will make a written estimate of the quantity of work performed in accordance with the contract, and the value thereof at the contract unit prices. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1000.00 will be approved for payment other than the final payment.

Progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics' Lien Act, 770 ILCS 60/23(c).

If a Contractor or subcontractor has defaulted on a loan issued under the Department's Disadvantaged Business Revolving Loan Program (20 ILCS 2705/2705-610), progress payments may be reduced pursuant to the terms of that loan agreement. In such cases, the amount of the estimate related to the work performed by the Contractor or subcontractor, in default of the loan agreement, will be offset, in whole or in part, and vouchered by the Department to the Working Capital Revolving Fund or designated escrow account. Payment for the work shall be considered as issued and received by the Contractor or subcontractor on the date of the offset voucher. Further, the amount of the offset voucher shall be a credit against the Department's obligation to pay the Contractor, the Contractor's obligation to pay the subcontractor, and the Contractor's or subcontractor's total loan indebtedness to the Department. The offset shall continue until such time as the entire loan indebtedness is satisfied. The Department will notify the Contractor and Fund Control Agent in a timely manner of such offset. The Contractor or subcontractor shall not be entitled to additional payment in consideration of the offset.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved."

## QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE)

Effective: January 1, 2012 Revised: January 1, 2014

Revise Note 7/ of Schedule B of Recurring Special Provision Check Sheet #31 of the Standard Specifications to read:

7/ The test of record for strength shall be the day indicated in Article 1020.04. For cement aggregate mixture II, a strength requirement is not specified and testing is not required. Additional strength testing to determine early falsework and form removal, early pavement or bridge opening to traffic, or to monitor strengths is at the discretion of the Contractor. Strength shall be defined as the average of two 6 x 12 in. (150 x 300 mm) cylinder breaks, three 4 x 8 in. (100 x 200 mm) cylinder breaks, or two beam breaks for field tests. Per Illinois Modified AASHTO T 23, cylinders shall be 6 x 12 in. (150 x 300 mm) when the nominal maximum size of the coarse aggregate exceeds 1 in. (25 mm).

### RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)

Effective: November 1, 2012 Revise: November 1, 2013

Revise Section 1031 of the Standard Specifications to read:

# "SECTION 1031. RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES

**1031.01 Description.** Reclaimed asphalt pavement and reclaimed asphalt shingles shall be according to the following.

- (a) Reclaimed Asphalt Pavement (RAP). RAP is the material produced by cold milling or crushing an existing hot-mix asphalt (HMA) pavement. The Contractor shall supply written documentation that the RAP originated from routes or airfields under federal, state, or local agency jurisdiction.
- (b) Reclaimed Asphalt Shingles (RAS). Reclaimed asphalt shingles (RAS). RAS is from the processing and grinding of preconsumer or post-consumer shingles. RAS shall be a clean and uniform material with a maximum of 0.5 percent unacceptable material, as defined in Bureau of Materials and Physical Research Policy Memorandum "Reclaimed Asphalt Shingle (RAS) Sources", by weight of RAS. All RAS used shall come from a Bureau of Materials and Physical Research approved processing facility where it shall be ground and processed to 100 percent passing the 3/8 in. (9.5 mm) sieve and 93 percent passing the #4 (4.75 mm) sieve based on a dry shake gradation. RAS shall be uniform in gradation and asphalt binder content and shall meet the testing requirements specified herein. In addition, RAS shall meet the following Type 1 or Type 2 requirements.
  - (1) Type 1. Type 1 RAS shall be processed, preconsumer asphalt shingles salvaged from the manufacture of residential asphalt roofing shingles.
  - (2) Type 2. Type 2 RAS shall be processed post-consumer shingles only, salvaged from residential, or four unit or less dwellings not subject to the National Emission Standards for Hazardous Air Pollutants (NESHAP).

1031.02 Stockpiles. RAP and RAS stockpiles shall be according to the following.

(a) RAP Stockpiles. The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. No additional RAP shall be added to the pile after the pile has been sealed. Stockpiles shall be sufficiently separated to prevent intermingling at the base. Stockpiles shall be identified by signs indicating the type as listed below (i.e. "Homogeneous Surface"). Prior to milling, the Contractor shall request the District provide documentation on the quality of the RAP to clarify the appropriate stockpile.

(1) Fractionated RAP (FRAP). FRAP shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures. The coarse aggregate in FRAP shall be crushed aggregate and may represent more than one aggregate type and/or quality but shall be at least C quality. All FRAP shall be fractionated prior to testing by screening into a minimum of two size fractions with the separation occurring on or between the #4 (4.75 mm) and 1/2 in. (12.5 mm) sieves. Agglomerations shall be minimized such that 100 percent of the RAP shall pass the sieve size specified below for the mix into which the FRAP will be incorporated.

Mixture FRAP will be used in:	Sieve Size that 100% of FRAP
	Shall Pass
IL-25.0	2 in. (50 mm)
IL-19.0	1 1/2 in. (40 mm)
IL-12.5	1 in. (25 mm)
IL-9.5	3/4 in. (20 mm)
IL-4.75	1/2 in. (13 mm)

- (2) Homogeneous. Homogeneous RAP stockpiles shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures and represent: 1) the same aggregate quality, but shall be at least C quality; 2) the same type of crushed aggregate (either crushed natural aggregate, ACBF slag, or steel slag); 3) similar gradation; and 4) similar asphalt binder content. If approved by the Engineer, combined single pass surface/binder millings may be considered "homogenous" with a quality rating dictated by the lowest coarse aggregate quality present in the mixture.
- (3) Conglomerate. Conglomerate RAP stockpiles shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality but shall be at least C quality. This RAP may have an inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate RAP shall be processed prior to testing by crushing to where all RAP shall pass the 5/8 in. (16 mm) or smaller screen. Conglomerate RAP stockpiles shall not contain steel slag.
- (4) Conglomerate "D" Quality (DQ). Conglomerate DQ RAP stockpiles shall consist of RAP from Class I, HMA (High or Low ESAL), or "All Other" (as defined by Article 1030.04(a)(3)) mixtures. The coarse aggregate in this RAP may be crushed or round but shall be at least D quality. This RAP may have an inconsistent gradation and/or asphalt binder content. Conglomerate DQ RAP stockpiles shall not contain steel slag.
- (5) Non-Quality. RAP stockpiles that do not meet the requirements of the stockpile categories listed above shall be classified as "Non-Quality".

RAP/FRAP containing contaminants, such as earth, brick, sand, concrete, sheet asphalt, bituminous surface treatment (i.e. chip seal), pavement fabric, joint sealants, etc., will be unacceptable unless the contaminants are removed to the satisfaction of the Engineer. Sheet asphalt shall be stockpiled separately.

(b) RAS Stockpiles. Type 1 and Type 2 RAS shall be stockpiled separately and shall not be intermingled. Each stockpile shall be signed indicating what type of RAS is present.

Unless otherwise specified by the Engineer, mechanically blending manufactured sand (FM 20 or FM 22) up to an equal weight of RAS with the processed RAS will be permitted to improve workability. The sand shall be "B Quality" or better from an approved Aggregate Gradation Control System source. The sand shall be accounted for in the mix design and during HMA production.

Records identifying the shingle processing facility supplying the RAS, RAS type and lot number shall be maintained by project contract number and kept for a minimum of three years.

1031.03 Testing. RAP/FRAP and RAS testing shall be according to the following.

- (a) RAP/FRAP Testing. When used in HMA, the RAP/FRAP shall be sampled and tested either during or after stockpiling.
  - (1) During Stockpiling. For testing during stockpiling, washed extraction samples shall be run at the minimum frequency of one sample per 500 tons (450 metric tons) for the first 2000 tons (1800 metric tons) and one sample per 2000 tons (1800 metric tons) thereafter. A minimum of five tests shall be required for stockpiles less than 4000 tons (3600 metric tons).
  - (2) After Stockpiling. For testing after stockpiling, the Contractor shall submit a plan for approval to the District proposing a satisfactory method of sampling and testing the RAP/FRAP pile either in-situ or by restockpiling. The sampling plan shall meet the minimum frequency required above and detail the procedure used to obtain representative samples throughout the pile for testing.

Each sample shall be split to obtain two equal samples of test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedure. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

(b) RAS Testing. RAS or RAS blended with manufactured sand shall be sampled and tested during stockpiling according to Illinois Department of Transportation Policy Memorandum, "Reclaimed Asphalt Shingle (RAS) Source".



Samples shall be collected during stockpiling at the minimum frequency of one sample per 200 tons (180 metric tons) for the first 1000 tons (900 metric tons) and one sample per 250 tons (225 metric tons) thereafter. A minimum of five samples are required for stockpiles less than 1000 tons (900 metric tons). Once a ≤ 1000 ton (900 metric ton), five-sample/test stockpile has been established it shall be sealed. Additional incoming RAS or RAS blended with manufactured sand shall be stockpiled in a separate working pile as designated in the Quality Control plan and only added to the sealed stockpile when the test results of the working pile are complete and are found to meet the tolerances specified herein for the original sealed RAS stockpile.

Before testing, each sample shall be split to obtain two test samples. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall perform a washed extraction and test for unacceptable materials on the other test sample according to Department procedures. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

If the sampling and testing was performed at the shingle processing facility in accordance with the QC Plan, the Contractor shall obtain and make available all of the test results from start of the initial stockpile.

1031.04 Evaluation of Tests. Evaluation of tests results shall be according to the following.

(a) Evaluation of RAP/FRAP Test Results. All of the extraction results shall be compiled and averaged for asphalt binder content and gradation and, when applicable G<sub>mm</sub>. Individual extraction test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	FRAP/Homogeneous /Conglomerate	Conglomerate "D"  Quality
1 in. (25 mm)		± 5 %
1/2 in. (12.5 mm)	±8%	± 15 %
No. 4 (4.75 mm)	±6%	± 13 %
No. 8 (2.36 mm)	± 5 %	
No. 16 (1.18 mm)		± 15 %
No. 30 (600 μm)	± 5 %	
No. 200 (75 μm)	± 2.0 %	± 4.0 %
Asphalt Binder	± 0.4 % <sup>1/</sup>	± 0.5 %
G <sub>mm</sub>	± 0.03	

1/ The tolerance for FRAP shall be  $\pm$  0.3 %.

If more than 20 percent of the individual sieves and/or asphalt binder content tests are out of the above tolerances, the RAP/FRAP shall not be used in HMA unless the

RAP/FRAP representing the failing tests is removed from the stockpile. All test data and acceptance ranges shall be sent to the District for evaluation.

With the approval of the Engineer, the ignition oven may be substituted for extractions according to the Illinois Test Procedure, "Calibration of the Ignition Oven for the Purpose of Characterizing Reclaimed Asphalt Pavement (RAP)".

(b) Evaluation of RAS and RAS Blended with Manufactured Sand Test Results. All of the test results, with the exception of percent unacceptable materials, shall be compiled and averaged for asphalt binder content and gradation. Individual test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	RAS
No. 8 (2.36 mm)	± 5 %
No. 16 (1.18 mm)	± 5 %
No. 30 (600 µm)	± 4 %
No. 200 (75 μm)	± 2.0 %
Asphalt Binder Content	± 1.5 %

If more than 20 percent of the individual sieves and/or asphalt binder content tests are out of the above tolerances, or if the percent unacceptable material exceeds 0.5 percent by weight of material retained on the # 4 (4.75 mm) sieve, the RAS or RAS blend shall not be used in Department projects. All test data and acceptance ranges shall be sent to the District for evaluation.

### 1031.05 Quality Designation of Aggregate in RAP/FRAP.

- (a) RAP. The aggregate quality of the RAP for homogenous, conglomerate, and conglomerate "D" quality stockpiles shall be set by the lowest quality of coarse aggregate in the RAP stockpile and are designated as follows.
  - (1) RAP from Class I, Superpave/HMA (High ESAL), or (Low ESAL) IL-9.5L surface mixtures are designated as containing Class B quality coarse aggregate.
  - (2) RAP from Superpave/HMA (Low ESAL) IL-19.0L binder mixture is designated as Class D quality coarse aggregate.
  - (3) RAP from Class I, Superpave/HMA (High ESAL) binder mixtures, bituminous base course mixtures, and bituminous base course widening mixtures are designated as containing Class C quality coarse aggregate.
  - (4) RAP from bituminous stabilized subbase and BAM shoulders are designated as containing Class D quality coarse aggregate.
- (b) FRAP. If the Engineer has documentation of the quality of the FRAP aggregate, the Contractor shall use the assigned quality provided by the Engineer.



If the quality is not known, the quality shall be determined as follows. Coarse and fine FRAP stockpiles containing plus #4 (4.75 mm) sieve coarse aggregate shall have a maximum tonnage of 5,000 tons (4,500 metric tons). The Contractor shall obtain a representative sample witnessed by the Engineer. The sample shall be a minimum of 50 lb (25 kg). The sample shall be extracted according to Illinois Modified AASHTO T 164 by a consultant prequalified by the Department for the specified testing. The consultant shall submit the test results along with the recovered aggregate to the District Office. The cost for this testing shall be paid by the Contractor. The District will forward the sample to the BMPR Aggregate Lab for MicroDeval Testing, according to Illinois Modified AASHTO T 327. A maximum loss of 15.0 percent will be applied for all HMA applications.

**1031.06 Use of RAP/FRAP and/or RAS in HMA.** The use of RAP/FRAP and/or RAS shall be a Contractor's option when constructing HMA in all contracts.

- (a) RAP/FRAP. The use of RAP/FRAP in HMA shall be as follows.
  - (1) Coarse Aggregate Size. The coarse aggregate in all RAP shall be equal to or less than the nominal maximum size requirement for the HMA mixture to be produced.
  - (2) Steel Slag Stockpiles. Homogeneous RAP stockpiles containing steel slag will be approved for use in all HMA (High ESAL and Low ESAL) Surface and Binder Mixture applications.
  - (3) Use in HMA Surface Mixtures (High and Low ESAL). RAP/FRAP stockpiles for use in HMA surface mixtures (High and Low ESAL) shall be FRAP or homogeneous in which the coarse aggregate is Class B quality or better. RAP/FRAP from Conglomerate stockpiles shall be considered equivalent to limestone for frictional considerations. Known frictional contributions from plus #4 (4.75 mm) homogeneous RAP and FRAP stockpiles will be accounted for in meeting frictional requirements in the specified mixture.
  - (4) Use in HMA Binder Mixtures (High and Low ESAL), HMA Base Course, and HMA Base Course Widening. RAP/FRAP stockpiles for use in HMA binder mixtures (High and Low ESAL), HMA base course, and HMA base course widening shall be FRAP, homogeneous, or conglomerate, in which the coarse aggregate is Class C quality or better.
  - (5) Use in Shoulders and Subbase. RAP/FRAP stockpiles for use in HMA shoulders and stabilized subbase (HMA) shall be FRAP, homogeneous, conglomerate, or conglomerate DQ.
  - (6) When the Contractor chooses the RAP option, the percentage of RAP shall not exceed the amounts indicated in Article 1031.06(c)(1) below for a given N Design.

- (b) RAS. RAS meeting Type 1 or Type 2 requirements will be permitted in all HMA applications as specified herein.
- (c) RAP/FRAP and/or RAS Usage Limits. Type 1 or Type 2 RAS may be used alone or in conjunction with RAP or FRAP in HMA mixtures up to a maximum of 5.0% by weight of the total mix.
  - (1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the Max RAP/RAS ABR table listed below for the given Ndesign.

RAP/RAS Maximum Asphalt Binder Replacement (ABR) Percentage

HMA Mixtures 1/, 2/	RAP	P/RAS Maximum AB	R %
Ndesign	Binder/Leveling Binder	Surface	Polymer Modified
30	30	30	10
50	25	15	10
70	15	10	10
90	10	10	10
105	10	10	10

- 1/ For HMA "All Other" (shoulder and stabilized subbase) N-30, the RAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG64-22 to be reduced to a PG58-28). If warm mix asphalt (WMA) technology is utilized, and production temperatures do not exceed 275 °F (135 °C) the high and low virgin asphalt binder grades shall each be reduced by one grade when RAP/RAS ABR exceeds 25 percent (i.e. 26 percent RAP/RAS ABR would require a virgin asphalt binder grade of PG64-22 to be reduced to a PG58-28).
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the FRAP/RAS table listed below for the given N design.

FRAP/RAS Maximum Asphalt Binder Replacement (ABR) Percentage

HMA Mixtures	FRA	P/RAS Maximun	n ABR %
Ndesign	Binder/Leveling Binder	Surface	Polymer Modified 37, 47
30	40	40	10

50	40	30	10
70	30	20	10
90	30	20	10
105	30	15	10

- 1/ For HMA "All Other" (shoulder and stabilized subbase) N30, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG64-22 to be reduced to a PG58-28). If warm mix asphalt (WMA) technology is utilized, and production temperatures do not exceed 275 °F (135 °C) the high and low virgin asphalt binder grades shall each be reduced by one grade when FRAP/RAS ABR exceeds 25 percent (i.e. 26 percent ABR would require a virgin asphalt binder grade of PG64-22 to be reduced to a PG58-28).
- 3/ For SMA the FRAP/RAS ABR shall not exceed 20 percent.
- 4/ For IL-4.75 mix the FRAP/RAS ABR shall not exceed 30 percent.

**1031.07 HMA Mix Designs.** At the Contractor's option, HMA mixtures may be constructed utilizing RAP/FRAP and/or RAS material meeting the detailed requirements specified herein.

- (a) RAP/FRAP and/or RAS. RAP/FRAP and/or RAS mix designs shall be submitted for verification. If additional RAP/FRAP stockpiles are tested and found that no more than 20 percent of the results, as defined under "Testing" herein, are outside of the control tolerances set for the original RAP/FRAP stockpile and HMA mix design, and meets all of the requirements herein, the additional RAP/FRAP stockpiles may be used in the original mix design at the percent previously verified.
- (b) RAS. Type 1 and Type 2 RAS are not interchangeable in a mix design. A RAS stone bulk specific gravity (Gsb) of 2.500 shall be used for mix design purposes.

1031.08 HMA Production. HMA production utilizing RAP/FRAP and/or RAS shall be as follows.

(a) RAP/FRAP. The coarse aggregate in all RAP/FRAP used shall be equal to or less than the nominal maximum size requirement for the HMA mixture being produced.

To remove or reduce agglomerated material, a scalping screen, gator, crushing unit, or comparable sizing device approved by the Engineer shall be used in the RAP feed system to remove or reduce oversized material. If material passing the sizing device adversely affects the mix production or quality of the mix, the sizing device shall be set at a size specified by the Engineer.



If the RAP/FRAP control tolerances or QC/QA test results require corrective action, the Contractor shall cease production of the mixture containing RAP/FRAP and either switch to the virgin aggregate design or submit a new RAP/FRAP design.

(b) RAS. RAS shall be incorporated into the HMA mixture either by a separate weight depletion system or by using the RAP weigh belt. Either feed system shall be interlocked with the aggregate feed or weigh system to maintain correct proportions for all rates of production and batch sizes. The portion of RAS shall be controlled accurately to within ± 0.5 percent of the amount of RAS utilized. When using the weight depletion system, flow indicators or sensing devices shall be provided and interlocked with the plant controls such that the mixture production is halted when RAS flow is interrupted.

When producing HMA containing RAS, a positive dust control system shall be utilized.

- (c) RAP/FRAP and/or RAS. HMA plants utilizing RAP/FRAP and/or RAS shall be capable of automatically recording and printing the following information.
  - (1) Dryer Drum Plants.
    - a. Date, month, year, and time to the nearest minute for each print.
    - b. HMA mix number assigned by the Department.
    - c. Accumulated weight of dry aggregate (combined or individual) in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
    - d. Accumulated dry weight of RAP/FRAP/RAS in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
    - e. Accumulated mineral filler in revolutions, tons (metric tons), etc. to the nearest 0.1 unit.
    - f. Accumulated asphalt binder in gallons (liters), tons (metric tons), etc. to the nearest 0.1 unit.
    - g. Residual asphalt binder in the RAP/FRAP material as a percent of the total mix to the nearest 0.1 percent.
    - h. Aggregate and RAP/FRAP moisture compensators in percent as set on the control panel. (Required when accumulated or individual aggregate and RAP/FRAP are printed in wet condition.)
  - (2) Batch Plants.
    - a. Date, month, year, and time to the nearest minute for each print.

- b. HMA mix number assigned by the Department.
- c. Individual virgin aggregate hot bin batch weights to the nearest pound (kilogram).
- d. Mineral filler weight to the nearest pound (kilogram).
- f. RAP/FRAP/RAS weight to the nearest pound (kilogram).
- g. Virgin asphalt binder weight to the nearest pound (kilogram).
- h. Residual asphalt binder in the RAP/FRAP/RAS material as a percent of the total mix to the nearest 0.1 percent.

The printouts shall be maintained in a file at the plant for a minimum of one year or as directed by the Engineer and shall be made available upon request. The printing system will be inspected by the Engineer prior to production and verified at the beginning of each construction season thereafter.

1031.09 RAP in Aggregate Surface Course and Aggregate Shoulders. The use of RAP in aggregate surface course (temporary access entrances only) and aggregate wedge shoulders Type B shall be as follows.

- (a) Stockpiles and Testing. RAP stockpiles may be any of those listed in Article 1031.02, except "Non-Quality" and "FRAP". The testing requirements of Article 1031.03 shall not apply. RAP used to construct aggregate surface course and aggregate shoulders shall be according to the current Bureau of Materials and Physical Research's Policy Memorandum, "Reclaimed Asphalt Pavement (RAP) for Aggregate Applications".
- (b) Gradation. One hundred percent of the RAP material shall pass the 1 1/2 in. (37.5 mm) sieve. The RAP material shall be reasonably well graded from coarse to fine. RAP material that is gap-graded or single sized will not be accepted."

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

### REINFORCEMENT BARS (BDE)

Effective: November 1, 2013

Revise the first and second paragraphs of Article 508.05 of the Standard Specifications to read:

"508.05 Placing and Securing. All reinforcement bars shall be placed and tied securely at the locations and in the configuration shown on the plans prior to the placement of concrete. Manual welding of reinforcement may only be permitted or precast concrete products as indicated in the current Bureau of Materials and Physical Research Policy Memorandum "Quality Control / Quality Assurance Program for Precast Concrete Products", and for precast prestressed concrete products as indicated in the Department's current "Manual for Fabrication of Precast Prestressed Concrete Products". Reinforcement bars shall not be placed by sticking or floating into place or immediately after placement of the concrete.

Bars shall be tied at all intersections, except where the center to center dimension is less than 1 ft (300 mm) in each direction, in which case alternate intersections shall be tied. Molded plastic clips may be used in lieu of wire to secure bar intersections, but shall not be permitted in horizontal bar mats subject to construction foot traffic or to secure longitudinal bar laps. Plastic clips shall adequately secure the reinforcement bars, and shall permit the concrete to flow through and fully encase the reinforcement. Plastic clips may be recycled plastic, and shall meet the approval of the Engineer. The number of ties as specified shall be doubled for lap splices at the stage construction line of concrete bridge decks when traffic is allowed on the first completed stage during the pouring of the second stage."

Revise the fifth paragraph of Article 508.05 of the Standard Specifications to read:

"Supports for reinforcement in bridge decks shall be metal. For all other concrete construction the supports shall be metal or plastic. Metal bar supports shall be made of cold-drawn wire, or other approved material and shall be either epoxy coated, galvanized or plastic tipped. When the reinforcement bars are epoxy coated, the metal supports shall be epoxy coated. Plastic supports may be recycled plastic. Supports shall be provided in sufficient number and spaced to provide the required clearances. Supports shall adequately support the reinforcement bars, and shall permit the concrete to flow through and fully encase the reinforcement. The legs of supports shall be spaced to allow an opening that is a minimum 1.33 times the nominal maximum aggregate size used in the concrete. Nominal maximum aggregate size is defined as the largest sieve which retains any of the aggregate sample particles. All supports shall meet the approval of the Engineer."

Revise the first sentence of the eighth paragraph of Article 508.05 of the Standard Specifications to read:

"Epoxy coated reinforcement bars shall be tied with plastic coated wire, epoxy coated wire, or molded plastic clips where allowed."

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

Add the following sentence to the end of the first paragraph of Article 508.06(c) of the Standard Specifications:

"In addition, the total slip of the bars within the splice sleeve of the connector after loading in tension to 30 ksi (207 MPa) and relaxing to 3 ksi (20.7 MPa) shall not exceed 0.01 in. (254 microns)."

Revise Article 1042.03(d) of the Standard Specifications to read:

"(d) Reinforcement and Accessories: The concrete cover over all reinforcement shall be within ±1/4 in. (±6 mm) of the specified cover.

Welded wire fabric shall be accurately bent and tied in place.

Miscellaneous accessories to be cast into the concrete or for forming holes and recesses shall be carefully located and rigidly held in place by bolts, clamps, or other effective means. If paper tubes are used for vertical dowel holes, or other vertical holes which require grouting, they shall be removed before transportation to the construction site."



## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2012 Revised: November 2, 2012

Revise Article 669.01 of the Standard Specifications to read:

"669.01 Description. This work shall consist of the transportation and proper disposal of contaminated soil and water. This work shall also consist of the removal, transportation, and proper disposal of underground storage tanks (UST), their content and associated underground piping to the point where the piping is above the ground, including determining the content types and estimated quantities."

Revise Article 669.08 of the Standard Specifications to read:

"669.08 Contaminated Soil and/or Groundwater Monitoring. The Contractor shall hire a qualified environmental firm to monitor the area containing the regulated substances. The affected area shall be monitored with a photoionization detector (PID) utilizing a lamp of 10.6eV or greater or a flame ionization detector (FID). Any field screen reading on the PID or FID in excess of background levels indicates the potential presence of contaminated material requiring handling as a non-special waste, special waste, or hazardous waste. No excavated soils can be taken to a clean construction and demolition debris (CCDD) facility or an uncontaminated soil fill operation with detectable PID or FID meter readings that are above background. The PID or FID meter shall be calibrated on-site and background level readings taken and recorded daily. All testing shall be done by a qualified engineer/technician. Such testing and monitoring shall be included in the work. The Contractor shall identify the exact limits of removal of non-special waste, special waste, or hazardous waste. All limits shall be approved by the Engineer prior to excavation. The Contractor shall take all necessary precautions.

Based upon the land use history of the subject property and/or PID or FID readings indicating contamination, a soil or groundwater sample shall be taken from the same location and submitted to an approved laboratory. Soil or groundwater samples shall be analyzed for the contaminants of concern, including pH, based on the property's land use history or the parameters listed in the maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605. The analytical results shall serve to document the level of soil contamination. Soil and groundwater samples may be required at the discretion of the Engineer to verify the level of soil and groundwater contamination.

Samples shall be grab samples (not combined with other locations). The samples shall be taken with decontaminated or disposable instruments. The samples shall be placed in sealed containers and transported in an insulated container to the laboratory. The container shall maintain a temperature of 39 °F (4 °C). All samples shall be clearly labeled. The labels shall indicate the sample number, date sampled, location and elevation, and any other observations.

The laboratory shall use analytical methods which are able to meet the lowest appropriate practical quantitation limits (PQL) or estimated quantitation limit (EQL) specified in "Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods", EPA Publication No. SW-846 and "Methods for the Determination of Organic Compounds in Drinking Water", EPA, EMSL, EPA-600/4-88/039. For parameters where the specified cleanup objective is below the acceptable detection limit (ADL), the ADL shall serve as the cleanup objective. For other parameters the ADL shall be equal to or below the specified cleanup objective."

Replace the first two paragraphs of Article 669.09 of the Standard Specifications with the following:

"669.09 Contaminated Soil and/or Groundwater Management and Disposal. The management and disposal of contaminated soil and/or groundwater shall be according to the following:

- (a) Soil Analytical Results Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels exceed the most stringent maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605, the soil shall be managed as follows:
  - (1) When analytical results indicate inorganic chemical constituents exceed the most stringent MAC but they are still considered within area background levels by the Engineer, the excavated soil can be utilized within the construction limits as fill, when suitable. Such soil excavated for storm sewers can be placed back into the excavated trench as backfill, when suitable, unless trench backfill is specified. If the soils cannot be utilized within the construction limits, they shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
  - (2) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for a Metropolitan Statistical Area (MSA) County, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
  - (3) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, or the MAC within the Chicago corporate limits, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago or within the Chicago corporate limits provided the pH of the soil is within the range of 6.25 9.0, inclusive.



- (4) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
- (5) When the Engineer determines soil cannot be managed according to Articles 669.09(a)(1) through (a)(4) above, the soil shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
- (b) Soil Analytical Results Do Not Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels do not exceed the most stringent MAC but the pH of the soil is less than 6.25 or greater than 9.0, the excavated soil can be utilized within the construction limits or managed and disposed of off-site as "uncontaminated soil" according to Article 202.03. However the excavated soil cannot be taken to a CCDD facility or an uncontaminated soil fill operation.
- (c) Groundwater. When groundwater analytical results indicate the detected levels are above Appendix B, Table E of 35 Illinois Administrative Code 742, the most stringent Tier 1 Groundwater Remediation Objectives for Groundwater Component of the Groundwater Ingestion Route for Class 1 groundwater, the groundwater shall be managed off-site as a special waste.

All groundwater encountered within lateral trenches may be managed within the trench and allowed to infiltrate back into the ground. If the groundwater cannot be managed within the trench it must be removed as a special or hazardous waste. The Contractor is prohibited from managing groundwater within the trench by discharging it through any existing or new storm sewer. The Contractor shall install backfill plugs within the area of groundwater contamination.

One backfill plug shall be placed down gradient to the area of groundwater contamination. Backfill plugs shall be installed at intervals not to exceed 50 ft (15 m). Backfill plugs are to be 4 ft (1.2 m) long, measured parallel to the trench, full trench width and depth. Backfill plugs shall not have any fine aggregate bedding or backfill, but shall be entirely cohesive soil or any class of concrete. The Contractor shall provide test data that the material has a permeability of less than 10 <sup>-7</sup> cm/sec according to ASTM D 5084, Method A or per another test method approved by the Engineer."

Revise Article 669.14 of the Standard Specifications to read:

"669.14 Final Environmental Construction Report. At the end of the project, the Contractor will prepare and submit three copies of the Environmental Construction Report on the activities conducted during the life of the project, one copy shall be submitted to the Resident Engineer, one copy shall be submitted to the District's Environmental Studies Unit, and one copy shall be submitted with an electronic copy in Adode.pdf format to the Geologic

FAU 6759 (Sheridan Road)
Section 07-00176-00-BR
City of Pekin
Tazewell County

and Waste Assessment Unit, Bureau of Design and Environment, IDOT, 2300 South Dirksen Parkway, Springfield, Illinois 62764. The technical report shall include all pertinent information regarding the project including, but not limited to:

- (a) Measures taken to identify, monitor, handle, and dispose of soil or groundwater containing regulated substances, to prevent further migration of regulated substances, and to protect workers,
- (b) Cost of identifying, monitoring, handling, and disposing of soil or groundwater containing regulated substances, the cost of preventing further migration of regulated substances, and the cost for worker protection from the regulated substances. All cost should be in the format of the contract pay items listed in the contract plans (identified by the preliminary environmental site investigation (PESA) site number),
- (c) Plan sheets showing the areas containing the regulated substances,
- (d) Field sampling and testing results used to identify the nature and extent of the regulated substances,
- (e) Waste manifests (identified by the preliminary environmental site investigation (PESA) site number) for special or hazardous waste disposal, and
- (f) Landfill tickets (identified by the preliminary environmental site investigation (PESA) site number) for non-special waste disposal."

Revise the second paragraph of Article 669.16 of the Standard Specifications to read:

"The transportation and disposal of soil and other materials from an excavation determined to be contaminated will be paid for at the contract unit price per cubic yard (cubic meter) for NON-SPECIAL WASTE DISPOSAL, OR HAZARDOUS WASTE DISPOSAL."

## REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)

Effective: November 2, 2012

Revise the first four paragraphs of Article 202.03 of the Standard Specifications to read:

"202.03 Removal and Disposal of Surplus, Unstable, Unsuitable, and Organic Materials. Suitable excavated materials shall not be wasted without permission of the Engineer. The Contractor shall dispose of all surplus, unstable, unsuitable, and organic materials, in such a manner that public or private property will not be damaged or endangered.

Suitable earth, stones and boulders naturally occurring within the right-of-way may be placed in fills or embankments in lifts and compacted according to Section 205. Broken concrete without protruding metal bars, bricks, rock, stone, reclaimed asphalt pavement with no expansive aggregate, or uncontaminated dirt and sand generated from construction or demolition activities may be used in embankment or in fill. If used in fills or embankments, these materials shall be placed and compacted to the satisfaction of the Engineer; shall be buried under a minimum of 2 ft (600 mm) of earth cover (except when the materials include only uncontaminated dirt); and shall not create an unsightly appearance or detract from the natural topographic features of an area. Broken concrete without protruding metal bars, bricks, rock, or stone may be used as riprap as approved by the Engineer. If the materials are used for fill in locations within the right-of-way but outside project construction limits, the Contractor must specify to the Engineer, in writing, how the landscape restoration of the fill areas will be accomplished. Placement of fill in such areas shall not commence until the Contractor's landscape restoration plan is approved by the Engineer.

Aside from the materials listed above, all other construction and demolition debris or waste shall be disposed of in a licensed landfill, recycled, reused, or otherwise disposed of as allowed by State or Federal laws and regulations. When the Contractor chooses to dispose of uncontaminated soil at a clean construction and demolition debris (CCDD) facility or at an uncontaminated soil fill operation, it shall be the Contractor's responsibility to have the pH of the material tested to ensure the value is between 6.25 and 9.0, inclusive. A copy of the pH test results shall be provided to the Engineer.

A permit shall be obtained from IEPA and made available to the Engineer prior to open burning of organic materials (i.e., plant refuse resulting from pruning or removal of trees or shrubs) or other construction or demolition debris. Organic materials originating within the right-of-way limits may be chipped or shredded and placed as mulch around landscape plantings within the right-of-way when approved by the Engineer. Chipped or shredded material to be placed as mulch shall not exceed a depth of 6 in. (150 mm)."

## **SEEDING (BDE)**

Effective: November 1, 2012

Revise the following seeding mixture shown in Table 1 of Article 250.07 of the Standard Specifications to read.

"TABLE 1 - SEEDING MIXTURES					
Class - Type		Seeds	lb/acre (kg/hectare)		
3	Northern Illinois	Elymus Canadensis			
	Slope Mixture 7/	(Canada Wild Rye) 5/	5 (5)		
		Perennial Ryegrass	20 (20)		
		Alsike Clover 2/	5 (5)		
		Desmanthus Illinoensis	( )		
		(Illinois Bundleflower) 2/, 5/	2 (2)		
		Andropogon Scoparius			
		(Little Bluestem) 5/	12 (12)		
		Bouteloua Curtipendula	` '		
		(Side-Oats Grama) 5/	10 (10)		
		Fult Salt Grass 1/	30 (35)		
		Oats, Spring	50 (55)		
		Slender Wheat Grass 5/	15 (15)		
		Buffalo Grass (Cody or Bowie) 4/, 5/, 9/	5 (5)"		



## WARM MIX ASPHALT (BDE)

Effective: January 1, 2012 Revised: November 1, 2013

<u>Description</u>. This work shall consist of designing, producing and constructing Warm Mix Asphalt (WMA) in lieu of Hot Mix Asphalt (HMA) at the Contractor's option. Work shall be according to Sections 406, 407, 408, 1030, and 1102 of the Standard Specifications, except as modified herein. In addition, any references to HMA in the Standard Specifications, or the special provisions shall be construed to include WMA.

WMA is an asphalt mixture which can be produced at temperatures lower than allowed for HMA utilizing approved WMA technologies. WMA technologies are defined as the use of additives or processes which allow a reduction in the temperatures at which HMA mixes are produced and placed. WMA is produced by the use of additives, a water foaming process, or combination of both. Additives include minerals, chemicals or organics incorporated into the asphalt binder stream in a dedicated delivery system. The process of foaming injects water into the asphalt binder stream, just prior to incorporation of the asphalt binder with the aggregate.

Approved WMA technologies may also be used in HMA provided all the requirements specified herein, with the exception of temperature, are met. However, asphalt mixtures produced at temperatures in excess of 275 °F (135 °C) will not be considered WMA when determining the grade reduction of the virgin asphalt binder grade.

## Materials.

Add the following to Article 1030.02 of the Standard Specifications.

"(h) Warm Mix Asphalt (WMA) Technologies (Note 3)"

Add the following note to Article 1030.02 of the Standard Specifications.

"Note 3. Warm mix additives or foaming processes shall be selected from the current Bureau of Materials and Physical Research Approved List, "Warm-Mix Asphalt Technologies"."

## Equipment.

Revise the first paragraph of Article 1102.01 of the Standard Specifications to read:

"1102.01 Hot-Mix Asphalt Plant. The hot-mix asphalt (HMA) plant shall be the batch-type, continuous-type, or dryer drum plant. The plants shall be evaluated for prequalification rating and approval to produce HMA according to the current Bureau of Materials and Physical Research Policy Memorandum, "Approval of Hot-Mix Asphalt Plants and Equipment". Once approved, the Contractor shall notify the Bureau of Materials and Physical Research to obtain approval of all plant modifications. The plants shall not be used to produce mixtures concurrently for more than one project or for private work unless permission is granted in writing

by the Engineer. The plant units shall be so designed, coordinated and operated that they will function properly and produce HMA having uniform temperatures and compositions within the tolerances specified. The plant units shall meet the following requirements."

Add the following to Article 1102.01(a) of the Standard Specifications.

- "(13) Equipment for Warm Mix Technologies.
  - a. Foaming. Metering equipment for foamed asphalt shall have an accuracy of ± 2 percent of the actual water metered. The foaming control system shall be electronically interfaced with the asphalt binder meter.
  - b. Additives. Additives shall be introduced into the plant according to the supplier's recommendations and shall be approved by the Engineer. The system for introducing the WMA additive shall be interlocked with the aggregate feed or weigh system to maintain correct proportions for all rates of production and batch sizes."

## Mix Design Verification.

Add the following to Article 1030.04 of the Standard Specifications.

- "(e) Warm Mix Technologies.
  - (1) Foaming. WMA mix design verification will not be required when foaming technology is used alone (without WMA additives). However, the foaming technology shall only be used on HMA designs previously approved by the Department.
  - (2) Additives. WMA mix designs utilizing additives shall be submitted to the Engineer for mix design verification.

### Production.

Revise the second paragraph of Article 1030.06(a) of the Standard Specifications to read:

"At the start of mix production for HMA, WMA, and HMA using WMA technologies, QC/QA mixture start-up will be required for the following situations; at the beginning of production of a new mixture design, at the beginning of each production season, and at every plant utilized to produce mixtures, regardless of the mix."

## Quality Control/Quality Assurance Testing.

Revise the table in Article 1030.05(d)(2)a. of the Standard Specifications to read:

	Frequency of Tests	T Francisco F. T	
	riequency of resis	Frequency of Tests	Test Method See Manual of
Parameter	High ESAL Mixture Low ESAL Mixture	All Other Mixtures	Test Procedures for Materials
Aggregate Gradation	1 washed ignition oven test on the mix per half day of production	1 washed ignition oven test on the mix per day of production	Illinois Procedure
% passing sieves: 1/2 in. (12.5 mm), No. 4 (4.75 mm), No. 8 (2.36 mm), No. 30 (600 μm) No. 200 (75 μm)	Note 4.	Note 4.	
Note 1.			
Asphalt Binder Content by Ignition Oven Note 2.	1 per half day of production	1 per day	Illinois-Modified AASHTO T 308
VMA	Day's production	N/A	Illinois-Modified
Note 3.	≥ 1200 tons:		AASHTO R 35
Note 5.	1 per half day of production		
	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per day thereafter (first sample of the day)		
Air Voids	Day's production		
Bulk Specific Gravity of Gyratory Sample	≥ 1200 tons: 1 per half day of production	1 per day	Illinois-Modified AASHTO T 312
Note 5.	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per day thereafter (first sample of the day)		
Maximum Specific Gravity of Mixture	Day's production ≥ 1200 tons:	1 per day	Illinois-Modified AASHTO T 209
	1 per half day of production		
	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per		

	Frequency of Tests	Frequency of Tests	Toot Mathed
Parameter	High ESAL Mixture	All Other Mixtures	Test Method See Manual of Test Procedures
	Low ESAL Mixture	, other winteres	for Materials
Aggregate Gradation	1 washed ignition oven test on the mix per half day of production	1 washed ignition oven test on the mix per day of production	Illinois Procedure
% passing sieves: 1/2 in. (12.5 mm), No. 4 (4.75 mm), No. 8 (2.36 mm), No. 30 (600 μm) No. 200 (75 μm)	Note 4.	Note 4.	
Note 1.			
Asphalt Binder Content by Ignition Oven Note 2.	1 per half day of production	1 per day	Illinois-Modified AASHTO T 308
VMA	Day's production	N/A	Illinois-Modified
Note 3.	≥ 1200 tons:		AASHTO R 35
	1 per half day of production		
	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per day thereafter (first sample of the day)		
Air Voids	Day's production		
Bulk Specific Gravity of Gyratory Sample	≥ 1200 tons: 1 per half day of production	1 per day	Illinois-Modified AASHTO T 312
Note 5.	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per day thereafter (first sample of the day)		
Maximum Specific Gravity of Mixture	Day's production ≥ 1200 tons:	1 per day	Illinois-Modified AASHTO T 209
	1 per half day of production		
	Day's production < 1200 tons:		
	1 per half day of production for first 2 days and 1 per		

	Frequency of Tests	Frequency of Tests	Test Method See Manual of
Parameter	High ESAL Mixture Low ESAL Mixture	All Other Mixtures	Test Procedures for Materials
	day thereafter (first sample of the day)		

Note 1. The No. 8 (2.36 mm) and No. 30 (600  $\mu m)$  sieves are not required for All Other Mixtures.

Note 2. The Engineer may waive the ignition oven requirement for asphalt binder content if the aggregates to be used are known to have ignition asphalt binder content calibration factors which exceed 1.5 percent. If the ignition oven requirement is waived, other Department approved methods shall be used to determine the asphalt binder content.

Note 3. The  $G_{\text{sb}}$  used in the voids in the mineral aggregate (VMA) calculation shall be the same average  $G_{\text{sb}}$  value listed in the mix design.

Note 4. The Engineer reserves the right to require additional hot bin gradations for batch

Note 5. The WMA compaction temperature for mixture volumetric testing shall be 270  $\pm$  5 °F (132  $\pm$  3 °C) for quality control testing. The WMA compaction temperature for quality assurance testing will be 270  $\pm$  5 °F (132  $\pm$  3 °C) if the mixture is not allowed to cool to room temperature. If the mixture is allowed to cool to room temperature it shall be reheated to standard HMA compaction temperatures."

## Construction Requirements.

Revise the second paragraph of Article 406.06(b)(1) of the Standard Specifications to read:

"The HMA shall be delivered at a temperature of 250 to 350 °F (120 to 175 °C). WMA shall be delivered at a minimum temperature of 215 °F (102 °C)."

## Basis of Payment.

This work will be paid at the contract unit price bid for the HMA pay items involved. Anti-strip will not be paid for separately, but shall be considered as included in the cost of the work.

## WEEKLY DBE TRUCKING REPORTS (BDE)

Effective: June 2, 2012

The Contractor shall provide a weekly report of Disadvantaged Business Enterprise (DBE) trucks hired by the Contractor or subcontractors (i.e. not owned by the Contractor or subcontractors) that are used on the jobsite; or used for the delivery and/or removal of equipment/material to and from the jobsite. The jobsite shall also include offsite locations, such as plant sites or storage sites, when those locations are used solely for this contract.

The report shall be submitted on the form provided by the Department within ten business days following the reporting period. The reporting period shall be Monday through Sunday for each week reportable trucking activities occur. The report shall be submitted to the Engineer and a copy shall be provided to the district EEO Officer.

Any costs associated with providing weekly DBE trucking reports shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

## REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Compliance with Governmentwide Suspension and Debarment Requirements
- XI. Certification Regarding Use of Contract Funds for Lobbying

#### **ATTACHMENTS**

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

#### I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid design-build contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

- 2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

#### II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

- 1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.
- b. The contractor will accept as its operating policy the following statement:
  - "It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or onthe-job training."
- 2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

- **3. Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If

the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

#### 6. Training and Promotion:

- a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- **7. Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.
- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

#### 10. Assurance Required by 49 CFR 26.13(b):

- a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.
- b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
  - a. The records kept by the contractor shall document the following:
- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
  - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
  - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

## III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color,

religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

#### IV. Davis-Bacon and Related Act Provisions

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

#### 1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:

- (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
- (ii) The classification is utilized in the area by the construction industry; and
- (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

## 2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such

action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

#### 3. Payrolls and basic records

- a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.
- (1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose Wage and Hour Division Web http://www.dol.gov/esa/whd/forms/wh347instr.htm or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..
- (2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;
  - (ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;

- (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- (3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.
- (4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.
- c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

### 4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

- c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.
  - d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.
- **6. Subcontracts.** The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for

debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

- **8. Compliance with Davis-Bacon and Related Act requirements.** All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.
- **9. Disputes concerning labor standards.** Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

### 10. Certification of eligibility.

- a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

#### V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.
- 3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such

contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.

**4. Subcontracts.** The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

#### VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:
- (1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
- (2) the prime contractor remains responsible for the quality of the work of the leased employees:
- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
  - (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.
- 5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

#### **VII. SAFETY: ACCIDENT PREVENTION**

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

## VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

### 18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

# IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.
- 2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

# X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more — as defined in 2 CFR Parts 180 and 1200.

### 1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded,"

as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

\* \* \* \* \*

# 2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;
- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with

commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and

- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

#### 2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the

certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

\* \* \* \* \*

# Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\* \* \* \*

## XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

#### MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision shall be the minimum paid by contractors and subcontractors to laborers and mechanics.

#### NOTICE

The most current **General Wage Determination Decisions** (wage rates) are available on the IDOT web site. They are located on the Letting and Bidding page at <a href="http://www.dot.state.il.us/desenv/delett.html">http://www.dot.state.il.us/desenv/delett.html</a>.

In addition, ten (10) days prior to the letting, the applicable Federal wage rates will be e-mailed to subscribers. It is recommended that all contractors subscribe to the Federal Wage Rates List or the Contractor's Packet through IDOT's subscription service.

PLEASE NOTE: if you have already subscribed to the Contractor's Packet you will automatically receive the Federal Wage Rates.

The instructions for subscribing are at <a href="http://www.dot.state.il.us/desenv/subsc.html">http://www.dot.state.il.us/desenv/subsc.html</a>.

If you have any questions concerning the wage rates, please contact IDOT's Chief Contract Official at 217-782-7806.