

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	AS-BUILT QUANTITY
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR150520	MOBILIZATION	LS	1	
AR150540	HAUL ROUTE	LS	1	
AR152480	SHOULDER ADJUSTMENT	SY	10,200	
AR156520	INLET PROTECTION	EA	12	
AR201670	CRACK CONTROL FABRIC	SY	9,555	
AR401613	BIT. SURF. CSE.-METHOD I, SUPERPAVE	TON	865	
AR401650	BITUMINOUS PAVEMENT MILLING	SY	9,727	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	650	
AR403613	BIT. BASE CSE.-METHOD I, SUPERPAVE	TON	1,115	
AR603510	BITUMINOUS TACK COAT	GAL	3,900	
AR620520	PAVEMENT MARKING-WATERBORNE	SF	3,984	
AR620525	PAVEMENT MARKING-BLACK BORDER	SF	641	
AR901510	SEEDING	ACRE	2.0	
AR904510	SODDING	SY	1,550	
AR908510	MULCHING	ACRE	2.0	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	SCOPE OF WORK, GENERAL NOTES, TYPICAL SECTION
4	CONSTRUCTION SAFETY AND PHASING PLAN
5	PAVEMENT PREPARATION PLAN
6	TAXIWAY A PLAN & PROFILE STA. 123+60 TO STA 137+00
7	TAXIWAY A PLAN & PROFILE STA. 137+00 TO 150+53
8	MARKING PLAN
9	SWPPP & LANDSCAPING PLAN
10	TAXIWAY A CROSS SECTIONS STA. 123+60 TO 127+50
11	TAXIWAY A CROSS SECTIONS STA. 127+75 TO 128+50
12	TAXIWAY A CROSS SECTIONS STA. 129+00 TO 132+00
13	TAXIWAY A CROSS SECTIONS STA. 132+50 TO 134+00
14	TAXIWAY A CROSS SECTIONS STA. 134+50 TO 139+00
15	TAXIWAY A CROSS SECTIONS STA. 139+50 TO 144+00
16	TAXIWAY A CROSS SECTIONS STA. 144+50 TO 149+00
17	TAXIWAY A CROSS SECTIONS STA. 149+50 TO 150+53

REHABILITATE
TAXIWAY "A"

SUMMARY OF QUANTITIES
AND INDEX TO SHEETS

Hanson Project No. 12A0059
 Filename C-002-FLP.dwg
 Scale NOT TO SCALE
 Date 11/1/13

LAYOUT	KBS	04/30/13
DRAWN	KBS	4/30/13
REVIEWED	CAH	11/1/13

HANSON
 © Copyright Hanson Professional Services Inc. 2013
Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Ph: (217) 788-2450 Fax: (217) 788-2503
 www.hanson-inc.com
 Offices Nationwide

JOLIET REGIONAL AIRPORT
JOLIET PARK DISTRICT
JOLIET, ILLINOIS

IL PROJ.: J0T-4233 S.B.G. PROJ.: 3-17-SBGP-XX

REVISION

DATE