



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 9, 2020

SUBJECT: FAP Route 320 (IL 121)
Project NHPP-1ZHM (574)
Section (104,105)RS-4
Moultrie and Coles Counties
Contract No. 74260
Item No. 53, January 17, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices in iCX
2. Revised page i of the Table of Contents to the Special Provisions
3. Revised page 7 of the Special Provisions
4. Revised sheets 2-5,67 and 71 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	1
CHANGEABLE MESSAGE SIGNS	3
COOPERATION BETWEEN CONTRACTORS	3
HOT-MIX ASPHALT SHOULDERS, SPECIAL	4
INCIDENTAL HOT-MIX ASPHALT SURFACING	4
PAVEMENT PATCHING STANDARD 442201	6
PROTECTING OR RESETTING SURVEY MARKERS	6
REMOVAL OF EXISTING RAISED REFLECTIVE PAVEMENT MARKERS	7
REMOVE GRATING	7
STEEL PLATE BEAM GUARDRAIL, (SHORT RADIUS)	7
TRAFFIC BARRIER TERMINAL, TYPE 5A (SPECIAL)	7
SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	8
SURVEY MARKER VAULT	8
TEMPORARY RAMP, SPECIAL	9
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	9
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	10
COMPENSABLE DELAY COSTS (BDE)	12
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	15
DISPOSAL FEES (BDE)	24
EMULSIFIED ASPHALTS (BDE)	25
ENGINEER'S FIELD OFFICE AND LABORATORY (BDE)	28
EQUIPMENT PARKING AND STORAGE (BDE)	31
FUEL COST ADJUSTMENT (BDE)	31
GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE)	33
HOT-MIX ASPHALT – BINDER AND SURFACE COURSE (BDE)	36
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	42
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT DATA COLLECTION) (BDE)	46

Permanent Survey Markers. Permanent survey markers to be reset shall be in accordance with Section 667 of the Standard Specifications and as shown on Highway Standard 667101.

Basis of Payment The work for protecting or resetting survey markers shall be paid for at the contract unit price per each for PROTECTING OR RESETTING SURVEY MARKERS, which price shall include hiring an Illinois Professional Land Surveyor and providing the labor and equipment necessary to protect or reset survey markers and to adjust existing vaults.

The work for furnishing and installing new survey marker vaults will be paid for according to the survey marker vault special provision.

REMOVAL OF EXISTING RAISED REFLECTIVE PAVEMENT MARKERS

The removal of existing raised reflective pavement markers shall be included in the contract unit price per square yard (square meter) for HOT-MIX ASPHALT SURFACE REMOVAL of the thickness shown on the plans.

REMOVE GRATING

This work shall consist of removing drainage grates as directed by the Engineer. The existing grate shall be removed in its entirety, with the existing frame remaining intact and undisturbed. All materials shall be disposed of in accordance with Article 202.03 of the Standard Specifications.

This work shall be measured and paid for at the contract unit price per each for REMOVE GRATING, which price shall include all required materials, equipment, and labor as necessary to complete this work as specified.

STEEL PLATE BEAM GUARDRAIL, (SHORT RADIUS)

This work shall consist of constructing STEEL PLATE BEAM GUARDRAIL, at the locations and radii shown in the plans. This pay item will also be attached to the top of AR culverts in these locations. If possible, re-use the mounting hardware, if because of location of the new posts it will not be possible to re-use the mounting hardware, new mounting brackets shall be used. This work shall be paid for at the contract unit price per foot for STEEL PLATE BEAM GUARDRAIL, (SHORT RADIUS), which shall include all material, equipment and labor necessary to complete the work. This pay item shall also be constructed to the same specifications as Steel Plate Beam Guardrail, Type A, 6' Posts.

TRAFFIC BARRIER TERMINAL, TYPE 5A (SPECIAL)

This work shall consist of constructing Traffic Barrier Terminal, Type 5A (Special) at the locations shown in the plans according to Standard B.L.R. 27-1, Traffic Barrier Terminal Type 5A.

The work will be paid for at the contract unit price per each for TRAFFIC BARRIER TERMINAL, TYPE 5A (SPECIAL).