

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	TRAFFIC SIGNALS			EMERGENCY PRE-EMPTION 100% VILLAGE
				I000-2A	Y031-1F	Y031-3D	
20200100	EARTH EXCAVATION	CU YD	10	10			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	3	3			
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	761		761		
25200110	SODDING, SALT TOLERANT	SQ YD	761		761		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10			
40600300	AGGREGATE (PRIME COAT)	TON	46	46			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	323	323			
40600990	TEMPORARY RAMP	SQ YD	323	323			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	484	484			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1056	1056			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1005	1005			
42001300	PROTECTIVE COAT	SQ YD	345	167	178		
44000100	PAVEMENT REMOVAL	SQ YD	761		761		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12566	12566			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	10255	10255			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500			
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1438	1438			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	156	156			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	886	886			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	328	328			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	9	9			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	562	562			
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	190	190			
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5			

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	TRAFFIC SIGNALS			EMERGENCY PRE-EMPTION 100% VILLAGE
				I000-2A	Y031-1F	Y031-3D	
60404940	FRAMES AND GRATES, TYPE 23	EACH	7	7			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	912		912		
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	232	232			
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	120	120			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2160	2160			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	448	448			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8834	8834			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1540	1540			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	713	713			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	235	235			
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	448	448			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5285	5285			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5957	5957			
*72000100	SIGN PANEL - TYPE 1	SQ FT	36		36		
*72000200	SIGN PANEL - TYPE 2	SQ FT	30		30		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	448	448			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8834	8834			

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.P. 343/ F.A.U. RTE. 1273  
IL. 68 (DUNDEE RD.)  
EAST OF SKOKIE RD. TO FOREST WAY DR.  
PLOT DATE: 10/31/2007

10/31/2007