

SUMMARY OF QUANTITIES			100% STATE				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A	TRAFFIC SIGNALS Y031-1F	EMERGENCY PRE-EMPTION 100% VILLAGE Y031-3D				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1540	1540						
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	713	713						
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	235	235						
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	324	324						
*78200405	GUARDRAIL MARKERS	EACH	4	4						
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	292	292						
*81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	87		87					
*81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	64		64					
*81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	15		15					
*81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40		40					
*81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	66		66					
*81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	210		210					
*81400100	HANDHOLE	EACH	3		3					
*81400200	HEAVY-DUTY HANDHOLE	EACH	4		4					
*81400300	DOUBLE HANDHOLE	EACH	1		1					
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	362		362					
*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1					
*87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	560		560					
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1397		1397					
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1262		1262					
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	626		626					
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	904		904					

SUMMARY OF QUANTITIES			100% STATE				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A	TRAFFIC SIGNALS Y031-1F	EMERGENCY PRE-EMPTION 100% VILLAGE Y031-3D				
*87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	92		92					
*87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2					
*87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2		2					
*87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1					
*87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1					
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8					
*87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4					
*87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	47		47					
*88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6					
*88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2					
*88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2					
*88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2					
*88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2		2					
*88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	3		3					
*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8					
*88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8					
*88600100	DETECTOR LOOP, TYPE I	FOOT	949		949					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	144	144						
*88700200	LIGHT DETECTOR	EACH	2			2				
*88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1				
*88800100	PEDESTRIAN PUSH-BUTTON	EACH	5			5				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1				
89502380	REMOVE EXISTING HANDHOLE	EACH	5			5				

* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. 343/ F.A.U. RTE. 1273
IL. 68 (DUNDEE RD.)
EAST OF SKOKIE RD. TO FOREST WAY DR.
PLOT DATE: 10/31/2007

10/31/2007