

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	31 RS-5	DuPage	19	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	19	19				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2				
40600300	AGGREGATE (PRIME COAT)	TON	14	14				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	488	488				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	85	85				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	602	602				
42001300	PROTECTIVE COAT	SQ YD	37	37				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	143	143				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	6200	6200				
44000600	SIDEWALK REMOVAL	SQ FT	143	143				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	95	95				
44002232	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8"	SQ YD	185	185				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	50	50				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	80	80				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	10	10				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	35	35				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	77	77				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9	9				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	228	228				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	76	76				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4032	4032				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	342	342				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	76	76				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	76	76				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4032	4032				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	342	342				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	53	53				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	53	53				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	27	27				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	301	301				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

10/26/2007 10:26:00 AM C:\projects\60A\60A.dwg