CONTRACT NO. 60B80

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	104B-3-BR	WILL	42	4
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

- - -

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY I000 - 2A	BRIDGE X028-2A				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
70106705	TEMPORARY RUMBLE STRIP	FOOT	405	405					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2120	2120					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	410	410					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	410	410					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2200	2200					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	30					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	25	25					
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1					
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1					
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1600	1600					
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6	6					
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	6	6					
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1					
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6					
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	305	305					
* X8250090	COMBINATION POLE LIGHTING CONTROLLER	EACH	1	1					
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	3	3					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	980	980					
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 10/30/2007

10/30/2007
c:\projects\80135202\design.gp.dgn