

PROJECT: FAU RTE. 1312, EMERSON STREET OVER NORTH SHORE CHANNEL, COOK COUNTY

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
				80% FED 20% STATE		100% CITY OF EVANSTON		
				ROADWAY 1000-2A	BRIDGE X231-2A	TRAFFIC SIGNAL Y031-1F	LIGHTING Y030-1E	
* 88102710	PEDESTRIAN SIGNAL HEAD, L E D, 1-FACE, BRACKET MOUNTED	EACH	8			8		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2			2		
* A2004420	TREE, GINKGO BILOBA (GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2				
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3				
* A2005216	TREE, LARIX DECIDUA (EUROPEAN LARCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2				
* B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	2	2				
* C2006036	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 3' HEIGHT, BALLED AND BURLAPPED	EACH	120	120				
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103				
* X0322324	WEED CONTROL TEASEL	POUND	0.02	0.02				
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	960	960				
* X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	20	20				
X0323817	SEDIMENT CONTROL, SILT CURTAIN	EACH	4	4				
* X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1545	1545				
* X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1545	1545				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1002		1002			
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	600	600				
* X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	2		2			
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	117		117			
* 88030210	SIGNAL HEAD, L E D, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1			
* 88030240	SIGNAL HEAD, L E D, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	5		5			

\* SPECIALTY ITEMS                      \*\*\* Y080  
 \*\* NON PARTICIPATING ITEMS              ▲ 100% PARTICIPATION - VILLAGE OF SKOKIE

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE				
				80% FED 20% STATE		100% CITY OF EVANSTON		
				ROADWAY 1000-2A	BRIDGE X231-2A	TRAFFIC SIGNAL Y031-1F	LIGHTING Y030-1E	
* 88030320	SIGNAL HEAD, L E D, 3-FACE, 1-3 SECTION, 2-5 SECTION BRACKET MOUNTED	EACH	1			1		
* 88102740	PEDESTRIAN SIGNAL HEAD, L E D, 2-FACE, BRACKET MOUNTED	EACH	4			4		
XX003140	SHORT-TERM PAVEMENT MARKING REMOVAL	FOOT	502	502				
XX805656	INLET FILTER CLEANING	EACH	5	5				
X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2			2		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2568	2568				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
** Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5				
Z0064800	SELECTIVE CLEARING	UNIT	1	1				
*** Z0076600	TRAINEES	HOUR	1500	1500				
* X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2			2		
* X0325881	LUMINAIRE, MERCURY VAPOR, 400 WATT	EACH	8			8		
* X0325882	LIGHT POLE, ALUMINUM, 30FTM.H., 6FD AVIT ARM, BRIDGE MOUNTED	EACH	3			3		
* A2006516	TREE, <sup>QUERCUS BICOLOR</sup> (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.U. ROUTE 1312 (EMERSON STREET)

EMERSON STREET  
 SUMMARY OF QUANTITIES

SCALE: NONE                      DRAWN BY JSS  
 DATE: OCT. 17, 2007                      CHECKED BY JP

W:\Emerson Street\Proposed Plans\03-06\_Quant.txdgn  
 10/17/2007 3:01:27 PM