

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	ROADWAY 1000-2A	X181-2A BRIDGE				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	150	150					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	325	325					
42000500	PORTLAND CEMENT CONCRETE PAVEMENT, 10"	SQ YD	150	150					
42001300	PROTECTIVE COAT	SQ YD	1733	1733					
42001200	PAVEMENT FABRIC	SQ YD	150	150					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR	SQ YD	93	93					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	270	270					
44000700	APPROACH SLAB REMOVAL	SQ YD	475	475					
44000500	COMBINATION CONCRETE CURB & GUTTER REMOVAL	FOOT	360	360					
44003100	MEDIAN REMOVAL	SQ FT	7937	7937					
44000600	SIDEWALK REMOVAL	SQ FT	270	270					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1				
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	270	270					
50104650	SLOPE WALL REMOVAL	SQ YD	185		185				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	182.6		182.6				
50300260	BRIDGE DECK GROOVING	SQ YD	940		940				
50300300	PROTECTIVE COAT	SQ YD	1582		1582				
X5030205	CONCRETE WEARING SURFACE, 5"	SQ YD	1020		1020				
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	13185		13185				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	9000		9000				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36590		36590				
50800515	BAR SPLICERS	EACH	162		162				
50900105	ALUMINUM RAILING, TYPE L	FOOT	326		326				
51100100	SLOPE WALL 4 INCH	SQ YD	185		185				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	605		605				
60605000	COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24	FOOT	180	180					
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1235		1235				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4457		4457				
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	1973		1973				
60624600	CORRUGATED MEDIAN	SQ FT	74	74					
60253000	CATCH BASIN TO BE RECONSTRUCTED WITH NEW TYPE I FRAME, OPEN LID	EACH	1	1					
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2		2				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2		2				
63200310	GUARDRAIL REMOVAL	FOOT	100		100				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6				
67100100	MOBILIZATION	L SUM	1		1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		10				

* SPECIALITY ITEM

NP= NON-PARTICIPATING

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	ROADWAY 1000-2A	X181-2A BRIDGE				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40	40					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3020	3020					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	110	110					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	230	230					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7200	7200					
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	750	750					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	20	20					
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	750	750					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	660	660					
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	40	40					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2360	2360					
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	110	110					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35					
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1355	1355					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10					
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	625	625					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
* 87900200	DRILL EXISTING HANDHOLE	EACH	1	1					
X0321743	SILICONE JOINT SEALER, 1"	FOOT	86		86				
X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SQ FT	14900		14900				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	258		258				
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	882	882					
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	20		20				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	397.5		397.5				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A. 374: MILWAUKEE AVE (IL 21)
 SUMMARY OF QUANTITIES

Rev. 1-7-07
 Rev. 9-5-07

Rev.

PLOT DATE: 7/23/2007

7/23/2007 11:52:29 AM