

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2007-056 SG	COOK	30	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

100% STATE

CODE #	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				SIGNING	Y002-1C
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	203	203	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
25100630	EROSION CONTROL BLANKET	SQ YD	203	203	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	215	215	
44004250	PAVED SHOULDER REMOVAL	SQ YD	146	146	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	51	51	
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	60	60	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1	
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	50	50	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2668	2668	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	889	889	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5	412.5	
70400210	RELOCATE TEMPORARY CONCRETE BARRIER, SPECIAL	FOOT	20	20	
72000300	SIGN PANEL - TYPE 3	SQ FT	1006.5	1006.5	
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	100	100	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	49.1	49.1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	545	545	
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	250	250	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	38	38	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
* 78200500	BARRIER WALL MARKERS	EACH	104	104	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	764	764	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	38	38	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
X0325349	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	FOOT	237.5	237.5	
X6060003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.18	FOOT	20	20	
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	195	195	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	94.3	94.3	
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	1	1	
X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	12	12	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	144	144	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

PLAN

DATE

BY

SURVEYED

ALIGNMENT CHECKED

NOTATION CHECKED

PAID FILE NAME

NOTE BOOK NO.

PROFILE

DATE

BY

SURVEYED

GRADES CHECKED

STRUCTURE NOTATIONS CHECKED

NOTE BOOK NO.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

I-90/94 (KENNEDY EXPRESSWAY)

SCALE: VERT. 1:20
 HORIZ. 1:20
 DATE 10/31/07

DRAWN BY: DLZ
 CHECKED BY: GB

* SPECIALTY ITEMS

