

CONTRACT NO.: 60D50

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		LOCATION 1 OVER PRAIRIE CREEK SN# 099-0119	LOCATION 2 OVER N. BRANCH PRAIRIE CREEK SN# 099-0118				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1		1				
40600300	AGGREGATE (PRIME COAT)	TON	1		1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1		1				
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	33	11	22				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	60	17	43				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	570	285	285				
42001300	PROTECTIVE COAT	SQ YD	421	191	230				
44000100	PAVEMENT REMOVAL	SQ YD	108	54	54				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	506		506				
44000700	APPROACH SLAB REMOVAL	SQ YD	362	174	188				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	416		416				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1	1				
50102400	CONCRETE REMOVAL	CU YD	0.9	0.9					
50300225	CONCRETE STRUCTURES	CU YD	3.6	3.6					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.9	8.3	13.6				
50300260	BRIDGE DECK GROOVING	SQ YD	336	153	183				
50301200	CONCRETE WEARING SURFACE	SQ YD	383	174	209				
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1568	1568					
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	1883		1883				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8710	3640	5070				
50800515	BAR SPLICERS	EACH	93	38	55				
51500100	NAME PLATES	EACH	2	1	1				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	910	455	455				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4				
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	4	4				
63200310	GUARDRAIL REMOVAL	FOOT	910	455	455				
67100100	MOBILIZATION	L SUM	1	0.5	0.5				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		LOCATION 1 OVER PRAIRIE CREEK SN# 099-0119	LOCATION 2 OVER N. BRANCH PRAIRIE CREEK SN# 099-0118				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1				
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	2	1	1				
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	4	2	2				
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6	6				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	140	160				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	300	140	160				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	376	124	252				
*78008210	POLYUREA PAVEMENT MARKING - LINE 4" ^{TYPE I}	FOOT	102	47	55				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	6	10				
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	2	3				
*78200405	GUARDRAIL MARKERS	EACH	12	6	6				
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4	4				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	5	9				
*80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	1	1				
*80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0.5	0.5				
*81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	3200	1600	1600				
*82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	12	6	6				
*83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	12	6	6				
*84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	12	6	6				
*84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2	1	1				
*84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	1	1				
X0301245	SHOULDER REMOVAL	SQ YD	40	20	20				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	51.4	51.4				
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12	6	6				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	486	173	313				

* SPECIALITY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 330/ US 45 (LA GRANGE RD.)
OVER N. BRANCH PRAIRIE CREEK &
PRAIRIE CREEK