

CONTRACT NO. 62336


F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
533	119R-2-B	McHENRY	64	4
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO.				

SUMMARY OF QUANTITIES

PAY ITEM	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X071-2A	RETAINING WALLS QUANTITY Y007-2A
50300300	PROTECTIVE COAT	SQ YD	778		409	369
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	1,890		1,890	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	111,370		41,040	70,330
50800515	BAR SPLICERS	EACH	402		402	
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1,908		1,908	
51202305	DRIVING PILES	FOOT	1,908		1,908	
51203200	TEST PILE METAL SHELLS	EACH	2		2	
51205200	TEMPORARY SHEET PILING	SQ FT	1,244		1,244	
51500100	NAME PLATES	EACH	1		1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	84		84	
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6		6	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24		24	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	26	26		
58700300	CONCRETE SEALER	SQ FT	927		927	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	155		77	78
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4		
60107600	PIPE UNDERDRAINS 4"	FOOT	121	121		
60109580	PIPE UNDERDRAIN FOR STRUCTURES 4"	FOOT	123		123	
60600605	CONCRETE CURB, TYPE B	FOOT	120	120		
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	4	4		
61000120	TYPE E INLET BOX, STANDARD 610001 (SPECIAL)	EACH	1	1		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	460	460		
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	84	84		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4,020	4,020		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3,775	3,775		
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	44	44		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,660	2,660		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,100	1,100		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,080	1,080		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,953	1,953		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	308	308		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11	11		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4		
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	13	13		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III 4 INCH	FOOT	3,775	3,775		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3,114	3,114		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

20076400 TRAINERS HOUR 500 500

* SPECIALTY ITEMS @ 1080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 176 OVER THE KISHWAUKEE RIVER SUMMARY OF QUANTITIES SCALE: DATE: 10-05-07 DRAWN BY: WS CHECKED BY: RJS
NAME	DATE	
 GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS		