

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2003-106LS	COOK	59	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62699				

SEEDING CL 4 (M2500310)

STATION - STATION AREA (SQ M) HECTARE

LSM-16A				
GATEWAY DETAIL			0.01	
TOTAL =			0.1	

MOWING (M2500750)

STATION WIDTH(m) - STATION WIDTH(m) HECTARE

NOMINAL QUANTITY	21.0
TOTAL = 21.0	

INTERSEEDING CL 4 (M2503310)

STATION - STATION AREA (SQ M) HECTARE

NOMINAL QUANTITY	0.20
TOTAL = 0.2	

EROSION CONTR BLANKET (M2510630)

STATION WIDTH(m) - STATION WIDTH(m) SQ METER

NOMINAL QUANTITY	5,000.0
LSM-16A	70.0
TOTAL = 5,070	

MULCH PLACEMENT 100 (MX032651)

STATION OFFSET - STATION OFFSET SQ METER

LSNS-29				
I-94				
30+567	- 30+245		290.0	
LSNS-34				
19+816.000 RT	- 19+760.000 RT		175.0	
LS170-40	RT			
MULCH BEDS AND MULCH RINGS			150.0	
LSM-13				
MULCH RINGS AT TREES 8SQM X 4EA			32.0	
6+450.000 LT				
TOTAL =			647	

PERENNIAL PLANT CARE (MX032675)

STATION OFFSET - STATION OFFSET SQ METER

NOMINAL QUANTITY	480 X 3CYCLES=	1,440.0
TOTAL =		1440

WEED CONTR PRE-EM GRN (MX032680)

KG

RATE	112 KG / HA	
	2442.0 SQ M	2.44HA
TOTAL =		274
		274

WEED CONT N SEL/N RES (MX033189)

STATION OFFSET - STATION SQ M LITER

RATE = 0.022467 LITER / m²				
LSM-9				
50+075.000	-	50+090.000	40.00	0.90
LSM-16				
7+600.000	-	7+950.000	160.00	3.59
LS83-19				
50+105.000	-	50+120.000	40.00	0.90
LSNS-29				
30+567	-	30+245.000	290.00	6.52
LSNS-33				
19+600.000	-	19+625.000	20.00	0.45
19+675.000	-	19+700.000	20.00	0.45
19+760.000	-	19+785.000	20.00	0.45
19+840.000	-	19+865.000	20.00	0.45
LSNS-35				
19+250.000	-	19+275.000	20.00	0.45
19+340.000	-	19+365.000	20.00	0.45
19+425.000	-	19+450.000	20.00	0.45
19+515.000	-	19+540.000	20.00	0.45
LSNS-36				
18+960.000	-	18+985.000	20.00	0.45
19+060.000	-	19+085.000	20.00	0.45
19+170.000	-	19+195.000	20.00	0.45
LSNS-37				
18+650.000	-	18+675.000	20.00	0.45
18+750.000	-	18+775.000	20.00	0.45
18+860.000	-	18+885.000	20.00	0.45
LSNS-38				
0+000.000	-	0+025.000	20.00	0.45
LS170-39				
350+025.000	-	350+050.000	45.00	1.01
89+825.000	-	89+850.000	12.00	0.27
TOTAL =			20	

COARSE SAND PLACE 100 (MX033323)

STATION OFFSET - STATION OFFSET SQ METER

LSM-9				
50+075.000	-	50+090.000	0.000	40.0
LS83-19				
50+105.000	-	50+120.000	0.000	40.0
LSNS-33				
19+600.000	-	19+625.000	20.00	
19+675.000	-	19+700.000	20.00	
19+760.000	-	19+785.000	20.00	
19+840.000	-	19+865.000	20.00	
LSNS-35				
19+250.000	-	19+275.000	20.00	
19+340.000	-	19+365.000	20.00	
19+425.000	-	19+450.000	20.00	
19+515.000	-	19+540.000	20.00	
LSNS-36				
18+960.000	-	18+985.000	20.00	
19+060.000	-	19+085.000	20.00	
19+170.000	-	19+195.000	20.00	
LSNS-37				
18+650.000	-	18+675.000	20.00	
18+750.000	-	18+775.000	20.00	
18+860.000	-	18+885.000	20.00	
LSNS-38				
0+000.000	-	0+025.000	20.00	
LS170-39				
350+025.000	-	350+050.000	45.00	
89+825.000	-	89+850.000	12.00	
TOTAL =			437.0	

PERENNIAL PLT-GAL POT (X0301407)

SHEET OFFSET UNIT

LSM-16A	RT	2.0
LSNS-35	RT	5.0
LSNS-36	RT	5.0
LSNS-37	RT	2.0
LSNS-38	RT	5.0
LS170-39	RT	0.5
LS170-39	LT	2.0
TOTAL =		21.5

CONSTRUCTION LAYOUT (Z0013798)

L SUM

NOMINAL QUANTITY	1.0
TOTAL =	

08/22/2007 8:53:33 AM g:\Project\20140901\CADD\ContractLaWB\sch001.rdb

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
LANDSCAPING PLAN
SCHEDULE OF QUANTITIES

SCALE 1:500 DRAWN BY ACE/CAD
DATE 06/07 CHECKED BY TJW

AMERICAN
CONSULTING ENGINEERS