

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
108	116T-1	STEPHENSON	78	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE #	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				80% FEDERAL 20% STATE ROADWAY 1000-1A	80% FEDERAL 20% STATE BOX CULVERT Y007 S. N. 089-1108	80% FEDERAL 20% STATE BOX CULVERT X028-2A S. N. 089-1109
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	60	60		
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	62	62		
5421D048	PIPE CULVERTS, CLASS D, TYPE 1 48" (TEMPORARY)	FOOT	24		24	
54213450	END SECTIONS 15"	EACH	2	2		
54213453	END SECTIONS 18"	EACH	2	2		
54213471	END SECTIONS 36"	EACH	2	2		
54213495	END SECTIONS 60"	EACH	1		1	
54248510	CONCRETE COLLAR	CU YD	0.6		0.6	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	50	50		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	187.5	187.5		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100	100		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) FLARED	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	319	319		
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	75	75		
63500105	DELINEATORS	EACH	12	12		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	29	29		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	2		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	2		
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12	12		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4446	4446		
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	60	60		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1603	1603		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	662.5	662.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	462.5	462.5		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	18278	18278		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	36	36		
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4		
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	1676	1676		



REVISSED 1/4/08

* - INDICATES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 IL RTE 73 CULVERT REPLACEMENTS

SCALE: VERT.: N.A.
 HORIZ.: 1:20
 DATE: OCTOBER 1, 2007

DRAWN BY: DLZ
 CHECKED BY: GB

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#