

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
108	116T-1	STEPHENSON	78	8
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

48101500 AGGREGATE SHOULDERS, TYPE B 6"

SQ_YD	LOCATION
21	STA. 1042+58.9 TO STA. 1043+33.9 LT
354	STA. 1043+90.1 TO STA. 1052+50 LT
169	STA. 1048+69.9 TO STA. 1052+50 LT
544	TOTAL

48203021 HOT-MIX ASPHALT SHOULDERS, 6"

SQ_YD	LOCATION
898	STA. 962+05 TO STA. 969+88 RT
476	STA. 964+45 TO STA. 968+91 LT
46	STA. 1038+85 TO STA. 1040+42 RT
569	STA. 1041+48 TO STA. 1048+70 RT
1989	TOTAL

50105200 REMOVE EXISTING CULVERTS

EACH	LOCATION
1	STA. 1043+61.4 LT
1	STA. 964+25.7 RT
2	TOTAL

54002020 EXPANSION BOLTS 3/4 INCH

EACH	LOCATION
12	STA. 1044+62 LT
12	TOTAL

542A1105 PIPE CULVERTS, CLASS A, TYPE 2 60"

FOOT	LOCATION
78	STA. 1044+62 (CULVERT)
78	TOTAL

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION
50	STA. 1046+65.9 RT
50	TOTAL

542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"

FOOT	LOCATION
60	STA. 1043+61.4 LT
60	TOTAL

542D0241 PIPE CULVERTS, CLASS D, TYPE 1 36"

FOOT	LOCATION
62	STA. 964+25.7 RT
62	TOTAL

5421D048 PIPE CULVERTS, CLASS D, TYPE 1 48" (TEMPORARY)

FOOT	LOCATION
24	STA. 1044+62 LT
24	TOTAL

54213450 END SECTIONS 15"

EACH	LOCATION
2	STA. 1046+65.9 RT
2	TOTAL

54213453 END SECTIONS 18"

EACH	LOCATION
2	STA. 1043+61.4 LT
2	TOTAL

54213471 END SECTIONS 36"

EACH	LOCATION
2	STA. 964+25.7 RT
2	TOTAL

54213495 END SECTIONS 60"

EACH	LOCATION
1	STA. 1044+62 RT (CULVERT)
1	TOTAL

54248510 CONCRETE COLLAR

CU_YD	LOCATION
0.6	STA. 1044+62 LT
0.6	TOTAL

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A

FOOT	LOCATION
187.5	STA. 965+30.3 TO STA. 968+65.9 RT
187.5	TOTAL

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

EACH	LOCATION
1	STA. 965+27.0 LT
1	STA. 967+52.8 LT
1	STA. 965+30.3 RT
1	STA. 968+65.9 RT
4	TOTAL

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION
128	STA. 965+44.9 TO STA. 967+48.8 LT
191	STA. 965+70.9 TO STA. 967+61.6 RT
319	TOTAL

63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A

FOOT	LOCATION
75	STA. 965+44.9 TO STA. 967+48.8 LT
75	TOTAL

63500105 DELINEATORS

EACH	LOCATION
4	STA. 966+60 LT & RT (CULVERT)
4	STA. 1044+62 LT & RT (CULVERT)
1	STA. 965+27.0 LT
1	STA. 967+52.8 LT
1	STA. 965+30.3 RT
1	STA. 968+65.9 RT
12	TOTAL

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION
1	STA. 963+50 RT
1	STA. 964+00 RT
1	STA. 965+50 RT
1	STA. 966+50 RT
1	STA. 968+00 RT
1	STA. 969+00 RT
1	STA. 970+00 RT
1	STA. 964+53.71 LT
1	STA. 966+50 LT
1	STA. 967+00 LT
1	STA. 968+50 LT
1	STA. 969+00 LT
1	STA. 1040+50 RT
1	STA. 1040+85 RT
1	STA. 1043+00 RT
1	STA. 1043+20 RT
1	STA. 1043+80 RT
1	STA. 1044+65 RT
1	STA. 1046+50 RT
1	STA. 1048+00 RT
1	STA. 1049+00 RT
1	STA. 1052+00 RT
1	STA. 1052+75 RT
1	STA. 1043+00 LT
1	STA. 1043+35 LT
1	STA. 1046+00 LT
1	STA. 1047+50 LT
1	STA. 1051+50 LT
1	STA. 1052+75 LT
29	TOTAL

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
1	STA. 966+60 (CULVERT)
1	STA. 1044+62 (CULVERT)
2	TOTAL

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

EACH	LOCATION
1	STA. 966+60 (CULVERT)
1	STA. 1044+62 (CULVERT)
2	TOTAL

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION
1	STA. 945+15.4 RT
1	STA. 950+15.4 RT
1	STA. 955+15.4 RT
1	STA. 977+99.8 LT
1	STA. 982+99.8 LT
1	STA. 987+99.8 LT
1	STA. 1032+90.0 RT
1	STA. 1027+90.0 RT
1	STA. 1022+90.0 RT
1	STA. 1055+66.9 LT
1	STA. 1060+66.9 LT
1	STA. 1065+66.9 LT
12	TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION
8	STA. 966+05.0 TO STA. 967+05.0
4	STA. 1044+42.0 TO STA. 1044+83.0
12	TOTAL

REVISIED 1/4/08

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULE OF QUANTITIES</p> <p>IL RTE 73 CULVERT REPLACEMENTS</p> <p>SCALE: VERT.: N.A. HORIZ.: 1:20</p> <p>DATE: OCTOBER 1, 2007</p> <p>DRAWN BY: DLZ CHECKED BY: GB</p>

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 USER NAME = #USER#