

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1087	116T-1	STEPHENSON	78	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE #	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				80% FEDERAL 20% STATE ROADWAY 1000-1A	80% FEDERAL 20% STATE BOX CULVERT Y007 S. N. 089-1108	80% FEDERAL 20% STATE BOX CULVERT X028-2A S. N. 089-1109
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	421	421		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	310	310		
20200100	EARTH EXCAVATION	CU YD	3793	3793		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	160			160
20400100	BORROW EXCAVATION	CU YD	1921	1921		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	310			310
25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50		
25000310	SEEDING, CLASS 4	ACRE	0.75	0.75		
25000750	MOWING	ACRE	1.50	1.50		
25100115	MULCH, METHOD 2	ACRE	2.00	2.00		
25100630	EROSION CONTROL BLANKET	SQ YD	1128	1128		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	582	582		
28000300	TEMPORARY DITCH CHECKS	EACH	42	42		
28000400	PERIMETER EROSION BARRIER	FOOT	623	623		
28000500	INLET AND PIPE PROTECTION	EACH	5	5		
28100107	STONE RIPRAP, CLASS A4	SQ YD	167		57	110
28200200	FILTER FABRIC	SQ YD	167		57	110
35100100	AGGREGATE BASE COURSE, TYPE A	TON	18	18		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	453	453		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	286	286		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	68	68		
44200926	CLASS B PATCHES, TYPE IV, 7 INCH	SQ YD	264	264		
44213100	PAVEMENT FABRIC	SQ YD	373	373		
44213200	SAW CUTS	FOOT	300	300		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	544	544		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1989	1989		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1	
50105200	REMOVE EXISTING CULVERTS	EACH	2	2		
50800105	REINFORCEMENT BARS	POUND	77487			77487
50800515	BAR SPLICERS	EACH	153			153
X0323983	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1780		960	820
51500100	NAME PLATES	EACH	2		1	1
54002020	EXPANSION BOLTS 3/4 INCH	EACH	12		12	
54003000	CONCRETE BOX CULVERTS	CU YD	189.2			189.2
542A1105	PIPE CULVERTS, CLASS A, TYPE 2 60"	FOOT	78		78	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	50	50		

■ 100% STATE N/P

* - INDICATES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 IL RTE 73 CULVERT REPLACEMENTS

SCALE: VERT.: N.A.
 HORIZ.: 1:20
 DATE: OCTOBER 1, 2007

DRAWN BY: DLZ
 CHECKED BY: GB

PLT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#