CODE NUMBER	ITEM	UNIT	X081-2A 100% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	149
20400800	FURNISHED EXCAVATION	CU YD	505
25100630	EROSION CONTROL BLANKET	SQ YD	2,214
28000400	PERIMETER EROSION BARRIER	FOOT	1,233
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	113
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	31
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	211
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	559
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1,175
50102400	CONCRETE REMOVAL	CU YD	5
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1119
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2000
50901050	STEEL RAILING, TYPE SM	FOOT	210
51500100	NAME PLATES	EACH	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	637.5
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	1533
63500105	DELINEATORS	EACH	4
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMPLE STRIP	EACH	6
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,961
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	749
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4500
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	751
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1129
X0321781	MECHANICAL SPLICE	EACH	256
X0712400	TEMPORARY PAVEMENT	SQ YD	166
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	160
XZ191600	SILICONE BRIDGE JOINT SEALANT	FOOT	33
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	6
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

*SPECIALTY ITEMS