

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	11T	CARROLL	79	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2
70106700	TEMPORARY RUMBLE STRIP	EACH	18
70300520	PAVEMENT MARKING TAPE TYPE III, 4"	FOOT	8424
70300570	PAVEMENT MARKING TAPE TYPE III, 24"	FOOT	66
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2941
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1038
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1013
* 78001110	PAINT PAVEMENT MARKING LINE 4"	FOOT	6133
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300105	PAVEMENT MARKING REMOVAL	FOOT	5890
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8
* A2002914	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	32
X0323988	TEMPORARY SOIL RETENSION SYSTEM	SQ FT	2037
X4810100	TEMPORARY SHOULDERS	SQ YD	48
XX002909	CLASS SI CONCRETE	CU YD	168.9
Z0005400	BREAKER-RUN CRUSHED STONE	TON	1163
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NONREDIRECTIVE), TEST LEVEL 3	EACH	6
Z0030350	IMPACT ATTENUATORS, RELOCATE (NONREDIRECTIVE), TEST LEVEL 3	EACH	4
* Z5100900	TURF REINFORCEMENT MAT	SQ YD	219

* Specialty Item

PLOT DATE = Fri, Oct 12, 12:40:56, 2007
 FILE NAME = c:\pwork\64882\22866688\64882688.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = cshamby