

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	11T	CARROLL	79	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

44201796	CLASS D PATCHES, TYPE IV, 12 INCH LOCATION STA 800+91.65 TO 802+01.24 STA 805+13.91 TO 806+33.96 STA 813+13.00 TO 814+00.00 STA 826+40.82 TO 826+92.66 STA 842+76.81 TO 843+32.38	SQ YD 317 347 251 150 161 TOTAL 1226	54213450	END SECTIONS 15' LOCATION STA 842+06 RT STA 842+52 RT	EACH 1 1 TOTAL 2
44213200	SAW CUTS LOCATION STA 803+63.03 TO 807+11.26 LT STA 810+90.60 TO 815+40.04 LT	EQOI 348.2 449.4 TOTAL 797.7	54213453	END SECTIONS 18' LOCATION STA 812+63 42' RT	EACH 1 TOTAL 1
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1 LOCATION STA 801+47	EACH 1 TOTAL 1	54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36" LOCATION STA 826+67 LT STA 843+08 LT	EACH 2 2 TOTAL 4
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2 LOCATION STA 805+74	EACH 1 TOTAL 1	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A LOCATION STA 801+10.00 TO 802+05.00 LT STA 799+25.00 TO 801+50.00 RT	EQOI 175 225 TOTAL 400
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3 LOCATION STA 813+61	EACH 1 TOTAL 1	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) LOCATION STA 798+75.00 TO 799+25.00 RT STA 800+60.00 TO 801+10.00 LT STA 801+50.00 TO 802+00.00 RT STA 802+85.00 TO 803+35.00 LT	EACH 1 1 1 1 TOTAL 4
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4 LOCATION STA 826+67	EACH 1 TOTAL 1	63200310	GUARDRAIL REMOVAL LOCATION STA 800+31 TO 801+95 RT STA 800+97 TO 802+63 LT STA 804+34 TO 805+88 RT STA 805+37 TO 806+88 LT STA 812+91 TO 814+07 LT STA 813+26 TO 814+27 RT	EQOI 164 166 154 151 116 101 TOTAL 852
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5 LOCATION STA 843+08	EACH 1 TOTAL 1	63500105	DELINEATORS LOCATION STA 798+75 RT STA 800+60 LT STA 801+47 RT CULVERT STA 801+47 LT CULVERT STA 802+00 RT STA 803+35 LT STA 805+00 RT CULVERT STA 805+00 LT CULVERT STA 813+60 RT CULVERT STA 813+60 LT CULVERT STA 826+71 RT CULVERT STA 826+71 LT CULVERT STA 843+08 RT CULVERT STA 843+08 LT CULVERT	EACH 1 1 1 1 1 1 1 1 1 1 1 1 1 1 TOTAL 14
50104600	CONCRETE RETAINING WALL REMOVAL LOCATION STA 806+09 42' LT	EQOI 41 TOTAL 41	66411900	TEMPORARY FENCE LOCATION STA 800+00 TO 802+46 LT STA 842+00 TO 843+51 LT	EQOI 137 162 TOTAL 299
51205200	TEMPORARY SHEET PILING LOCATION STA 813+13.00 TO 814+00.00	SQ FT 4537 TOTAL 4537	66502300	WOVEN WIRE FENCE REMOVAL LOCATION STA 798+37.73 TO 801+95.83 RT STA 800+00 TO 802+50 LT STA 802+26.91 TO 802+81.48 RT STA 802+50 TO 805+00 LT STA 804+00 TO 806+44.53 RT STA 805+00 TO 807+24.69 LT STA 812+00 TO 813+45.14 LT STA 813+24.75 TO 815+50 RT STA 813+45.14 LT STA 813+83.09 LT STA 813+97.17 TO 815+00 LT STA 825+50 TO 828+00 LT STA 825+50 TO 827+50 RT STA 841+50 TO 844+50 RT STA 842+00 TO 844+50 LT STA 843+45 LT	EQOI 358 250 55 250 245 225 142 309 74 78 103 250 200 300 250 51 TOTAL 3140
51500100	NAME PLATES LOCATION STA 801+47 STA 805+74 STA 813+61 STA 826+67 STA 843+08	EACH 1 1 1 1 1 TOTAL 5			
54010707	PRECAST CONCRETE BOX CULVERT 7' X 7' LOCATION STA 813+61	EQOI 176 TOTAL 176			
54010800	PRECAST CONCRETE BOX CULVERT 8' X 8' LOCATION STA 801+47	EQOI 88 TOTAL 88			
54011000	PRECAST CONCRETE BOX CULVERT 10' X 8' LOCATION STA 805+74	EQOI 98 TOTAL 98			
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" LOCATION STA 826+67 STA 843+08	EQOI 122 136 TOTAL 258			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15' LOCATION STA 842+29.43 18' RT	EQOI 46 TOTAL 46			
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18' LOCATION STA 812+63 TO 813+45 RT	EQOI 82 TOTAL 82			

PLOT DATE = Mon, Oct 23, 10:52:00 AM 2006  
FILE NAME = c:\pwworkspace\64d82\64d82.dgn  
PLOT SCALE = 5/8"=1'-0" / IN.  
USER NAME = parkinsd