

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	11T	CARROLL	79	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY-MARKERS

LOCATION	EACH
STA 798+50 33' RT	1
STA 800+00 33' LT	1
STA 801+15 85' RT	1
STA 801+85 75' LT	1
STA 802+52.07 33' LT	1
STA 802+75 33' RT	1
STA 804+00 33' RT	1
STA 804+50 45' RT	1
STA 805+00 33' LT	1
STA 805+50 90' RT	1
STA 805+50 45' LT	1
STA 806+00 85' LT	1
STA 806+40 33' RT	1
STA 806+50 85' LT	1
STA 807+00 45' LT	1
STA 807+50 33' LT	1
STA 812+00 33' RT	1
STA 812+00 33' LT	1
STA 813+00 90' RT	1
STA 813+25 90' LT	1
STA 814+00 90' RT	1
STA 814+15 90' LT	1
STA 815+00 33' LT	1
STA 815+50 33' RT	1
STA 825+50 33' RT	1
STA 825+50 33' LT	1
STA 826+50 65' RT	1
STA 826+50 65' LT	1
STA 827+00 65' RT	1
STA 827+00 65' LT	1
STA 827+50 33' RT	1
STA 828+00 33' LT	1
STA 841+50 33' RT	1
STA 842+00 33' LT	1
STA 842+50 75' RT	1
STA 843+00 90' LT	1
STA 843+25 75' RT	1
STA 843+80 80' LT	1
STA 844+50 33' LT	1
STA 844+50 33' RT	1
TOTAL	40

70106700 TEMPORARY RUMBLE STRIP

LOCATION	EACH
STA 780+64 RT STAGE 2 & 3	1
STA 785+64 RT STAGE 2 & 3	1
STA 790+64 RT STAGE 2 & 3	1
STA 801+25.58 RT STAGE 3	1
STA 796+25.58 RT STAGE 3	1
STA 791+25.58 RT STAGE 3	1
STA 803+13.89 RT STAGE 2	1
STA 808+13.89 RT STAGE 2	1
STA 813+13.89 RT STAGE 2	1
STA 816+43.60 LT STAGE 2	1
STA 821+43.60 LT STAGE 2	1
STA 826+43.60 LT STAGE 2	1
STA 817+19.38 LT STAGE 3	1
STA 822+19.38 LT STAGE 3	1
STA 827+19.38 LT STAGE 3	1
STA 824+97.50 LT STAGE 2 & 3	1
STA 829+97.50 LT STAGE 2 & 3	1
STA 834+97.50 LT STAGE 2 & 3	1
TOTAL	18

70300520 PAVEMENT MARKING TAPE TYPE III, 4'

LOCATION	EQOI
STA 797+64.00 TO 810+19.38 LT - STAGE 3	2511
STA 797+64.00 TO 809+43.60 RT - STAGE 2	2397
STA 808+25.58 TO 817+97.50 LT - STAGE 3	1948
STA 810+13.89 TO 817+97.50 RT - STAGE 2	1568
TOTAL	8424

70300570 PAVEMENT MARKING TAPE TYPE III, 24'

LOCATION	FOOT
STA 797+64.00 RT STAGE 2 & 3	11
STA 808+25.58 RT STAGE 3	11
STA 809+43.60 LT STAGE 2	11
STA 810+13.89 RT STAGE 2	11
STA 810+19.38 LT STAGE 3	11
STA 817+97.50 LT STAGE 2 & 3	11
TOTAL	66

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	SQ FT
STA 797+64.00 TO 810+19.38 LT - STAGE 3	837
STA 797+64.00 TO 809+43.60 RT - STAGE 2	799
STA 808+25.58 TO 817+97.50 LT - STAGE 3	650
STA 810+13.89 TO 817+97.50 RT - STAGE 2	523
STA 797+64.00 RT STAGE 2 & 3	22
STA 808+25.58 RT STAGE 3	22
STA 809+43.60 LT STAGE 2	22
STA 810+13.89 RT STAGE 2	22
STA 810+19.38 LT STAGE 3	22
STA 817+97.50 LT STAGE 2 & 3	22
TOTAL	2941

LOCATION	EQOI
STA 799+07.61 TO 807+37.33 STAGE 2	750
STA 812+25.18 TO 815+12.32 STAGE 2	288
TOTAL	1038

LOCATION	EQOI
STA 799+50.48 TO 802+12.84 RT STAGE 3	263
STA 803+50.38 TO 806+50.00 RT STAGE 3	300
STA 811+37.87 TO 815+87.02 RT STAGE 3	450
TOTAL	1013

LOCATION	EQOI
STA 797+64.00 TO 799+41.00 WHITE EOP	354
STA 797+64.00 TO 799+41.00 YELLOW CL DOUBLE YELLOW	354
STA 799+41.00 TO 809+45.00 WHITE EOP	2088
STA 799+41.01 TO 809+45.00 YELLOW CL SOLID LEFT	1004
STA 799+41.00 TO 809+45.00 YELLOW CL SKIP DASH RT	251
STA 809+45.00 TO 817+97.50 WHITE EOP	1705
STA 809+45.00 TO 817+97.50 YELLOW CL SKIP DASH	214
STA 826+40.82 TO 826+92.66 WHITE EOP	104
STA 826+40.82 TO 826+92.66 YELLOW CL SKIP DASH	13
STA 842+76.81 TO 843+32.38 WHITE EOP	112
STA 842+76.81 TO 843+32.38 YELLOW CL SKIP DASH	14
TOTAL	6133

LOCATION	EACH
STA 801+47 2-WAY AMBER - 80'	2
STA 805+74 2-WAY AMBER - 80'	2
STA 813+61 2-WAY AMBER - 80'	2
STA 826+67 2-WAY AMBER - 80'	1
STA 843+08 2-WAY AMBER - 80'	1
TOTAL	8

78200410 GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
STA 801+10.00 TO 802+85.00 LT	4
STA 799+25.00 TO 801+50.00 RT	4
TOTAL	8

78201000 TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH
STA 798+75.00 RT	1
STA 800+60.00 LT	1
STA 802+00.00 RT	1
STA 803+35.00 LT	1
TOTAL	4

78300105 PAVEMENT MARKING REMOVAL

LOCATION	EQOI
STA 797+64.00 TO 799+41.00	708
STA 799+41.00 TO 809+45.00	3263
STA 809+45.00 TO 817+97.50	1919
TOTAL	5890

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
STA 801+47	2
STA 805+74	2
STA 813+61	2
STA 826+67	1
STA 843+08	1
TOTAL	8

X8323988 TEMPORARY SOIL RETENTION SYSTEM

LOCATION	SQ FT
STA 801+47	1035
STA 805+74	1002
TOTAL	2037

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NONREDIRECTIV), TEST LEVEL 3

LOCATION	EACH
STA 799+86.61 LT	1
STA 807+38.33 LT	1
STA 802+12.84 RT NARROW	1
STA 806+49.94 LT NARROW	1
STA 812+24.18 LT	1
STA 815+13.32 LT	1
TOTAL	6

Z0030350 IMPACT ATTENUATORS, RELOCATE (NONREDIRECTIV), TEST LEVEL 3

LOCATION	EACH
STA 799+49.48 RT	1
STA 803+49.38 LT	1
STA 811+36.87 RT	1
STA 815+88.02 RT	1
TOTAL	4

LOCATION	SQ YD
STA 813+23 RT	29
STA 826+63 RT	81
STA 842+95 RT	109
TOTAL	219

PLOT DATE = Wed Oct 18 15:28:33 2007
 FILE NAME = c:\projects\0206088\080608.dgn
 USER NAME = jrb
 USER = jrb