

90% FED. 80% FED. 90% FED.
10% ST. 20% ST. 10% ST.
ACIM BRI ACIM

90% FED. 80% FED. 90% FED.
10% ST. 20% ST. 10% ST.
ACIM

F.A.I. SECTION COUNTY TOTAL SHEETS SHEET NO.
80 (50-5) HBK-2 LASALLE 331 5
STA. TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|--------|------------|-------------------------|----------------|--------------------------|
| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QTY. | ROADWAY J000-2A LASALLE | BRIDGE LASALLE | LIGHTING Y030-1E LASALLE |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 1,149 | 1,149 | | |
| 63301000 | REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL | FOOT | 266 | 266 | | |
| 63302000 | REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2 | EACH | 4 | 4 | | |
| 63500105 | DELINEATORS | EACH | 170 | 170 | | |
| 64200105 | SHOULDER RUMBLE STRIP | FOOT | 25,961 | 25,961 | | |
| 66500105 | WOVEN WIRE FENCE, 4' | FOOT | 1,710 | 1,710 | | |
| 66502300 | WOVEN WIRE FENCE REMOVAL | FOOT | 1,215 | 1,215 | | |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 29 | 29 | | |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 3 | 3 | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 20 | 20 | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| 70103700 | TRAFFIC CONTROL COMPLETE | L SUM | 1 | 1 | | |
| 70103816 | TRAFFIC CONTROL SURVEILLANCE | CAL MO | 18 | 18 | | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 18 | 18 | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 6,523 | 6,523 | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 115,361 | 115,361 | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 1,811 | 1,811 | | |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 2,467 | 2,467 | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 369 | 369 | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 125 | 125 | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 44,884 | 44,884 | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 8,741 | 8,741 | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 1,485 | 1,485 | | |
| * 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 99 | 99 | | |
| 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | EACH | 1 | 1 | | |
| 72400500 | RELOCATE SIGN PANEL ASSEMBLY - TYPE A | EACH | 1 | 1 | | |
| 72400600 | RELOCATE SIGN PANEL ASSEMBLY - TYPE B | EACH | 5 | 5 | | |
| * 72400710 | RELOCATE SIGN PANEL - TYPE 1 | SQ FT | 146 | 146 | | |
| * 72400720 | RELOCATE SIGN PANEL - TYPE 2 | SQ FT | 96 | 96 | | |
| * 72400730 | RELOCATE SIGN PANEL - TYPE 3 | SQ FT | 1,406 | 1,406 | | |
| 72700100 | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 14861 | 14861 | | |

* SPECIALTY ITEM

| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QTY. | ROADWAY J000-2A LASALLE | BRIDGE LASALLE | LIGHTING Y030-1E LASALLE |
|------------|---|-------|------------|-------------------------|----------------|--------------------------|
| 72900200 | METAL POST - TYPE B | FOOT | 56 | 56 | | |
| 73000100 | WOOD SIGN SUPPORT | FOOT | 959 | 959 | | |
| 73400100 | CONCRETE FOUNDATIONS | CU YD | 32 | 32 | | |
| 73700100 | REMOVE GROUND-MOUNTED SIGN SUPPORT | EACH | 79 | 79 | | |
| 73700200 | REMOVE CONCRETE FOUNDATION - GROUND MOUNT | EACH | 28 | 28 | | |
| 78003130 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6" | FOOT | 3,410 | 3,410 | | |
| * 78008300 | POLYUREA PAVEMENT MARKING TYPE II - LETTERS & SYMBOLS | SQ FT | 88 | 88 | | |
| * 78008310 | POLYUREA PAVEMENT MARKING TYPE II - LINE 4" | FOOT | 48,835 | 48,835 | | |
| * 78008330 | POLYUREA PAVEMENT MARKING TYPE II - LINE 6" | FOOT | 1,123 | 1,123 | | |
| * 78008340 | POLYUREA PAVEMENT MARKING TYPE II - LINE 8" | FOOT | 5,973 | 5,973 | | |
| * 78008350 | POLYUREA PAVEMENT MARKING TYPE II - LINE 12" | FOOT | 1,751 | 1,751 | | |
| * 78008370 | POLYUREA PAVEMENT MARKING TYPE II - LINE 24" | FOOT | 72 | 72 | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 457 | 457 | | |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 14 | 14 | | |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 16 | 16 | | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 22,588 | 22,588 | | |
| * 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 1 | | | 1 |
| * 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 45 | | | 45 |
| * 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 35 | | | 35 |
| * 81018700 | CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL | FOOT | 235 | | | 235 |
| * 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 187 | | | 187 |
| * 81200230 | CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC | FOOT | 168 | | | 168 |
| * 81300520 | JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 8" X 6" | EACH | 2 | | | 2 |
| * 81603040 | UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE | FOOT | 13,286 | | | 13,286 |
| * 81702120 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8 | FOOT | 243 | | | 243 |
| * 81702130 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6 | FOOT | 486 | | | 486 |
| * 81800200 | AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE | FOOT | 4,314 | | | 4,314 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)
SUMMARY OF QUANTITIES
 SCALE: NONE
 DATE: 11/02/07
 DRAWN BY: KM
 CHECKED BY: SE

