

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TREE REMOVAL		
LOCATION	6 TO 15 UNITS DIAMETER (INCHES) 20100110	OVER 15 UNITS DIAMETER (INCHES) 20100210
RAMP A		
200+86.45, 23.32 RT	6	
201+16.83, 12.35 RT	15	
201+29.23, 4.37 RT	10	
201+80.89, 12.59 LT	15	
203+03.81, 29.28 LT	10	
RAMP B		
318+54.94, 3.24 LT	15	
318+79.76, 2.72 LT	10	
319+15.66, 0.49 RT		24
319+96.51, 21.71 LT		25
320+12.88, 24.36 RT		24
320+28.87, 13.93 LT		24
RAMP C		
420+44.00, 22.00' RT	15	
TOTALS:	96	97

PAVEMENT REMOVAL			
LOCATION	PAVEMENT REMOVAL (SQ YD) 44000100	PAVED SHOULDER REMOVAL (SQ YD) 440004250	HOT-MIX ASPHALT SURFACE REMOVAL, (1 1/2") (SQ YD) 44000155
MARSEILLES			
105+00 TO 117+00	2933	127	122
117+00 TO 128+00	2747	113	
128+00 TO 136+50	1956	-	119
RAMP A			
200+86.45, 23.32 RT	2655	1702	
201+16.83, 12.35 RT	1342	1282	
RAMP B			
314+65.38, 8.61 RT	2507	1328	
315+69.76, 1.33 RT	1786	1195	
RAMP C			
417+19.92, 23.11 LT	2266	1300	
417+21.51, 26.53 LT	1829	1170	
RAMP D			
501+02.63, 23.86 RT	2637	1644	
501+112.7, 4.35 RT	1438	1339	
F.A.I. 80			
810+70 TO 872+30		5476	38330
TOTALS:	24094	16676	38571

ISLAND REMOVAL 44002805	
LOCATION	(SQ FT)
MARSEILLES	
114+40, LT	515
125+67, RT	430
TOTALS:	945

APPROACH SLAB REMOVAL 44000700	
LOCATION	(SQ YD)
MARSEILLES	
18+59 TO 18+99	179
21+01 TO 21+41	179
TOTALS:	358

DRIVEWAY PAVEMENT REMOVAL 44000200	
LOCATION	(SQ YD)
MARSEILLES	
107+30, LT	181
109+55, LT	720
110+65, LT	221
111+17, LT	204
111+65, LT	251
133+85, RT	22
TOTALS:	1599

EXISTING DRAINAGE ITEM REMOVAL			
LOCATION	TYPE	PIPE CULVERT REMOVAL (FT) 50105200	CONCRETE HEADWALL REMOVAL (EACH) 50104400
MARSEILLES			
106+99, 43' LT TO 107+64, 42' LT	15" C.M.P.	1	-
109+21, 43' LT TO 109+88, 43' LT	15" C.M.P.	1	-
110+13, 45' RT TO 110+53, 45' RT	15" C.M.P.	1	-
110+26, 40' LT TO 111+97, 29' LT	15" C.M.P.	1	-
113+29, 30' LT TO 113+30, 29' RT	12" R.C.P.	1	2
132+50, 21' RT TO 132+60, 21' RT	12" C.M.P.	1	-
133+76, 21' RT TO 134+04, 21' RT	12" C.M.P.	1	-
134+68, 19' LT TO 134+90, 19' LT	12" C.M.P.	1	-
134+91, 20' RT TO 135+19, 21' RT	12" C.M.P.	1	-
RAMP A			
208+82, 30' LT TO 209+91, 18' LT	18" R.C.P.	1	1
RAMP B			
305+48, 11' RT	-	-	1
309+72, 22' RT TO 309+81, 20' LT	18" R.C.P.	1	2
313+52, 36' RT TO 313+52, 84' RT	24" R.C.P.	1	2
RAMP C			
404+68, 33' RT	-	-	1
418+73, 63' RT TO 418+84, 11' RT	18" R.C.P.	1	2
RAMP D			
506+84, 37' RT TO 507+05, 1' LT	36" R.C.P.	1	2
515+64, 28' RT	-	-	1
F.A.I. 80			
840+92, 66' RT TO 842+10, 67' RT	24" R.C.P.	1	2
840+92, 65' LT TO 842+61, 66' LT	24" R.C.P.	1	2
TOTALS:		16	18

GUARDRAIL REMOVAL 63200310	
LOCATION	(FT)
MARSEILLES	
LT, 117+60 TO LT, 119+00	140
RT, 117+73 TO RT, 119+00	127
LT, 120+99 TO LT, 122+27	128
RT, 120+99 TO RT, 122+39	140
F.A.I. 80	
RT, 838+40 TO RT, 841+34	294
LT, 841+65 TO LT, 844+85	320
TOTALS:	1149

WOVEN WIRE FENCE REMOVAL 66502300	
LOCATION	(FT)
MARSEILLES	
RT, 112+98 TO RT, 113+98	110
LT, 113+20 TO LT, 114+03	92
LT, 126+10 TO LT, 127+48	145
RAMP C	
RT, 401+07 TO RT, 404+70	363
RT, 404+93 TO RT, 406+98	210
RT, 410+81 TO RT, 411+30	45
RAMP D	
RT, 519+74 TO RT, 522+24	250
TOTALS:	1215

Baker

Baker Engineering, Inc.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 11/02/07

DRAWN BY: KM
CHECKED BY: SE