

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EARTHWORK QUANTITIES FOR PRESTAGE					
LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	1427	1070	515	555	-
RAMP A					
200+00 TO 226+10	-	-	-	-	-
RAMP B					
300+00 TO 321+20	-	-	-	-	-
RAMP C					
400+00 TO 421+15	-	-	-	-	-
RAMP D					
500+00 TO 526+45	-	-	-	-	-
TOTALS:	1427	1070	515	555	0

EARTHWORK QUANTITIES FOR STAGE 1B					
LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	-	-	-	-	-
RAMP A					
200+00 TO 226+10	-	-	-	-	-
RAMP B					
300+00 TO 321+20	2987	2240	934	1306	-
RAMP C					
400+00 TO 421+15	-	-	-	-	-
RAMP D					
500+00 TO 526+45	2515	1886	1192	694	-
TOTALS:	5502	4126	2126	2000	0

EARTHWORK QUANTITIES FOR STAGE 1A					
LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	4130	3098	3614	-516	-
TEMP MARSEILLES					
101+50 TO 112+00	135	101	570	-469	-
131+00 TO 139+50	355	267	23	244	-
RAMP A					
200+00 TO 226+10	-	-	-	-	-
RAMP B					
300+00 TO 321+20	10895	8172	2385	5786	-
TEMP RAMP B					
3010+00 TO 3012+00	79	59	172	-113	-
RAMP C					
400+00 TO 421+15	-	-	-	-	-
RAMP D					
500+00 TO 526+45	3119	2339	2637	-298	-
TEMP RAMP D					
5001+00 TO 5005+50	25.70	19	728	-709	-
F.A.I. 80					
810+70 TO 872+30	1150	862	5215	-4353	1825
TOTALS:	19889	14917	15344	-427	1825

EARTHWORK QUANTITIES FOR STAGE 2A					
LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	5899	4424	3844	580	-
RAMP A					
200+00 TO 226+10	260	195	3720	-3525	-
TEMP RAMP A					
2001+50 TO 2003+50	0	0	1040	-1040	-
RAMP B					
300+00 TO 321+20	403	302	51	251	1805
TEMP RAMP B					
3010+00 TO 3012+00	157	118	0	118	-
RAMP C					
400+00 TO 421+15	4675	3507	3356	151	-
TEMP RAMP C					
4017+50 TO 4022+00	30.72	23	300	-277	-
RAMP D					
500+00 TO 526+45	673	505	330	175	1561
TEMP RAMP D					
5001+00 TO 5005+50	374.28	281	0	281	-
TOTALS:	12472	9354	12641	-3286	3366

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)
SCHEDULE OF QUANTITIES
 SCALE: NONE
 DATE: 11/02/07
 DRAWN BY: KM
 CHECKED BY: SE

