

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	43
STA. TO STA.		ILLINOIS FED. AID PROJECT		

- LEGEND:**
- ① TEMPORARY PAVEMENT MARKING LINE, 4 INCHES (WHITE)
 - ② TEMPORARY PAVEMENT MARKING LINE, 4 INCHES (DOUBLE YELLOW)
 - ③ TEMPORARY PAVEMENT MARKING LINE, 4 INCHES (YELLOW)
 - ④ TEMPORARY PAVEMENT MARKING LINE, SKIP-DASH, 4 INCHES (WHITE)
 - ⑤ DRUM WITH STEADY BURNING LIGHT
 - ⑥ TEMPORARY PAVEMENT
 - ⑦ DOUBLE VERTICAL PANELS (BACK TO BACK) WITH BI-DIRECTIONAL STEADY BURNING LIGHTS
 - ⑧ TEMPORARY CONCRETE BARRIER

MARSEILLES ROAD STAGE 1A & 1B
 STA. 105+00.00 TO STA. 136+00.00
 (BRIDGE OMISSION STA. 117+50.00 TO STA. 122+25.00)
 *TEMPORARY PAVEMENT VARIES 0' TO 17'
 SEE DETAIL "A"

MARSEILLES ROAD STAGE 2A & 2B
 STA. 105+00.00 TO STA. 136+00.00
 (BRIDGE OMISSION STA. 117+50 TO STA. 122+25.00)
 *TEMPORARY PAVEMENT VARIES 0' TO 10' ON OUTSIDE
 AND 0' TO 9' ON INSIDE
 SEE DETAIL "A"

DETAIL "C"
 PROP. RAMP B/
 EXIST. RAMP C
 EXIST. RAMP A/
 PROP. RAMP D

MEET EXISTING MARSEILLES ROAD PAVEMENT

3% MAX

VARIES

2' & VAR. AT RAMP C/D
 0.5' & VAR. AT RAMP A/B

3% MAX

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (VAR. DEPTH) •

EXISTING MARSEILLES ROAD PAVEMENT

NOTES:
 1. TEMPORARY PAVEMENT CONSTRUCTED PRIOR TO STAGE 1B TRAFFIC.

TEMPORARY PAVEMENT DETAIL
 MARSEILLES ROAD RAMP B & D
 * SHALL BE INCLUDED IN COST OF HOT-MIX ASPHALT BINDER COURSE, IL-19, N-50 (TON) PAY ITEM

DETAIL "B"

MEET EXISTING RAMP PAVEMENT

VARIES

23'

VARIES

3% MAX

1.5%

EXISTING RAMP PAVEMENT

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (VAR. DEPTH) •

NOTES:
 1. TEMPORARY PAVEMENT CONSTRUCTED PRIOR TO STAGE 1B TRAFFIC.

TEMPORARY PAVEMENT DETAIL
 MARSEILLES ROAD RAMP A & C
 * SHALL BE INCLUDED IN COST OF HOT-MIX ASPHALT BINDER COURSE, IL-19, N-50 (TON) PAY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
 TYPICAL CROSS-SECTIONS
 MARSEILLES ROAD

SCALE: 1"=50'
 DATE: 11/02/07

DRAWN BY: KM
 CHECKED BY: SE

