



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
786	(109) BR	LASALLE	351	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

IL RTE. 170 BRIDGE REPLACEMENT AT SENECA					80%/20% FED/STATE				CITY
SP	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
					ROADWAY J000	BRIDGE X4.71	LIGHTING Y030	RETAINING WALL Y007	
	54213687	PRECAST REINFORCED CONCRETE ^{FLARED} END SECTIONS 42"	EACH	2	2				
	54213447	END SECTIONS 12"	EACH	5	5				
	54213450	END SECTIONS 15"	EACH	2	2				
	54213465	END SECTIONS 30"	EACH	4	4				
	542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	106	106				
	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	96	96				
	542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	124	124				
	550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	81	81				
	550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	155	155				
	550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	269	269				
	550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	816	816				
	550A0470	STORM SEWERS, CLASS A, TYPE 2, 42"	FOOT	234	234				
	55100500	STORM SEWER REMOVAL 12"	FOOT	141	141				
	55101200	STORM SEWER REMOVAL 24"	FOOT	71	71				
	55101400	STORM SEWER REMOVAL 30"	FOOT	107	107				
	552A0900	STORM SEWERS JACKED IN PLACE, CLASS A 24"	FOOT	168	168				
	56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	5	5				
	58700300	CONCRETE SEALER	SO FT	2,796		2,796			
	59100100	GEOCOMPOSITE WALL DRAIN	SO YD	273		151		122	
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	20	20				
	60100945	PIPE DRAINS 12"	FOOT	180	180				
	60109580	PIPE UNDERDRAIN FOR STRUCTURES, 4"	FOOT	250		250			
	60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1				
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7				
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1				
	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	6	6				
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6	6				
	60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	2	2				
	60255500	MANHOLES TO BE ADJUSTED	EACH	3	3				
	60260100	INLETS TO BE ADJUSTED	EACH	3	3				
	60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	7	7				
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1				
	60403400	GRATES, TYPE A	EACH	1	1				
	60500040	REMOVING MANHOLES	EACH	3	3				
	60500050	REMOVING CATCH BASINS	EACH	2	2				
	60500060	REMOVING INLETS	EACH	8	8				
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8	8				
	60602800	CONCRETE GUTTER, TYPE B	FOOT	174	174				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	517	517				
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	51	51				
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,318	2,318				
	60900515	CONCRETE THRUST BLOCKS	EACH	3	3				
*	63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,775	1,775				
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3				
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3				
	63200310	GUARDRAIL REMOVAL	FOOT	953	953				
*	63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	530	530				
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	32	32				
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	964	964				
*	66900210	HAZARDOUS WASTE DISPOSAL	CU YD	21	21				
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES III OF V

SCALE: DRAWN BY CJO
 DATE: OCTOBER, 2007 CHECKED BY JCL

PLOT DATE = 10/14/2007
 FILE NAME = RT170
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = pjo/mct