



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
786	(109) BR	LASALLE	351	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

INDEX OF QUANTITY SCHEDULES		
NUMBER	SCHEDULE	SHEET
1	TREE REMOVAL	17
2	PAVEMENT REMOVAL	17
3	DRIVEWAY PAVEMENT REMOVAL	17
4	HMA SURFACE REMOVAL	17
5	GUARDRAIL REMOVAL	17
6	CURB AND GUTTER REMOVAL	17
7	SIDEWALK REMOVAL	17
8	EXISTING DRAINAGE STRUCTURES AND STORM SEWER	18
9	EARTHWORK	18
10	PROPOSED PAVEMENT	19
11	PROPOSED DRIVEWAYS	20
12	PROPOSED SIDEWALK	20
13	COMBINATION CONCRETE CURB AND GUTTER	20
14	PROPOSED GUARDRAIL, TYPE A	20
15	PROPOSED RIP RAP	20
16	PROPOSED SIGNS	20
17	PROPOSED DRAINAGE STRUCTURES AND STORM SEWER	21 - 22
18	PROPOSED PAVEMENT MARKING	23
19	TEMPORARY PAVEMENT MARKING	23

TREE REMOVAL				
STATION	OFFSET	SIZE 6"-15" (UNIT)	SIZE >15" (UNIT)	
67+48.38	19.36 LT		30	
67+49.67	30.97 LT		30	
67+58.69	18.75 LT		24	
67+74.53	17.31 LT		28	
67+81.65	16.94 LT		30	
67+97.11	16.35 LT		30	
68+12.14	16.73 LT		15	
68+72.40	20.51 LT		40	
68+77.19	44.86 LT	8		
68+80.59	48.78 LT	8		
68+82.84	50.14 LT	11		
68+83.44	40.7 LT	8		
68+84.98	45.87 LT	8		
68+89.07	11.34 LT	12		
68+89.93	24.03 LT	9		
68+97.98	35.21 LT	6		
68+98.26	15.15 LT	8		
69+00.21	10.88 LT	12		
69+07.60	36.84 LT	6		
69+10.85	25.3 LT	10		
69+12.78	26.4 LT	14		
69+12.98	32.24 LT	14		
69+15.07	50.33 LT	9		
69+18.00	20.34 LT	9		
69+19.07	51.38 LT		18	
69+21.71	35.51 LT	6		
69+23.99	15.21 LT	15		
69+25.37	19.01 LT	9		
69+27.73	17.4 LT	7		
69+28.93	45.16 LT	12		
69+30.76	30.92 LT	6		
69+32.12	50.91 LT	7		
69+34.73	48.95 LT	12		
69+37.56	27.51 LT	12		
69+43.01	30.78 LT	6		
69+45.74	42.37 LT	10		
69+50.37	46.29 LT	11		
69+55.61	64.72 LT	6		
69+60.26	38.98 LT	13		
69+62.96	24.9 LT		30	
69+67.24	58.82 LT	6		
69+67.26	36.21 LT	6		
69+75.43	40.17 LT	9		
69+87.50	45.72 LT		20	
69+92.85	35.86 LT	8		
69+94.75	50.24 LT	7		
69+95.64	69.72 LT	10		
69+96.38	43.01 LT	9		
70+05.44	65.19 LT	10		
70+09.64	25.4 LT	6		
70+10.68	37.58 LT	12		
70+22.23	47.24 LT	6		
70+22.52	64.96 LT	8		
70+22.78	44.48 LT	6		
70+28.36	64.96 LT	7		
70+30.50	75.85 LT	6		
70+32.60	31.57 LT		18	
70+34.44	71.84 LT	9		
70+37.41	27.21 LT	6		
70+38.10	76.15 LT	10		
70+39.78	82.6 LT	7		
70+41.52	73.16 LT	12		
70+41.88	58.34 LT	12		
70+45.71	57.24 LT	9		
70+46.27	65.68 LT	9		
70+46.85	76.76 LT	11		
70+47.24	31.05 LT	15		
70+56.21	18.66 LT	11		
70+56.21	18.66 LT	9		
70+58.96	58.23 LT		24	
70+65.23	55.62 LT	11		
70+72.43	18.58 LT	10		
70+73.92	44.05 LT	12		
70+80.97	93.06 LT	10		
70+81.79	11.8 RT	15		
70+84.47	30.82 LT	9		
70+85.59	45.31 LT		30	
70+89.36	93.35 LT	12		
70+89.36	93.35 LT	10		
70+90.02	57.16 LT	8		
70+90.16	24.45 LT	10		
70+95.47	11.48 RT	15		
71+02.30	23.57 LT		24	

TREE REMOVAL				
STATION	OFFSET	SIZE 6"-15" (UNIT)	SIZE >15" (UNIT)	
71+06.11	72.62 LT		10	
71+08.20	45.73 LT		12	
71+09.28	70.18 LT		6	
71+10.15	59.51 LT		7	
71+12.99	54.77 LT		14	
71+14.17	36.93 LT		15	
71+15.40	53.09 LT		6	
71+15.88	35.99 LT		14	
71+25.84	41.26 LT		9	
71+27.25	51.97 LT		7	
71+29.94	26.66 LT		6	
71+29.94	26.66 LT		14	
71+31.07	11.77 RT		5	
71+33.50	64.78 LT		6	
71+37.40	30.86 LT		6	
71+41.15	37.5 LT		10	
71+44.88	62.44 LT		6	
71+45.47	70.62 LT		7	
71+47.27	40.43 LT		6	
71+47.27	40.43 LT		8	
71+48.24	74.04 LT		7	
71+48.24	74.04 LT		8	
71+48.55	62.89 LT		6	
71+48.71	28.91 LT		9	
71+48.79	40.47 LT		11	
71+53.05	36.67 LT		12	
71+57.32	31.82 LT		12	
71+61.05	7.81 RT		6	
71+61.45	66.00 LT		7	
71+62.93	21.86 LT		8	
71+65.27	60.87 LT		7	
71+65.28	77.77 LT		6	
71+66.49	63.16 LT		7	
71+67.18	31.88 LT		7	
71+74.81	77.77 LT		8	
71+75.91	44.19 LT		7	
71+75.91	44.19 LT		6	
71+78.09	37.21 LT		9	
71+79.82	29.83 LT		7	
71+79.82	29.83 LT		9	
71+82.08	6.69 RT		8	
71+83.42	37.72 LT		10	
71+85.62	37.72 LT		9	
71+97.79	5.72 RT		8	
72+03.00	42.3 LT		6	
72+03.00	42.3 LT		8	
72+15.60	31.09 LT		6	
72+22.23	33.3 LT		12	
72+25.23	21.52 LT		12	
72+31.95	28.47 LT		11	
72+49.75	34.93 LT		9	
72+53.18	28.39 LT		12	
73+13.75	24.67 LT		10	
73+77.48	17.48 LT		36	
74+55.18	19.32 LT		18	
74+58.19	17.48 LT		18	
74+59.87	20.03 LT		7	
74+60.00	7.15 LT		36	
76+45.96	13.39 RT		18	
76+66.48	9.22 RT		30	
76+68.62	10.62 RT		8	
TOTALS:		1132	532	

PAVEMENT REMOVAL			
LOCATION STA. TO STA.	LENGTH (FT)	WIDTH (FT)	AREA (SQ. YD.)
IL-170			
64+34.55 to 67+00	265	28	823
67+00 to 72+19.91	520	28	1517
72+50 to 74+54.93	205 (Bit)	Var	696
72+71.62 to 73+84.87	113 (Conc)	Var	153
74+05 to 76+34.56	230	14.5	356
76+19 to 76+84.62	65.6	Boat Ramp	202
87+28.35 to 89+00	172	28	1090
89+00 to 94+50	550	28	1780
94+50 to 97+49.50	300	28	1014
Dupont Road			
145+00 to 150+50	550	20	1320
150+50 to 154+00	350	20	793
River Road			
17+50 to 19+46.42	196	24	567
20+77.46 to 21+00	22.5	24	60
TOTAL PAVEMENT REMOVAL			10371

DRIVEWAY PAVEMENT REMOVAL			
LOCATION STA. TO STA.	LENGTH (FT)	WIDTH (FT)	AREA (SQ. YD.)
IL-170			
63+27.53			39
64+70.12			11
65+61.92			24
66+57.73			106
67+13.32			12
67+16.45			247
67+62.59			40
68+98.37			448
Dupont Road			
148+22.36			238
150+87.28			290
TOTAL DRIVEWAY REMOVAL			1455

HMA SURFACE REMOVAL, 1 1/2"			
LOCATION STA. TO STA.	LENGTH (FT)	WIDTH (FT)	AREA (SQ. YD.)
IL-170			
62+41.06 to 64+34.35	193	28	597
97+49 TO 99+47.00	198	32	690
TOTAL			1287

GUARDRAIL REMOVAL		
STA. TO STA. (Centerline)	OFFSET	LENGTH (FT)
IL-170		
70+43.57 to 72+18.49	18.8/30.4 RT	176.05
70+43.57 to 72+18.49	52.4/54.0 RT	176.56
87+29.3 to 88+02.43	66.3/51.9 RT	75.86
87+29.3 to 87+76.04	89.4/100.4 RT	49.63
93+15.24 to 94+50	37.6/21.6 RT	134.76
94+50 to 97+85.31	21.4/22.1 RT	340.20
Total		953.06

CURB AND GUTTER REMOVAL		
STA. TO STA.	OFFSET	LENGTH (FT)
IL-170		
62+41 to 67+00	14/27 RT	462
63+47 to 67+00	16/3 LT	352
66+90 to 67+63	0/38 LT	81
67+00 to 71+20	6 LT / 29 RT	356
67+00 to 71+20	27/72 RT	399
87+28 to 89+00	88/128 RT	166
87+29 to 89+00	67/2 RT	223
89+00 to 94+50	67 RT / 16 LT	568
94+50 to 99+47	13/20 LT	495
94+50 to 97+86	16/18 RT	182
River Road		
19+07 to 19+47	12/23 LT	41
Total		3325

SIDEWALK REMOVAL				
STA. TO STA. (Centerline)	OFFSET	LENGTH (FT)	WIDTH (FT)	AREA (SQ. FT)
IL-170				
62+41 to 67+00	16/36 RT		5	2295
63+37 to 66+45	21/32 LT		5	1245
66+75 to 67+00	16/23 LT		5	107
67+00 to 68+65	31/60 RT		5	954
67+40 to 69+53	18 LT / 4 RT		5	927
Total				5528

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 1" = 20'

DATE: OCTOBER, 2007

DRAWN BY: CJO
CHECKED BY: JCL