

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(3)I	LASALLE	5	3
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	90% FED. / 10% STATE
				CONSTRUCTION CODE:
				Y031-1F
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	896	896
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	20	20
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2	2
81900200	^{AND} TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	896	896
85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1	1
85800100	FLASHER CONTROLLER	EACH	1	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	935	935
88040030	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	1	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	624	624

PLOT DATE = 07/07
 FILE NAME = NOTES.DGN
 PLOT SCALE =
 USER NAME = NOE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 68 (IL 23)
 SECTION (3)I
 LASALLE COUNTY

SCALE: VERT.
 HORIZ.
 DATE 07/07

DRAWN BY NOE
 CHECKED BY JLS