

SCOPE OF WORK

MILE POST	STR. NUMBER	LANE	GR REMOVAL	SPBGR TYPE A	TBT TYPE 1 SPEC (TANG)	TERM MKS DA	TBT T6	TBT T2	IMP ATTN NON-RE TL3	FURN FX	CONC STRUCT.	P.CULV. CL "D" TYPE 1, 15"	METAL END SECTIONS, 15"	REBAR EPOXY COATED	REM & REERECT GR	CURB REMOVAL	CLASS SI CONC (MISC)	CONC CURB TYPE B	SCOPE OF WORK (SEE LEGEND)	
			FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	CU YD	CU YD	FOOT	EACH	POUNDS	FOOT	FOOT	CU YD	FOOT		
36.5	006-0001	EBDL	44				1	1								30	5	0.56	30	2,6,10
36.5	006-0001	FBPL	44				1	1								30	5	0.56	30	2,6,10
36.5	006-0002	WBDL	44				1	1								30	5	0.56	30	2,6,10
36.5	006-0002	WBPI	44				1	1								30	5	0.56	30	2,6,10
37.8	006-0115	EBDL	94		1		1			5								1.1	44	1,2,4,5
37.8	006-0115	MEDIAN	200						2											7
37.8	006-0115	WBDL	94		1		1			5								1.1	44	1,2,4,5
37.2	006-0003	EBDL	44				1	1							30	5	0.56	30	2,6,10	
37.2	006-0003	FBPL	44				1	1							30	5	0.56	30	2,6,10	
37.2	006-0004	WBDL	44				1	1							30	5	0.56	30	2,6,10	
37.2	006-0004	WBPI	44				1	1							30	5	0.56	30	2,6,10	
38.5	006-0122	FB	158		1		2			5								1.1	44	1,2,4,5
38.5	006-0122	MEDIAN	200						2											7
38.5	006-0122	WB	94		1		1			5								1.1	44	1,2,4,5
39.2	006-0005	EBDL	44				1	1							30	5	0.56	30	2,6,10	
39.2	006-0005	FBPL	44				1	1							30	5	0.56	30	2,6,10	
39.2	006-0006	WBDL	44				1	1							30	5	0.56	30	2,6,10	
39.2	006-0006	WBPI	44				1	1							30	5	0.56	30	2,6,10	
39.4	006-0007	EBDL	50		1					5										1,4
39.4	006-0007	FBPL	200	300	1		1			5										4,8
39.4	006-0008	WBDL	50		1					5										1,4
39.4	006-0008	WBPI	200	300	1					5										4,8
40.3	006-0121	FB	44				1											0.56	44	2,5
40.3	006-0121	MEDIAN	200						2											7
40.3	006-0121	WB	44		1		1			5								0.56	44	1,2,4,5
41	NO STRUCTURE	WBDL	50		1		1													1,4
42.2	006-0117	FB	44		1		1			5								0.56	44	1,2,4,5
42.2	006-0117	MEDIAN	200						2											7
42.2	006-0117	WB	44				1											0.56	44	2,5
43.5	006-0009	EBDL			1		1			5										1,4
43.5	006-0009	FBPL	200	300	1		1			5										4,8
43.5	006-0010	WBDL																		NO WORK
43.5	006-0010	WBPI																		NO WORK
44	006-0011	EBDL																		NO WORK
44	006-0011	FBPL																		NO WORK
44	006-0012	WBDL			1		1			5										1,4
44	006-0012	WBPI	200	300	1		1			5										4,8
45	006-0089	FB	158		1		1	2		5								2.2	88	1,2,4,5
45	006-0089	MEDIAN	260						2			75	2							7,11
45	006-0089	WB	108					2										2.2	88	1,2,4,5
45.1	006-0013	FB	44					1										1.1	44	2,5
45.1	006-0013	MEDIAN	340						2											7
45.1	006-0013	WB	158		1		1	2		5								2.2	44	1,2,4,5
47	NO STRUCTURE	EBDL	50		1		1													1,4
48.2	006-0123	FB	44				1											1.1	44	2,5
48.2	006-0123	MEDIAN	310						2											7
48.2	006-0123	WB	94		1		1	1		5								1.1	44	1,2,4,5
50.1	006-0112	FB	94		1		1	1		5								1.1	44	1,2,4,5
50.1	006-0112	MEDIAN	360						2											7
50.1	006-0112	WB	94		1		1	1		5								1.1	44	1,2,4,5

SCOPE OF WORK LEGEND: 1.REM DEFICIENT E.S. AND REPLACE W/TYPE 1 E.S. 2. REM DEFICIENT END SECTION/REPLACE W/TYPE 6 E.S. 3.ADD PIPE CULVERT NEAR PIER FOR DRAINAGE 4. ADD FURNISHED EXCAVATION FOR TBT, T1 (SP) TO MEET STD 630301  
 5. PLACE TYPE B CURB UNDER EXIST. OR PROP. T6 END SECT 6. REMOVE 5' FO TAPERED CURB AND PLACE NEW C&G UNDER ALL OF TYPE 6 E.S. 7. REMOVE MEDIAN G.R. AND REPLACE W/IMP. ATTN.  
 8. REMOVE TAPERED MEDIAN G.R, REPLACE WITH TANGENT G.R. AND TYPE 1 (SP) TANGENT E.S. 9. ADD CONCRETE TO PIER CAP 10. REMOVE AND RE-ERECT G.R. FOR TYPE B CURB PLACMENT 11. PLACE PIPE CULVERT AT CENTER PIER FOR DRAINAGE  
 NOTE--EXISTING GR IN BITUMINOUS STABILIZATION FOR 006-0124 EBDL. REMOVE AND INSERT NEW END SECTION THROUGH EXISTING STABILIZATION-COST INCLUDED IN THE PRICE OF TBT, T1 (SP) TANG.  
 NOTE- NO CURB TO BE PLACE NEAR STRUCTURES 006-0007,006-0008,006-0009,006-0010,006-0011,006-0012-THESE BRIDGES TO HAVE NEW DECKS WITH APPROACH PAVEMENT WITHIN A YEAR ON A SPERERATE CONTRACT

GUARDRAIL AND BARRIER WALL MARKERS		
LOCATION	GUARDRAIL	BARRIER
	MARKERS	WALL MARKERS
BUREAU COUNTY	EACH 50	EACH 50
TOTAL	50	50

GUARDRAIL MARKERS ARE TO BE PLACED ON ALL NEW GUARDRAIL AND END SECTIONS ACCORDING TO STADARD 635006. ALSO, PLACE GUARDRAIL MARKERS, DELINATORS, AND BARRIER WALL MARKERS THROUGHOUT COUNTY TO REPLACE MISSING OR DAMAGED ONES. FINAL LOCATION TO BE DETERMINED BY THE RESIDENT ENGINEER