

ROUTE NO. FAP 313	SECTION (7BY)BR	COUNTY HENDERSON	SHEET 68	SHEET 4A
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES		80% / 20% FED / STATE				
CODE #	ITEM	UNIT	TOTAL	CONSTRUCTION CODE		
				ROADWAY 1000	SN 029-0066 X071	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	1130	1130		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4	4		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1		1	
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	228	228		
70300200	TEMPORARY PAVEMENT MARKING	FOOT	6618	6618		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5868	5303	565	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19	19		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2	
* 78200405	GUARDRAIL MARKERS	EACH	32	32		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8		
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	553	553		
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	188	188		
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	1483	1483		
Z0013796	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0016600	DETOUR ROADWAY REMOVAL	SQ YD	3122	3122		
Z0028000	GEOTECHNICAL FABRIC FOR EROSION CONTROL	SQ YD	229	229		

* - SPECIALTY ITEM

7A

HAMPTON, LENZINI & RENWICK, INC. CIVIL & STRUCTURAL ENGINEERS 3085 STEVENSON DRIVE, SUITE 201 SPRINGFIELD, ILLINOIS 62703 (217) 548-3400 ELGIN • SPRINGFIELD		SUMMARY OF QUANTITIES U.S. 34 OVER P.D. CREEK F.A.P. 313 / SECTION (7BY)BR HENDERSON COUNTY STRUCTURE NO. 036-0052 / STATION 301+23
PROJECT NUMBER: 12-44-0001-X	DATE: 08/07/07	
DESIGNED: W.D.G.	CHECKED: L.F.S.	DRAWN: W.J.S.