

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(103BRH-1	MERCER	9	2
STA. 10+530.216		TO STA. 10+560.696		
FED. RDW DIST. NO. 4 ILLINOIS FED. AID PROJECT				

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Construction field requirements for guardrail work shall be according to Article 633 of the "Standard Specifications for Road and Bridge Construction".

Construction field requirements for Erosion Control Blanket work shall be according to Supplemental Specification for Section 1081.

Onsite storage of metal materials shall be off of the pavement and according to Article 1006.34

PLOT DATE * #DATE66-29-87
 FILE NAME * #FILE1ESKAGEINORREFASTONP.MS\SOUND\A\Bridg\Repr\Contra\sta\Emer\gen\p\CBear\Repar\A6752 91666-0893 US67over\pope\c\ldgn
 PLOT SCALE * #SCALE8
 REFERENCE * #REF4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: VERT.
HORIZ.
DATE 07-02-2007

DRAWN BY CEJ
CHECKED BY