

# SUMMARY OF QUANTITIES

		100% STATE SAFETY-2A McDONOUGH COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	48	48
40600525	LEVELING BINDER (HAND METHOD), N50	TON	13	13
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	44	44
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	70	70
50102400	CONCRETE REMOVAL	CU YD	18.7	18.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18.3	18.3
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	2,469	2,469
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,560	1,560
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	318	318
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	1,213	1,213
67000400	ENGINEER FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,600	1,600

		100% STATE SAFETY-2A McDONOUGH COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	533	533
70400100	TEMPORARY CONCRETE BARRIER	FOOT	762.5	762.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	762.5	762.5
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,000	2,000
78200530	BARRIER WALL MARKERS, TYPE C	EACH	4	4
X0301424	SILICONE JOINT SEALER	FOOT	30	30
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	2,501	2,501
X0320887	POLYMER CONCRETE	CU FT	3.1	3.1
Z0001900	ASBETOS BEARING PAD REMOVAL	EACH	11	11
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

\*SPECIALTY ITEM