

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(121,122)RS-3	VERMILION	89	13
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PARTIAL DEPTH PATCHING SCHEDULE (EX. 6" CONCRETE PAVEMENT)

STATION	DIRECTION	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (inch)	X4401705	X4421000
					PARTIAL DEPTH REMOVAL (sq. yd)	PARTIAL DEPTH PATCHING (tons)
1206+48	NB	6	12	7.5	8.0	4.7
1210+90	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1211+61	NB	50	6	7.5	33.3	19.6
1212+55	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1215+00	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
1215+80	SB	6	12	7.5	8.0	4.7
1218+44	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
1225+17	SB	200	12	7.5	266.7	156.8
1233+50	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
1233+64	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1235+65	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
1237+38	NB	8	12	7.5	10.7	6.3
	SB	8	12	7.5	10.7	6.3
1240+55	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
1242+65	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1253+54	SB	12	6	7.5	8.0	4.7
1260+81	NB	50	12	7.5	66.7	39.2
1261+21	NB	50	6	7.5	33.3	19.6
1261+70	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1271+00	NB	6	12	7.5	8.0	4.7
1272+27	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
1275+42	SB	8	12	7.5	10.7	6.3
	NB	8	12	7.5	10.7	6.3
SHEET TOTALS					650.7 (sq. yd)	382.6 (tons)
EX. 6" TOTALS					3264.0 (sq. yd)	1948.0 (tons)

PARTIAL DEPTH PATCHING SCHEDULE (EX. 7" CONCRETE PAVEMENT)

STATION	DIRECTION	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (inch)	X4401705	X4421000
					PARTIAL DEPTH REMOVAL (sq. yd)	PARTIAL DEPTH PATCHING (tons)
848+00	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
848+53	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
849+02	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
850+02	NB	8	12	7.5	10.7	6.3
	SB	8	12	7.5	10.7	6.3
853+02	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
864+35	NB	10	12	7.5	13.3	7.8
866+87	SB	6	12	7.5	8.0	4.7
867+36	SB	6	12	7.5	8.0	4.7
	NB	6	12	7.5	8.0	4.7
868+33	NB	6	12	7.5	8.0	4.7
	SB	6	12	7.5	8.0	4.7
					0.0	0.0
SHEET TOTALS					138.7 (sq. yd)	81.5 (Tons)
EX. 7" SHEET TOTALS					139.0 (sq. yd)	82.0 (tons)

PARTIAL DEPTH SUMMARY		
ITEMS	X4401705 - PARTIAL DEPTH REMOVAL	X4421000 - PARTIAL DEPTH PATCHING
EX. 6" CONCRETE PAVEMENT	3264.0	1948.0
EX. 7" CONCRETE PAVEMENT	139.0	82.0
TOTALS	3403.0	2030.0

NOTE:

DUE TO THE EXISTING OVERLAY THICKNESS OF 7 1/2", PARTIAL DEPTH PATCHING DEPTHS WILL EXCEED 4 3/4 INCHES. THE PATCH SHALL BE PLACED IN 2 LIFTS. THIS WORK WILL BE MEASURED IN TONS AND PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR PARTIAL DEPTH PATCHING.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES
NAME	DATE	
SCALE: VERT.	DRAWN BY	CHECKED BY
HORIZ. DATE		