

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	DOUGLAS	42	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

(12,Y-15D)10RS-2

## SUMMARY OF QUANTITIES

SHEET 1 OF 2

LOCATION OF WORK:

FAP 808  
IL. RTE. 130  
RURAL TWO LANE  
DOUGLAS COUNTY  
STA. 3+33.00  
TO  
STA. 297+50.00

FUNDING BREAKOUT:

80 % FED  
20 % STATE

CONSTRUCTION TYPE CODE:

1000

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40300602	SEAL COAT AGGREGATE, SPECIAL	TON	193.0
20200100	EARTH EXCAVATION	CU YD	96.0
20400800	FURNISHED EXCAVATION	CU YD	380.0
* 25000200	SEEDING, CLASS 2	ACRE	0.7
* 25000350	SEEDING, CLASS 7	ACRE	0.7
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	56.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	56.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	56.0
* 25100115	MULCH, METHOD 2	ACRE	0.7
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	70.0
* 28000400	PERIMETER EROSION BARRIER	FOOT	1,836.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	229.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	43.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8,036.0
40600300	AGGREGATE (PRIME COAT)	TON	169.0
40600625	LEVEL BINDER (MACHINE METHOD), N50	TON	2,580.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,710.0
40600990	TEMPORARY RAMP	SQ YD	544.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5,360.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,780.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	911.0
40800030	AGGREGATE (PRIME COAT)	TON	17.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	718.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	88,854.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	958.0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	213.0
44000500	COMBINATION CURB <sup>AND</sup> GUTTER REMOVAL	FOOT	150.0
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	69.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,720.0
60255500	MANHOLES TO BE ADJUSTED	EACH	7.0
60260100	INLETS TO BE ADJUSTED	EACH	1.0

\*SPECIALTY ITEM

PLT DATE : 10/08/2007  
 PLT NAME : C:\Users\j...  
 PLT SCALE : 1:1  
 USER NAME : j...

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 F.A.P. 808 (IL ROUTE 130)  
 SECTION (12,Y-15D)10RS-2  
 DOUGLAS COUNTY  
 Sheet 1 of 2  
 SCALE: NOT TO SCALE  
 DATE: 10/04/07  
 DRAWN BY: B.B.P.  
 CHECKED BY: G.A.E.