

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	DOUGLAS	42	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHEET 3 OF 5

(12,Y-15D)ORS-2

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
3+33.00		22+20.00	SKIP-DASH	480.0	YELLOW
3+33.00		5+56.00	S. B. NO PASS	223.0	YELLOW
22+20.00		25+95.00	DBL NO PASS	750.0	YELLOW
3+33.00		25+95.00	EDGE LINE	4,524.0	WHITE
26+03.75		224+50.00	EDGE LINE	39,692.5	WHITE
26+03.75		28+70.00	DBL NO PASS	532.5	YELLOW
28+70.00		90+82.00	SKIP-DASH	1,560.0	YELLOW
49+90.00		57+92.00	N. B. NO PASS	802.0	YELLOW
61+72.00		69+04.00	S. B. NO PASS	732.0	YELLOW
77+54.00		83+60.00	N. B. NO PASS	606.0	YELLOW
88+74.00		94+54.00	S. B. NO PASS	580.0	YELLOW
94+54.00		224+50.00	SKIP-DASH	3,260.0	YELLOW
90+82.00		97+46.00	N. B. NO PASS	664.0	YELLOW
100+72.00		106+16.00	S. B. NO PASS	544.0	YELLOW
105+56.00		117+06.00	N. B. NO PASS	1,150.0	YELLOW
117+06.00		126+14.00	S. B. NO PASS	908.0	YELLOW
169+50.00		176+10.00	N. B. NO PASS	660.0	YELLOW
182+40.00		187+90.00	S. B. NO PASS	550.0	YELLOW
224+50.00		225+75.00	EDGE LINE	125.0	WHITE
224+50.00		251+00.00	SKIP-DASH	670.0	YELLOW
251+00.00		252+87.33	DBL NO PASS	374.7	YELLOW
253+18.00		255+30.00	DBL NO PASS	424.0	YELLOW
255+30.00		263+13.00	SKIP-DASH	210.0	YELLOW
263+13.00		265+95.00	MEDIAN	767.7	YELLOW
265+43.00		265+95.00	TURN LANE	52.0	WHITE
266+96.00		267+74.00	TURN LANE	78.0	WHITE
266+96.00		270+94.00	MEDIAN	1,279.3	YELLOW
270+94.00		278+06.00	SKIP-DASH	190.0	YELLOW
277+09.00		278+06.00	EDGE LINE	97.0	WHITE
278+06.00		297+50.00	EDGE LINE	3,888.0	WHITE
278+06.00		297+50.00	SKIP-DASH	500.0	YELLOW
8+96.00		9+53.00	MEDIAN	114.0	YELLOW (HARRISON AVE)
8+96.00		9+53.00	TURN LANE	57.0	WHITE (HARRISON AVE)
10+46.00		11+06.00	MEDIAN	120.0	YELLOW (HARRISON AVE)
10+46.00		11+06.00	TURN LANE	60.0	WHITE (HARRISON AVE)
TOTAL = 67,224.7 FT					
USE = 67,225.0 FT					

70300240 TEMPORARY PAVEMENT MARKING - LINE 6"

STATION	LOCATION	QUANTITY (FT)	COLOR
266+01.00	CROSSWALK	56.0	WHITE
266+07.00	CROSSWALK	62.0	WHITE
266+84.00	CROSSWALK	62.0	WHITE
266+90.00	CROSSWALK	56.0	WHITE
9+59.00	CROSSWALK	64.0	WHITE (HARRISON AVE)
9+65.00	CROSSWALK	74.0	WHITE (HARRISON AVE)
10+34.00	CROSSWALK	66.0	WHITE (HARRISON AVE)
10+40.00	CROSSWALK	56.0	WHITE (HARRISON AVE)
TOTAL = 496.0 FT			

70300260 TEMPORARY PAVEMENT MARKING - LINE 12"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
263+93.00		265+43.00	MEDIAN	54.0	YELLOW
267+74.00		270+14.00	MEDIAN	83.0	YELLOW
TOTAL = 137.0 FT					

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

STATION	LOCATION	QUANTITY (FT)	COLOR
RT. 22+30.00	RXR STOP BAR	13.0	WHITE
RT. 22+80.00	RXR STOP BAR	13.0	WHITE
RT. 25+80.00	RXR STOP BAR	13.0	WHITE
LT. 26+19.00	RXR STOP BAR	13.0	WHITE
LT. 28+10.00	RXR STOP BAR	13.0	WHITE
LT. 28+60.00	RXR STOP BAR	13.0	WHITE
RT. 251+10.00	RXR STOP BAR	13.0	WHITE
RT. 251+60.00	RXR STOP BAR	13.0	WHITE
RT. 252+75.00	RXR STOP BAR	13.0	WHITE
LT. 253+30.00	RXR STOP BAR	13.0	WHITE
LT. 254+70.00	RXR STOP BAR	13.0	WHITE
LT. 255+20.00	RXR STOP BAR	13.0	WHITE
RT. 265+95.00	STOP BAR	26.0	WHITE
LT. 266+96.00	STOP BAR	30.0	WHITE
RT. 9+53.00	STOP BAR	32.0	WHITE (HARRISON AVE)
LT. 10+46.00	STOP BAR	28.0	WHITE (HARRISON AVE)
TOTAL = 272.0 FT			

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

STATION	LOCATION	QUANTITY (FT)	COLOR
RT. 22+55.00	RXR CROSSING	61.2	WHITE
LT. 28+35.00	RXR CROSSING	61.2	WHITE
RT. 251+35.00	RXR CROSSING	61.2	WHITE
LT. 254+95.00	RXR CROSSING	61.2	WHITE
RT. 265+43.00	TURN ARROW	15.6	WHITE
RT. 265+77.00	TURN ARROW	15.6	WHITE
LT. 267+14.00	TURN ARROW	15.6	WHITE
LT. 267+74.00	TURN ARROW	15.6	WHITE
RT. 8+96.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
RT. 9+35.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
LT. 10+64.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
LT. 11+06.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
TOTAL = 369.6 FT			
USE = 370.0 FT			

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
224+50.00		251+00.00	SKIP-DASH	670.0	YELLOW
251+00.00		252+87.33	DBL NO PASS	374.7	YELLOW
253+18.00		255+30.00	DBL NO PASS	424.0	YELLOW
255+30.00		263+13.00	SKIP-DASH	210.0	YELLOW
263+13.00		265+95.00	MEDIAN	767.7	YELLOW
265+43.00		265+95.00	TURN LANE	52.0	WHITE
266+96.00		267+74.00	TURN LANE	78.0	WHITE
266+96.00		270+94.00	MEDIAN	1,279.3	YELLOW
270+94.00		278+06.00	SKIP-DASH	190.0	YELLOW
8+96.00		9+53.00	MEDIAN	114.0	YELLOW (HARRISON AVE)
8+96.00		9+53.00	TURN LANE	57.0	WHITE (HARRISON AVE)
10+46.00		11+06.00	MEDIAN	120.0	YELLOW (HARRISON AVE)
10+46.00		11+06.00	TURN LANE	60.0	WHITE (HARRISON AVE)
TOTAL = 4,396.7 FT					
USE = 4,397.0 FT					

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

STATION	LOCATION	QUANTITY (FT)	COLOR
266+01.00	CROSSWALK	56.0	WHITE
266+07.00	CROSSWALK	62.0	WHITE
266+84.00	CROSSWALK	62.0	WHITE
266+90.00	CROSSWALK	56.0	WHITE
9+59.00	CROSSWALK	64.0	WHITE (HARRISON AVE)
9+65.00	CROSSWALK	74.0	WHITE (HARRISON AVE)
10+34.00	CROSSWALK	66.0	WHITE (HARRISON AVE)
10+40.00	CROSSWALK	56.0	WHITE (HARRISON AVE)
TOTAL = 496.0 FT			

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
263+93.00		265+43.00	MEDIAN	54.0	YELLOW
267+74.00		270+14.00	MEDIAN	83.0	YELLOW
TOTAL = 137.0 FT					

PLOT DATE = 10/18/2007
 FILE NAME = c:\projects\0506902 (v8)\70275\text.dgn
 USER NAME = collierfw

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. 808 (IL ROUTE 130)
 SECTION (12,Y-15D)ORS-2
 DOUGLAS COUNTY
 Sheet 3 of 5
 SCALE: NOT TO SCALE
 DATE: 10/04/07
 DRAWN BY: B.B.P.
 CHECKED BY: G.A.E.