

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	DOUGLAS	42	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHEET 4 OF 5

(12,Y-15D)ORS-2

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

STATION	LOCATION	QUANTITY (FT)	COLOR
RT. 22+30.00	RXR STOP BAR	13.0	WHITE
RT. 22+80.00	RXR STOP BAR	13.0	WHITE
RT. 25+80.00	RXR STOP BAR	13.0	WHITE
LT. 26+19.00	RXR STOP BAR	13.0	WHITE
LT. 28+10.00	RXR STOP BAR	13.0	WHITE
LT. 28+60.00	RXR STOP BAR	13.0	WHITE
RT. 251+10.00	RXR STOP BAR	13.0	WHITE
RT. 251+60.00	RXR STOP BAR	13.0	WHITE
RT. 252+75.00	RXR STOP BAR	13.0	WHITE
LT. 253+30.00	RXR STOP BAR	13.0	WHITE
LT. 254+70.00	RXR STOP BAR	13.0	WHITE
LT. 255+20.00	RXR STOP BAR	13.0	WHITE
RT. 265+95.00	STOP BAR	26.0	WHITE
LT. 266+96.00	STOP BAR	30.0	WHITE
RT. 9+53.00	STOP BAR	32.0	WHITE (HARRISON AVE)
LT. 10+46.00	STOP BAR	28.0	WHITE (HARRISON AVE)
TOTAL =		272.0 FT	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION	TO	STATION	LOCATION	QUANTITY (EACH)
3+33.00		5+56.00	NO PASSING	6.0
5+56.00		21+74.00	CENTERLINE	20.0
21+74.00		25+95.00	NO PASSING	11.0
26+03.75		29+56.00	NO PASSING	9.0
29+56.00		49+90.00	CENTERLINE	25.0
49+90.00		57+92.00	NO PASSING	20.0
57+92.00		61+72.00	CENTERLINE	5.0
61+72.00		69+04.00	NO PASSING	18.0
69+04.00		77+54.00	CENTERLINE	11.0
77+54.00		83+60.00	NO PASSING	15.0
83+60.00		88+74.00	CENTERLINE	6.0
88+74.00		97+46.00	NO PASSING	22.0
97+46.00		100+72.00	CENTERLINE	4.0
100+72.00		106+16.00	NO PASSING	14.0
106+16.00		116+50.00	NO PASSING	26.0
116+50.00		126+14.00	NO PASSING	24.0
126+14.00		145+24.74	CENTERLINE	24.0
149+48.36		169+50.00	CENTERLINE	25.0
169+50.00		176+10.00	NO PASSING	17.0
176+10.00		182+40.00	CENTERLINE	8.0
182+40.00		187+90.00	NO PASSING	14.0
187+90.00		250+97.00	CENTERLINE	79.0
250+97.00		252+87.33	NO PASSING	5.0
253+18.00		255+26.00	NO PASSING	5.0
255+26.00		263+93.00	CENTERLINE	11.0
263+93.00		265+93.00	MEDIAN	20.0
265+43.00		265+93.00	TURN LANE	2.0
266+96.00		270+14.00	MEDIAN	32.0
266+96.00		267+74.00	TURN LANE	2.0
270+14.00		272+54.90	CENTERLINE	3.0
273+91.48		297+50.00	CENTERLINE	30.0
TOTAL =				513.0 EACH

78001110 PAINT PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
3+33.00		22+20.00	SKIP-DASH	480.0	YELLOW
3+33.00		5+56.00	S. B. NO PASS	223.0	YELLOW
22+20.00		25+95.00	DBL NO PASS	750.0	YELLOW
3+33.00		25+95.00	EDGE LINE	4,524.0	WHITE
26+03.75		224+50.00	EDGE LINE	39,692.5	WHITE
26+03.75		28+70.00	DBL NO PASS	532.5	YELLOW
28+70.00		90+82.00	SKIP-DASH	1,560.0	YELLOW
49+90.00		57+92.00	N. B. NO PASS	802.0	YELLOW
61+72.00		69+04.00	S. B. NO PASS	732.0	YELLOW
77+54.00		83+60.00	N. B. NO PASS	606.0	YELLOW
88+74.00		94+54.00	S. B. NO PASS	580.0	YELLOW
94+54.00		224+50.00	SKIP-DASH	3,260.0	YELLOW
90+82.00		97+46.00	N. B. NO PASS	664.0	YELLOW
100+72.00		106+16.00	S. B. NO PASS	544.0	YELLOW
105+56.00		117+06.00	N. B. NO PASS	1,150.0	YELLOW
117+06.00		126+14.00	S. B. NO PASS	908.0	YELLOW
169+50.00		176+10.00	N. B. NO PASS	660.0	YELLOW
182+40.00		187+90.00	S. B. NO PASS	550.0	YELLOW
224+50.00		225+75.00	EDGE LINE	125.0	WHITE
277+09.00		278+06.00	EDGE LINE	97.0	WHITE
278+06.00		297+50.00	EDGE LINE	3,888.0	WHITE
278+06.00		297+50.00	SKIP-DASH	500.0	YELLOW
TOTAL =					62,828.0 FT

78100100 RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO	STATION	LOCATION	QUANTITY (EACH)	TYPE
3+33.00		22+20.00	CENTERLINE	25.0	TWO-WAY AMBER
22+20.00		25+95.00	DBL NO PASS	12.0	TWO-WAY AMBER
26+03.75		28+70.00	DBL NO PASS	8.0	TWO-WAY AMBER
28+70.00		90+82.00	CENTERLINE	79.0	TWO-WAY AMBER
90+82.00		94+54.00	DBL NO PASS	12.0	TWO-WAY AMBER
94+54.00		145+24.74	CENTERLINE	64.0	TWO-WAY AMBER
149+48.36		251+00.00	CENTERLINE	128.0	TWO-WAY AMBER
251+00.00		252+87.33	DBL NO PASS	6.0	TWO-WAY AMBER
253+18.00		255+20.00	DBL NO PASS	8.0	TWO-WAY AMBER
255+20.00		263+13.00	CENTERLINE	11.0	TWO-WAY AMBER
263+13.00		263+93.00	MEDIAN	6.0	TWO-WAY AMBER
263+93.00		265+43.00	MEDIAN	10.0	TWO-WAY AMBER
265+43.00		265+95.00	MEDIAN	4.0	TWO-WAY AMBER
265+43.00		265+95.00	TURN LANE	3.0	ONE-WAY CRYSTAL
266+96.00		267+74.00	TURN LANE	3.0	ONE-WAY CRYSTAL
266+96.00		267+74.00	MEDIAN	6.0	TWO-WAY AMBER
267+74.00		270+14.00	MEDIAN	14.0	TWO-WAY AMBER
270+14.00		270+94.00	MEDIAN	6.0	TWO-WAY AMBER
270+94.00		272+54.90	CENTERLINE	3.0	TWO-WAY AMBER
273+91.48		297+50.00	CENTERLINE	31.0	TWO-WAY AMBER
TOTAL =					439.0 EACH

PLOT DATE = 10/18/2007
 FILE NAME = G:\projects\0506902 (v8)\70275\text.dgn
 USER NAME = collierdw

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. 808 (IL ROUTE 130)
 SECTION (12,Y-15D)ORS-2
 DOUGLAS COUNTY
 Sheet 4 of 5
 SCALE: NOT TO SCALE
 DATE: 10/04/07
 DRAWN BY: B.B.P.
 CHECKED BY: G.A.E.