

GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.07

EXISTING STATE-OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THESE LINES. THE STATE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.

ALSO THERE MAY BE UTILITIES PRESENT WHICH WERE INSTALLED BY THE STATE BUT ARE MAINTAINED BY OTHERS (CITY, TOWN, ETC.) THE APPROXIMATE LOCATIONS OF THESE LINES ARE ALSO SHOWN ON THE PLANS ALONG WITH THE NAME OF THE MAINTAINING AGENCY. THE CONTRACTOR SHALL COORDINATE THE LOCATING OF THESE LINES WITH THE LOCAL AGENCY PRIOR TO COMMENCING ANY EXCAVATION OR BORING IN THEIR VICINITY. SHOULD THESE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF, AND AT NO COST TO, THE LOCAL AGENCY AND THE STATE.

G.N.-107.31

UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED (QUALITY LEVEL C &/OR QUALITY LEVEL D) AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PERFORMED. J.U.L.I.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800)892-0123.

THE FOLLOWING UTILITY OWNERS MARKED WITH AN "*" BELONG TO J.U.L.I.E.:

Mr. David Pottle
* Ameren-IP (Gas)
1112 W. Anthony Drive
P.O. Box 17070
Urbana, IL 61803
(217) 383-7241

Mr. Greg Curtis
* Verizon North Central, Inc
ILL0301
212 E Grove St
Rantoul, IL 61866
(217) 892-3359

GENERAL NOTES

1. CONTRACTOR SHALL REPLACE POLES AS CLOSE AS POSSIBLE TO THE EXISTING LIGHT POLE LOCATIONS.
2. ALL POLES MUST BE LOCATED TO MAINTAIN THE REQUIRED DISTANCE TO THE OVERHEAD POWERLINES.
3. PROPOSED LIGHTING CONTROLLER AND FLASHING BEACON CONTROLLER ARE TO BE HOUSED IN THE SAME CABINET.

Mr. Steve Estes
* Ameren-IP (Electric)
1112 West Anthony Drive
P.O. Box 17070
Urbana, IL 61803-7070
(217) 383-7304

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

LIST OF STANDARDS

STANDARD NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701006-02	TRAFFIC CONTROL
701301-02	TRAFFIC CONTROL
701701-05	TRAFFIC CONTROL
701901	TRAFFIC CONTROL DEVICES

INDEX OF SHEETS

1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS & STANDARDS IN THE PLANS
3	SUMMARY OF QUANTITIES
4	LIGHTING PLAN SHEET
5	BILL OF MATERIALS, DETAILS
6-9	DETAIL SHEETS

FILE NAME = c:\projects\4502007 (v8)\4735\plan.dgn	USER NAME = colliebw	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GEN. NOTES, INDEX, STANDARDS	F.A.P. RTE. 323	SECTION 149L	COUNTY EDGAR	TOTAL SHEETS 9	SHEET NO. 2	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -	SCALE: _____			SHEET NO. ____ OF ____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 70656			
PLOT DATE = 10/25/2007	DATE -	REVISED -	FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT								