

F.A. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR. *	**	35	11

* D5 CRACK & JOINT SEAL 2008-1
 ** DEWITT/PIATT/MCLEAN

SUMMARY OF QUANTITIES

LOCATION OF WORK:

VARIOUS ROUTES

D5 CRACK AND JOINT SEAL 2008-1
 DEWITT, PIATT & MCLEAN COUNTIES

LOCATION #1
 DEWITT CO.
 RURAL
 100% STATE
 ROUT & SEAL
 F000

LOCATION #2
 PIATT CO.
 RURAL
 100% STATE
 ROUT & SEAL
 F000

LOCATION #3
 MCLEAN CO.
 URBAN
 100% STATE
 ROUT & SEAL
 F000

LOCATION #4, #5 & #6
 MCLEAN CO.
 RURAL
 100% STATE
 ROUT & SEAL
 F000

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
45100100	CRACK ROUTING (PAVEMENT)	FOOT	430,899.0	21,201.0	70,487.0	104,079.0	235,132.0
45100200	CRACK FILLING	POUND	172,360.0	8,480.0	28,195.0	41,632.0	94,053.0
67100100	MOBILIZATION	L SUM	1.0	0.1	0.2	0.2	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.1	0.3	0.0	0.6
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	0.0	0.0	1.0	0.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.0	0.0	1.0	0.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,989.0	0.0	0.0	9,989.0	0.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	11,870.0	0.0	0.0	11,870.0	0.0
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	13,818.0	0.0	0.0	13,818.0	0.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	83,458.0	4,009.0	23,713.0	0.0	55,736.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	11.0	0.0	0.0	11.0	0.0

* SPECIALTY ITEM

PLOT DATE = 08/23/07
 FILE NAME = \\c:\pwworkspace\70658\70658.dgn
 PLOT SCALE = 43.2522 / 1
 USER NAME = collinsb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 ROUTE VARIOUS
 SECTION D5 CRACK & JOINT SEAL 2008-1
 DEWITT, PIATT & MCLEAN COUNTIES
 SCALE: N/A
 DATE: 08/23/07
 DRAWN BY: JRP
 CHECKED BY: