

SCHEDULE OF QUANTITIES

CLASS B PATCHING

BEGINNING STATION	ENDING STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
						TYPE I 10.0" (sq. yd)	TYPE II 10.0" (sq. yd)	TYPE III 10.0" (sq. yd)	TYPE IV 10.0" (sq. yd)				
						171+86.00	169+90.00	SOUTHBOUND	DL				
171+86.00	169+90.00	SOUTHBOUND	PL	196	12	0.0	0.0	0.0	261.3	0	196.0	0	261.3
SUB-TOTALS						0.0 (sq. yd)	0.0 (sq. yd)	0.0 (sq. yd)	522.7 (sq. yd)	0.0 (each)	588.0 (ft)	98.0 (each)	522.7 (sq. yd)

BEGINNING STATION	ENDING STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
						TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV * (sq. yd)				
						169+90.00	169+68.00	SOUTHBOUND	DL				
169+90.00	169+68.00	SOUTHBOUND	PL	22	12	0.0	0.0	0.0	29.3	10	46.0	0	29.3
172+37.00	171+86.00	SOUTHBOUND	DL	51	12	0.0	0.0	0.0	68.0	10	114.0	26	68.0
172+37.00	171+86.00	SOUTHBOUND	PL	51	12	0.0	0.0	0.0	68.0	10	63.0	0	68.0
SUB-TOTALS						0.0 (sq. yd)	0.0 (sq. yd)	0.0 (sq. yd)	194.7 (sq. yd)	40.0 (each)	291.0 (ft)	37.0 (each)	194.7 (sq. yd)

PATCH AREA		DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
TYPE IV 10" (sq. yd)	TYPE IV * (sq. yd)				
523.0 (sq. yd)	195.0 (sq. yd)				
FINAL TOTALS					

* CLASS B PATCHES, TYPE IV ARE VARIABLE DEPTH - SEE DETAIL