

SCHEDULE OF QUANTITIES

RAISED REFLECTIVE PAVEMENT MARKER - 78100100

ONE WAY CRYSTAL MARKER *

STATION	TO STATION	EACH
172+37.00	169+68.00	6.0

TOTAL 6.0 EACH

* USE DOUBLE LANE LINE MARKERS

POLYUREA PAVEMENT MARKING TYPE II - LINE 4" - 78008310

WHITE - CENTERLINE STRIPE

STATION	TO STATION	FOOT
172+37.00	169+68.00	70.0

WHITE - EDGE LINE STRIPE

STATION	TO STATION	FOOT
172+37.00	169+68.00	269.0

YELLOW - EDGE LINE STRIPE

STATION	TO STATION	FOOT
172+37.00	169+68.00	269.0

TOTAL 609.0 FOOT

FILE NAME = c:\projects\d505707 (v8)\70677text.dgn	USER NAME = collierbw	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 51	SECTION 05_PAICHING_2008-3	COUNTY CHAMPAIGN	TOTAL SHEETS 10	SHEET NO. 7
PLOT SCALE = 200.0000' / IN.	PLOT DATE = 10/22/2007	DRAWN - ---	CHECKED - ---	REVISED - ---	REVISED - ---	SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 10677 FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT		