

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNITS	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				1000-2A	SFTY-4A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
X0320887	POLYMER CONCRETE	CU FT	7.5				7.5		
X0321744	SILICONE JOINT SEALER, 2"	FOOT	105				105		
* X0322011	LIGHT POLE REMOVE AND RE-ERECT	EACH	17	17					
X0322066	PROTECTIVE SHIELD (PERMANENT)	SO YD	178			178			
X0322279	OUTLET MARKER	EACH	474	474					
X0322729	MATERIAL TRANSFER DEVICE	TON	69,508	69,508					
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	1,042	1,042					
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	28	28					
* X0323016	ELECTRIC CABLE IN CONDUIT * 14-7STRAND XHHW XLP-600V	FOOT	44	44					
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	106				106		
* X0323857	EXISTING LIGHT POLE FOUNDATION ADJUSTMENT	EACH	17	17					
Δ X0325893	CLEAN EXISTING END SECTION	EACH	1	1					
X0324952	DETOUR SIGNING	L SUM	1	1					
* X0325231	CABLE GUARD MARKER	EACH	565		565				
* X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	22,305		22,305				
* X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	8		8				
* X0325606	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	2		2				
X0358300	REMOVE AND RELAY END SECTIONS	EACH	2	2					
X0976500	END SECTIONS TO BE REMOVED	EACH	5	5					
Δ X2503000	MAINTENANCE MOWING	ACRE	184	184					
X6013820	PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL	EACH	47		47				
X7240205	REMOVE SIGN COMPLETE	EACH	63	63					
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	239,497	239,497					
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	922	922					
Δ Z0010615	CLEANING EXISTING INLETS	EACH	4	4					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Δ Z0014800	CULVERT TO BE CLEANED	FOOT	446	446					
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	26				1	25	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	13				13		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	111				55	56	
Z0017100	DOWEL BARS	EACH	5,906	5,888			18		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW).	EACH	6				1	1	4
	TEST LEVEL 3								

PLOT DATE : 01-23-2007 08:51:02AM  
 FILE NAME : c:\p1\m1\6652822\sumqty.dgn  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : jaughlin1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_

Δ NON-PARTICIPATING      \* SPECIALTY ITEMS

Rev.